

NOTICE TO ALL PREQUALIFIED CONTRACTORS

BEGINNING WITH THE APRIL 22, 2004 BID LETTING THE OKLAHOMA DEPARTMENT OF TRANSPORTATION WILL START ACCEPTING BIDS OVER THE INTERNET THROUGH 'BID EXPRESS'.

TO SET UP AN ACCOUNT WITH BID EXPRESS, CONTRACTORS SHOULD CONTACT INFO TECH, INC. AT (352)381-4400 AND ASK FOR BIX EXPRESS SUPPORT DESK.

Notice

Electronic bid packages are available for the [April 22, 2004](#) Letting. Instructions for using the electronic bidding system (EBS) are available from the Office Engineer's office. The printed bid sheets created from the EBS system must be placed in front of the bid item pages in the bidding proposal and will be turned in with the bid documents along with the proper disk. They should be placed and attached there without detaching the original proposal. (The paper copy of the bid items is the official bid document.) Please remember that you must use the electronic bidding system (EBS) when bidding projects in the highway Letting. Failure to use the EBS system could mean possible rejection of bids. Plans and proposals should be ready for sale on [March 29, 2004](#).

The direct line to the ODOT order desk is 522-3474. Please use this number when ordering plans and proposals. If ordering plans only please call the Reproduction Branch at 521-2586.

A Pre-Bid Conference will be held at [10:00 a.m.](#) on [April 9, 2004](#) concerning this [April](#) Bid Opening at the Oklahoma Department of Transportation (ODOT) Commission Room. Please review plans and proposals and send your comments and questions to the Office Engineer Division (attn: Masoud Pajoh or Jack Stewart) as early as possible at Fax: (405) 522-0972 or phone: (405) 521-2625. This will help both ODOT and Contractor.

All proposals not mailed must be turned into the Reproduction office off the main lobby of the ODOT building until 30 minutes before the Opening. From 30 minutes before the Bid Opening until the time of the Bid Opening, bid proposals must be turned in directly to the ODOT Commission Room on the east side of the lobby.

Please write the call order number of the jobs you are bidding electronically on the disk label of the original disk. Be sure to save your work and any revisions you receive to your original disk and submit that disk with your bid.

Until further notice all projects which include a pay item for Contractors Quality Control (Item 643) will require the bidder to bid a minimum amount for that item.

This minimum will be specified at the end of the Special Provision 648-1QA(a)99, Payment for Contractor's Quality Control. You may increase this amount as necessary to cover the estimated Quality Control expenses.

Failure to include at least this amount will be considered grounds for rejection of Contractor's bid as nonresponsive.

Note:

ODOT will no longer allow DBE credit towards project DBE goals for the supplying of liquid asphalt cement or other bituminous materials.

**Long Form and Short Form Notices, Bid Tabs and Awards,
can be accessed on ODOT's Web site
<http://www.okladot.state.ok.us/>**

Reminder

The low bidder must submit to the Office Engineer Division written confirmation from the DBE that it is participating in the contract as provided in the prime contractor's commitment. This may be submitted with the bid or not later than the Department's close of business on the Wednesday following the bid opening. Otherwise the bid shall be considered nonresponsive and shall be rejected by the Department.

Reminder

*Please be sure that bid bonds are stapled to the **back** of the proposal as instructed on the cover sheet of all proposals.*

Do not disassemble the bidding proposal in any way.

Note:

The **Order Form** included in this Short Form Notice may be used to order plans and proposals for this letting.

Please check off the proposal(s) in which you are interested and fax to:

405-522-0972 attention Linda Stoltz.

The Bid Opening can be heard from the AGC website which is:

<http://www.okagchwy.com/>

DATE : March 23, 2004 OKLAHOMA DEPARTMENT OF TRANSPORTATION
NOTICE TO CONTRACTORS -- April 22, 2004

LNTCNCA
LETTING

LNTCNCA-D

SEALED PROPOSALS SENT BY REGISTERED MAIL WILL BE RECEIVED THROUGH THE ODOT REPRODUCTION BRANCH UNTIL 30 MINUTES PRIOR TO THE SCHEDULED BID OPENING. FROM 30 MINUTES PRIOR TO THE BID OPENING UNTIL THE TIME OF THE BID OPENING, BID PROPOSALS MUST BE TURNED IN DIRECTLY TO THE ODOT COMMISSION ROOM LOCATED ON THE EAST SIDE OF THE LOBBY. THE SCHEDULED BID OPENING OF 10:30 A.M. April 22, 2004 , FOR THE WORK LISTED BELOW.

NO PROPOSAL FOR CONSTRUCTION OR MAINTENANCE WORK OF THE DEPARTMENT WILL BE ISSUED TO ANY CONTRACTOR AFTER 10:30 A.M. ON THE WORKING DAY PRECEDING OPENING OF BIDS FOR ANY CONTRACT.

EACH SEPARATE PROPOSAL SHALL BE ACCOMPANIED BY A CERTIFIED OR CASHIER'S CHECK OR BID BOND EQUAL TO 5% OF THE BID MADE PAYABLE TO THE STATE OF OKLAHOMA, DEPARTMENT OF TRANSPORTATION, AS A PROPOSAL GUARANTY. PROPOSAL CHECKS WILL BE HELD OR RETURNED BY THE DEPARTMENT AS PER SECTION 103.04 OF THE STATE STANDARD SPECIFICATIONS.

THIS WORK WILL BE DONE UNDER THE OKLAHOMA DEPARTMENT OF TRANSPORTATION COMMISSION'S APPLICABLE SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.

THE MINIMUM WAGE TO BE PAID LABORERS AND MECHANICS EMPLOYED ON THIS PROJECT WILL BE INCLUDED IN THE PROPOSAL.

PROPOSALS MUST BE PREPARED AS DIRECTED BY THE STATE STANDARD SPECIFICATIONS.

THIS WORK WILL BE DONE UNDER THE OKLAHOMA DEPARTMENT OF TRANSPORTATION COMMISSION'S APPLICABLE SPECIFICATIONS FOR HIGHWAY CONSTRUCTION AS DEPICTED ON THE LOWER LEFT CORNER OF THE PLAN'S TITLE SHEET.

PLANS, FORMS OF PROPOSALS, CONTRACTS AND SPECIFICATIONS MAY BE EXAMINED AT THE DIVISION HEADQUARTERS IN THE DIVISION THE WORK IS TO BE PERFORMED OR AT THE OKLAHOMA DEPARTMENT OF TRANSPORTATION OFFICE ENGINEER'S DIVISION IN OKLAHOMA CITY, OKLAHOMA.

PLANS AND PROPOSAL FORMS MAY BE ORDERED FROM JACK STEWART, DIVISION ENGINEER, OKLAHOMA DEPARTMENT OF TRANSPORTATION BUILDING, 200 N.E. 21ST STREET, OKLAHOMA CITY, OKLAHOMA 73105. COST OF BIDDING DOCUMENTS ARE \$25.00 + tax FOR EACH BIDDING PROPOSAL. STATE STANDARD SPECIFICATION 1988 EDITION (RED BOOK) AND 1991 SUPPLEMENT MAY BE PURCHASED FOR \$8.00 + tax, OR 1996 METRIC STANDARD SPECIFICATION \$27.00 + TAX, OR 1999 METRIC AND ENGLISH STANDARD SPECIFICATION \$55.00 + TAX. (OKLAHOMA TAX IS 8.375%). MAKE CHECKS PAYABLE TO OKLAHOMA DEPARTMENT OF TRANSPORTATION.

NO REFUNDS WILL BE MADE FOR BIDDING DOCUMENTS OR SPECIFICATION BOOKS PURCHASED BY PROSPECTIVE BIDDERS.

UPON AWARD OF CONTRACT TO A SUCCESSFUL BIDDER, THE CONTRACT WILL BE COMPLETELY AND CORRECTLY EXECUTED BY THE CONTRACTOR AND RETURNED TO THE DEPARTMENT WITHIN TEN (10) WORKING DAYS FROM THE DATE OF AWARD. THE DEPARTMENT WILL HAVE FOURTEEN (14) WORKING DAYS FROM THE DATE OF AWARD TO COMPLETE ITS EXECUTION OF THE CONTRACT.

THE OKLAHOMA DEPARTMENT OF TRANSPORTATION HEREBY NOTIFIES ALL BIDDERS THAT IT WILL AFFIRMATIVELY INSURE THAT IN ANY CONTRACT ENTERED INTO PURSUANT TO THIS ADVERTISEMENT, DISADVANTAGED BUSINESS ENTERPRISES WILL BE AFFORDED FULL OPPORTUNITY TO SUBMIT BIDS IN RESPONSE TO THIS INVITATION AND WILL NOT BE DISCRIMINATED AGAINST ON THE GROUNDS OF RACE, COLOR, SEX, RELIGION, NATIONAL ORIGIN, OR DISABILITY IN CONSIDERATION FOR AN AWARD.

BIDDERS ARE HEREBY NOTIFIED THAT ALL BIDS ARE LIKELY TO BE REJECTED IF THE LOWEST RESPONSIVE BID RECEIVED EXCEEDS THE ENGINEER'S ESTIMATE BY MORE THAN SEVEN (7) PERCENT. IN THE EVENT ALL BIDS ARE REJECTED FOR THIS REASON, THIS PROJECT MAY BE DEFERRED FOR READVERTISING FOR BIDS UNTIL A MORE COMPETITIVE SITUATION EXISTS.

DESCRIPTION OF WORK AND LOCATION OF PROJECT:

FEDERAL PROJECT

CALL ORDER : 020
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : BLAINE

GREER

CONTRACT ID : 040144
 PCN : 2131704
 PROJECTS : STPY-120H(95)
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 9.75
 CALENDAR DAYS : 30
 RES. ENG.:
 LIQ. DAM.: \$ 300

CONTRACT DESCRIPTION:
 BRIDGE WATERPROOF SEAL VARIOUS LOCATIONS IN DIVISION V.
 PROJECT LENGTH = 0.00 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	X031-BRIDGE A,B,C,D,E,F,G,H,I		
515 (B) 6014	WATER REPELLENT (PERFORMANCE TESTED)	12,447.000	SY
523 (A) 6550	(SP) SEALER CRACK PREPARATION	3,730.000	LF
523 (B) 6560	(SP) SEALER RESIN	25.100	GAL
641 1399	MOBILIZATION	1.000	LSUM
876 (C) 8482	(PL) TRUCK MOUNTED ATTENUATOR	20.000	SD
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 040
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : BRYAN

CONTRACT ID : 040145
 PCN : 1701904
 PROJECTS : STP-107B(013) UR
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 37.93
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 700

CONTRACT DESCRIPTION:
 INTERSECTION MOD & TRAFFIC SIGNALS DURANT: UNIVERSITY BLVD,
 AT WASHINGTON ST. AND RADIO ROAD. PROJECT LENGTH = 0.601 KM
 FLEXIBLE ESALS = 0.1 MILLION ASPHALT GRADE = 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001 ROADWAY				
201	M0102	CLEARING AND GRUBBING	1.000	LSUM
202(A)	M0183	UNCLASSIFIED EXCAVATION	4,812.000	M3
205	M4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	M2802	TEMPORARY SILT FENCE	200.000	M
227	M0100	TEMPORARY SILT DIKE	50.000	M
230(A)	M2806	SOLID SLAB SODDING	8,000.000	M2
233(A)	M2817	VEGETATIVE MULCHING	0.800	HA
326(B)	M4210	(SP)LIME	287.800	T
326(F)	M4250	(SP)LIME STABILIZED SUBGRADE	10,567.700	M2
403(E)	M0225	TRAFFIC BOUND SURFACE COURSE TYPE E	200.000	T
408	M5774	PRIME COAT	10,145.700	L
411(S3)	M5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	4,186.000	T
411(S4)	M5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	487.500	T
414(A1)	M5753	200MM P.C. DOWEL JOINTED CONCRETE PAVE.	13,252.000	M2
414(B)	M0290	200MM H.E.S. CONCRETE PAVEMENT	250.000	M2
501(A)	M0313	STRUCTURAL EXCAVATION UNCLASSIFIED	5.000	M3
501(B)	M1307	SUBSTRUCTURE EXCAVATION COMMON	298.000	M3
509(B)	M0321	CLASS A CONCRETE	26.000	M3
509(D)	M0325	CLASS C CONCRETE	10.000	M3
511(A)	M0332	REINFORCING STEEL	2,385.000	KG
609(A)	M0380	CONC.CURB(200MM BARRIER-INTEGRAL)	2,072.000	M
609(B)	M1526	800MM COMB.CRB.& GUT.(200MM BAR.)	60.000	M
610(A)	M0602	100MM CONCRETE SIDEWALK	2,656.000	M2
610(B)	M0399	150MM CONCRETE DRIVEWAY (H.E.S.)	1,442.000	M2
611(E)	M5112	INLET CICI DES. 2 (STD)	2.000	EA
611(G)	M4488	INLET FRM&GRT (SSIF-FRM,CIG-GRT-VG-F)	4.000	EA
611(K)	M4488	CAST IRON CURB INLETS	4.000	EA
613(B)	M0405	450MM R.C.PIPE CLASS III	13.000	M
619(B)	M0291	REMOVAL OF HEADWALL	4.000	EA
619(B)	M4727	REMOVAL OF CONCRETE PAVEMENT	2,336.000	M2
619(B)	M4728	REMOVAL OF ASPHALT PAVEMENT	9,014.000	M2
619(C)	M0924	SAWING PAVEMENT	1,420.000	M
629(A)	M4958	MAILBOX INSTALLATION-SINGLE	4.000	EA
629(C)	M4960	MAILBOX	4.000	EA
640	M1398	FIELD OFFICE	1.000	EA
641	M1552	MOBILIZATION	1.000	LSUM

CALL ORDER : 040
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : BRYAN

CONTRACT ID : 040145
 PCN : 1701904
 PROJECTS : STP-107B(013) UR
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 37.93
 CALENDAR DAYS : 90
 RES. ENG. :
 LIQ. DAM. : \$ 700

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	TRAFFIC		
802 (B) M8334	25MM PVC SCH.40 P.C.TR.	58.000	M
802 (B) M8338	38MM PVC SCH.40 P.C.TR.	467.700	M
802 (B) M8342	50MM PVC SCH.40 P.C.TR.	26.000	M
802 (B) M8346	75MM PVC SCH.40 P.C.TR.	167.800	M
803 M8065	PULL BOX(SIZE I)	6.000	EA
803 M8066	PULL BOX(SIZE II)	2.000	EA
803 M8067	PULL BOX(SIZE III)	8.000	EA
804 (A) M2915	STRUCTURAL CONCRETE	17.100	M3
804 (B) M2916	REINFORCING STEEL	1,465.700	KG
806 (A) M8762	9.7M MHP 7.6M TS & 4.6M LMA(G.STL.)	1.000	EA
806 (A) M8763	9.7M MHP 7.6M TS & 6.1M LMA(G.STL.)	1.000	EA
806 (A) M8774	9.7M MHP 9.1M TS & 6.1M LMA(G.STL.)	2.000	EA
806 (A) M8786	9.7M MHP 10.7M TS & 6.1M LMA(G.STL.)	3.000	EA
806 (A) M8798	9.7M MHP 12.2M TS & 6.1M LMA(G.STL.)	1.000	EA
809 (A) M8090	(PL)ROADWAY LUMINAIRE	8.000	EA
811 M8040	1/C NO.6 ELECT.COND.	200.000	M
811 M8044	1/C NO.10 ELECT.COND.	759.800	M
825 M8550	VEH.ACT.SOL.ST.TRAF.SIG.CON.ASM	2.000	EA
828 (B) M8138	LOOP DETECTOR WIRE	2,086.000	M
830 M8000	PEDESTRIAN PUSH BUTTON	16.000	EA
831 M8231	1WAY3SEC.ADJ.SIG.HD.S-6	16.000	EA
831 M8286	1WAY5SEC.ADJ.SIG.HD.S-19	8.000	EA
831 M8295	1WAY2SEC.ADJ.SIG.HD.S-20	16.000	EA
833 M3038	127MM BACKPLATE(300MM HDS) (B-2)	24.000	EA
834 (A) M8207	5/C TRAF.SIG.EL.CABLE	470.000	M
834 (A) M8208	7/C TRAF.SIG.EL.CABLE	200.000	M
834 (A) M8210	12/C TRAF.SIG.EL.CABLE	25.000	M
834 (A) M8211	15/C TRAF.SIG.EL.CABLE	80.000	M
834 (A) M8212	18/C TRAF.SIG.EL.CABLE	30.000	M
834 (B) M8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	1,010.000	M
840 (B) M8593	(PL)E.P.S. OPTICAL DETECTOR	8.000	EA
840 (C) M8594	(PL)E.P.S. OPTICAL DETECTOR CABLE	700.000	M
840 (D) M8595	(PL)E.P.S. 2 CHANNEL PHASE SELECTOR	4.000	EA
850 (A) M8110	SHEET ALUMINUM SIGNS	7.240	M2
850 (C) M8118	MAST ARM MOUNTED SIGNS(ALUM.)	15.600	M2
851 (C) M8327	57MM SQUARE TUBE POST	63.000	M
855 (A) M8812	TRAFFIC STRIPE(PLASTIC)(100MM WIDE)	5,912.700	M
855 (B) M8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	19.000	EA
855 (B) M8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	9.000	EA
856 (A) M8839	CONSTR.TRAFF.STR.(PAINT)(100MM WIDE)	800.000	M
856 (C) M8851	REM.PAVEMENT MARKING TAPE(100MM WIDE)	200.000	M
856 (G) M8887	(PL)CONST.ZONE PAV.MKRS(FLEX TAB) TYP.2-1	500.000	EA
859 (A) M8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	200.000	M
880 (J) M8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890 (A) M8724	(PL)REMOVAL OF EXISTING SIGNS	12.000	EA

CALL ORDER : 040
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : BRYAN

CONTRACT ID : 040145
 PCN : 1701904
 PROJECTS : STP-107B(013) UR
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 37.93
 CALENDAR DAYS : 90
 RES. ENG. :
 LIQ. DAM. : \$ 700

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	STAKING		
642 M0098	STAKING	1.000	LSUM
SECTION NO. 0004	NON-PARTICIPATING (CITY)		
612 (A) M0641	MANHOLES ADJUST TO GRADE	5.000	EA
612 (G) M0647	VALVE BOXES ADJUST TO GRADE	3.000	EA
612 (H) M0648	METER BOXES ADJUST TO GRADE	6.000	EA
612 (J) M0650	FIRE HYDRANT RESET	2.000	EA

CALL ORDER : 060
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : KAY
 LOGAN

KINGFISHER
 PAYNE

CONTRACT ID : 040146
 PCN : 1965605
 PROJECTS : STPY-152H(52)
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 16.26
 CALENDAR DAYS : 60
 RES. ENG. :
 LIQ. DAM. : \$ 500

CONTRACT DESCRIPTION:
 BRIDGE WATERPROOF SEAL VARIOUS LOCATIONS IN DIVISION IV.
 PROJECT LENGTH = 0.00

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	X031-BRIDGE A,B,C,D,E,F,G,H,I,J,K,L,M,N,O		
515 (B) 6014	WATER REPELLENT (PERFORMANCE TESTED)	21,656.000	SY
523 (A) 6550	(SP) SEALER CRACK PREPARATION	11,624.000	LF
523 (B) 6560	(SP) SEALER RESIN	82.800	GAL
641 1399	MOBILIZATION	1.000	LSUM
876 (C) 8482	(PL) TRUCK MOUNTED ATTENUATOR	54.000	SD
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 065
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : PAYNE
 LOGAN

KAY
 NOBLE

CONTRACT ID : 040118
 PCN : 2119604M
 PROJECTS : BPMIY-NBIP(342) 3B
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 10.84
 CALENDAR DAYS : 120
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE PAINTING VARIOUS LOCATIONS IN DIVISION IV. LENGTH =
 0.00 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE 'G' BPMIY-NBIP(342)3B		
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
SECTION NO. 0002	BRIDGE 'A' BHFY-NBIP(317)		
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
641 1399	MOBILIZATION	1.000	LSUM
SECTION NO. 0003	BRIDGE 'B' BRFY-NBIP(318)		
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
SECTION NO. 0004	BRIDGE 'C' BHFY-NBIP(319)		
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
SECTION NO. 0005	BRIDGE 'D' BHFY-NBIP(322)		
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
SECTION NO. 0006	BRIDGE 'E' BHFY-NBIP(324)		
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
SECTION NO. 0007	BRIDGE 'F' BPMY-NBIP(341)3B		
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
SECTION NO. 0008	TRAFFIC -BPMIY-NBIP(342)3B		
876(C) 8482	(PL)TRUCK MOUNTED ATTENUATOR	15.000	SD
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	15.000	SD

FEDERAL PROJECT

CALL ORDER : 065
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : PAYNE
 LOGAN

KAY
 NOBLE

CONTRACT ID : 040118
 PCN : 2119604M
 PROJECTS : BPMIY-NBIP(342) 3B
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 10.84
 CALENDAR DAYS : 120
 RES. ENG.:
 LIQ. DAM.: \$ 500

SECTION NO. 0009	TRAFFIC - BHFY-NBIP(317)		
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0010	TRAFFIC - BRFY-NBIP(318)		
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0011	TRAFFIC - BHFY-NBIP(319)		
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0012	TRAFFIC - BHFY-NBIP(322)		
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0013	TRAFFIC - BHFY-NBIP(324)		
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0014	TRAFFIC - BPMY-NBIP(341) 3B		
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 100
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : CHOCTAW

CONTRACT ID : 040148
 PCN : 1500204
 PROJECTS : ACNHY-22N(008)GB
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 39.02
 CALENDAR DAYS : 365
 RES. ENG.:
 LIQ. DAM.: \$ 1000

CONTRACT DESCRIPTION:
 GRADE , DRAIN AND SURFACE(ASPHALT) US-70; FROM SH-93,
 EXTEND EAST. PROJECT LENGTH = 2.983 MILES FLEXIBLE ESALS =
 14.76 MILLION ASPHALT GRADE = PG 64-22 OK, PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (A)	0183 UNCLASSIFIED EXCAVATION	157,449.190	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	328.080	LF
223	2801 TEMPORARY SILT FENCE	2,296.590	LF
224	2803 TEMPORARY SEDIMENT FILTER	7.000	EA
226	2805 TEMPORARY SEDIMENT REMOVAL	65.400	CY
227	0100 TEMPORARY SILT DIKE	984.250	LF
229	4318 DITCH LINER PROTECTION	1,312.340	LF
230 (A)	2806 SOLID SLAB SODDING	12,774.370	SY
230 (B)	2807 MULCH SODDING	80,502.090	SY
230 (F)	2812 WATERING	3,709.380	MGAL
232 (B)	2814 SEEDING METHOD B	74.870	AC
233 (A)	2817 VEGETATIVE MULCHING	74.870	AC
234 (A)	2824 FERTILIZING (10-20-10)	13.670	TON
234 (A)	4406 FERTILIZING (0-46-0)	3.640	TON
235 (A)	0100 (PL)ROCK FILTER DAM, TYPE 1	52.320	CY
241	2832 MOWING	46.950	AC
303	0192 AGGREGATE BASE	14,250.120	CY
325	5271 SEPARATOR FABRIC	82,697.000	SY
326 (B)	4210 (SP)LIME	2,523.190	TON
326 (F)	4250 (SP)LIME STABILIZED SUBGRADE	27,913.210	SY
403 (A)	0217 TRAFFIC BOUND SURFACE COURSE TYPE A	551.160	TON
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	16,286.130	TON
407	0250 TACK COAT	13,391.240	GAL
408	5774 PRIME COAT	35,211.260	GAL
411 (S2)	5930 (SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	24,452.570	TON
411 (S3)	5935 (SP)ASPH.CONC.,TYPE S3(PG 76-28 OK)	10,462.040	TON
411 (S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	3,821.710	TON
411 (S4)	5950 (SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	6,983.140	TON
411 (S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	2,358.950	TON
417	5267 COLD MILLING PAVEMENT	5,640.290	SY
420 (A)	4242 FABRIC REINFORCEMENT	812.080	SY
420 (B)	4268 BITUMINOUS BINDER	197.340	GAL
501 (A)	0313 STRUCTURAL EXCAVATION UNCLASSIFIED	566.360	CY
509 (B)	0321 CLASS A CONCRETE	1,362.330	CY
509 (C)	0322 CLASS A CONCRETE FOR SMALL STRUCTURES	0.820	CY

CALL ORDER : 100
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : CHOCTAW

CONTRACT ID : 040148
 PCN : 1500204
 PROJECTS : ACNHY-22N(008)GB
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 39.02
 CALENDAR DAYS : 365
 RES. ENG.:
 LIQ. DAM.: \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
509 (D) 0325	CLASS C CONCRETE	254.280	CY
511 (A) 0332	REINFORCING STEEL	213,211.260	LB
601A-1 0536	TYPE I-A PLAIN RIPRAP	635.040	TON
611 (D) 4215	MANHOLE FRAME & COVER	1.000	EA
611 (E) 6000	INLET (SMD-TYPE 1)	7.000	EA
611 (J) 0487	JUNCTION BOXES	35.320	CF
613 (B) 0491	18" R.C.PIPE CLASS III	485.560	LF
613 (B) 0492	24" R.C.PIPE CLASS III	118.110	LF
613 (B) 4410	28 1/2" X 18" R.C.PIPE CLASS A-III	242.780	LF
613 (CC) 7186	TYPE A4 CULVERT END TREATMENT	10.000	EA
613 (CC) 7187	TYPE B4 CULVERT END TREATMENT	16.000	EA
613 (CC) 7191	TYPE AA4 CULVERT END TREATMENT	2.000	EA
613 (D) 0689	18" CORR. GALV. STEEL PIPE	731.630	LF
613 (D) 0690	24" CORR. GALV. STEEL PIPE	370.740	LF
613 (D) 4527	21" X 15" CORR. GALV. STEEL PIPE ARCH	85.300	LF
613 (M) 4516	28" X 20" PREFAB. CULVERT END SEC., ARCH	1.000	EA
613 (M) 5726	18" PREFAB. CULVERT END SEC., ROUND	1.000	EA
613 (M) 5730	24" PREFAB. CULVERT END SEC., ROUND	4.000	EA
613 (P) 1092	8" PERFORATED PIPE UNDERDRAIN ROUND	1,125.330	LF
613 (Q) 1097	8" NON-PERF.PIPE UNDERDRAIN RND.	374.020	LF
613 (R) 1100	PIPE UNDERDRAIN COVER MAT'L.	337.460	CY
613 (S) 1180	TRENCH EXCAVATION	689.320	CY
613 (T) 1181	STANDARD BEDDING MATERIAL	214.510	CY
619 (A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619 (B) 0291	REMOVAL OF HEADWALL	9.000	EA
624 (A) 4281	FENCE-STYLE WWF	334.650	LF
624 (C) 4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	11,273.520	LF
624 (D) 4288	FENCE-STYLE CLF (4'HIGH, CLASS A)	134.510	LF
629 (A) 4958	MAILBOX INSTALLATION-SINGLE	5.000	EA
629 (C) 4960	MAILBOX	5.000	EA
629 (D) 4961	REMOVAL OF MAILBOX INSTALLATION	5.000	EA
640 1426	FIELD OFFICE	1.000	EA
641 1552	MOBILIZATION	1.000	LSUM
643 0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
653 (C) 5946	OUTLET LATERAL HEADWALL	5.000	EA
SECTION NO. 0002 Y000-TRAFFIC CONTROL			
850 (A) 8110	SHEET ALUMINUM SIGNS	329.480	SF
851 (C) 8327	2 1/4" SQUARE TUBE POST	658.760	LF
851 (C) 8330	2 1/2" SQUARE TUBE POST	59.970	LF
855 (A) 8812	TRAFFIC STRIPE (PLASTIC) (4" WIDE)	74,970.000	LF
855 (B) 8818	TRAFFIC STRIPE (PLASTIC) (ARROWS)	2.000	EA

CALL ORDER : 100
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : CHOCTAW

CONTRACT ID : 040148
 PCN : 1500204
 PROJECTS : ACNHY-22N(008)GB
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 39.02
 CALENDAR DAYS : 365
 RES. ENG. :
 LIQ. DAM. : \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002 Y000-TRAFFIC CONTROL			
855 (B) 8821	TRAFFIC STRIPE (PLASTIC) (WORDS)	1.000	EA
856 (A) 8839	CONSTRUCTION TRAFF. STR. (PAINT) (4" WIDE)	51,706.000	LF
859 (A) 8006	PAVEMENT MRKNG. REMOVAL (TRAF. STRP)	51,706.000	LF
880 (C) 8850	PERMANENT BARRICADE UNIT	3.000	EA
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING			
642 0098	STAKING	1.000	LSUM

CALL ORDER : 120
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : POTTAWATOMIE CLEVELAND

CONTRACT ID : 040149
 PCN : 0634604
 PROJECTS : BRFY-14B(321)
 DBE GOALS : 4.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 74.78
 CALENDAR DAYS : 310
 RES. ENG.:
 LIQ. DAM.: \$ 1000

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES SH-9: AT PECAN CREEK JUST W. OF THE
 CLEVELAND/POTTAWATOMIE COUNTY LINE. PROJECT LENGTH = 0.644
 KM FLEXIBLE ESALS = 4.63 MILLION ASPHALT GRADE = PG 64-22
 OK, PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (A)	0183 UNCLASSIFIED EXCAVATION	24,064.580	CY
202 (C)	0184 UNCLASSIFIED BORROW	72,067.070	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	262.470	LF
223	2801 TEMPORARY SILT FENCE	3,863.780	LF
225	2804 TEMPORARY SEDIMENT BASIN	4.000	EA
226	2805 TEMPORARY SEDIMENT REMOVAL	13.080	CY
227	0100 TEMPORARY SILT DIKE	229.660	LF
230 (A)	2806 SOLID SLAB SODDING	23,801.060	SY
230 (F)	2812 WATERING	946.260	MGAL
232 (B)	2814 SEEDING METHOD B	24.610	AC
233 (A)	2817 VEGETATIVE MULCHING	24.610	AC
234 (A)	2824 FERTILIZING (10-20-10)	4.780	TON
234 (A)	4406 FERTILIZING (0-46-0)	1.580	TON
241	2832 MOWING	20.710	AC
326 (A)	4200 (SP)FLY ASH	594.570	TON
326 (B)	4210 (SP)LIME	69.640	TON
326 (E)	4240 (SP)CEMENTITIOUS STABILIZED SUBGRADE	11,186.350	SY
326 (F)	4250 (SP)LIME STABILIZED SUBGRADE	2,237.270	SY
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	708.880	TON
407	0250 TACK COAT	3,020.860	GAL
408	5774 PRIME COAT	3,593.350	GAL
411 (S3)	5940 (SP)ASPH.CONC.,TYPE S3(PG 70-28 OK)	1,539.400	TON
411 (S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	5,256.420	TON
411 (S4)	5955 (SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	764.900	TON
411 (S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	1,223.720	TON
509 (D)	0325 CLASS C CONCRETE	10.000	CY
601 (A)	0297 TYPE I PLAIN RIPRAP	50.000	TON
609 (D)	0398 BITUMINOUS CURBING	1,083.820	LF
613 (CC)	7196 TYPE A6 CULVERT END TREATMENT	4.000	EA
613 (CC)	7198 TYPE C6 CULVERT END TREATMENT	2.000	EA
613 (CC)	7199 TYPE D6 CULVERT END TREATMENT	2.000	EA
613 (D)	0689 18" CORR. GALV. STEEL PIPE	366.470	LF
613 (D)	0690 24" CORR. GALV. STEEL PIPE	98.430	LF
613 (D)	0691 30" CORR. GALV. STEEL PIPE	181.430	LF

CALL ORDER : 120
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : POTTAWATOMIE CLEVELAND

CONTRACT ID : 040149
 PCN : 0634604
 PROJECTS : BRFY-14B(321)
 DBE GOALS : 4.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 74.78
 CALENDAR DAYS : 310
 RES. ENG.:
 LIQ. DAM.: \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
613 (D) 0692	36" CORR. GALV. STEEL PIPE	66.930	LF
619 (A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619 (B) 4728	REMOVAL OF ASPHALT PAVEMENT	15,950.770	SY
619 (C) 0924	SAWING PAVEMENT	646.680	LF
623 (A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	900.000	LF
623 (E) 7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	4.000	EA
623 (H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	4.000	EA
624 (C) 4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	2,593.750	LF
629 (A) 4958	MAILBOX INSTALLATION-SINGLE	3.000	EA
629 (C) 4960	MAILBOX	3.000	EA
629 (D) 4961	REMOVAL OF MAILBOX INSTALLATION	3.000	EA
SECTION NO. 0002 BRIDGE "A"			
202 (A) 1301	UNCLASSIFIED EXCAVATION	20,011.650	CY
501 (B) 1307	SUBSTRUCTURE EXCAVATION COMMON	444.710	CY
501 (G) 6309	CLSM BACKFILL	497.020	CY
503 (A) 1312	PRESTRESSED CONCRETE BEAMS (TYPE III)	1,724.390	LF
504 (A) 1304	APPROACH SLAB	989.560	SY
504 (C) 6250	SEALED EXPANSION JOINT	97.770	LF
504 (E) 6245	CONCRETE RAIL (TR4)	643.690	LF
506 (A) 1322	STRUCTURAL STEEL	3,417.170	LB
509 (A) 1326	CLASS AA CONCRETE	503.560	CY
509 (B) 1328	CLASS A CONCRETE	357.330	CY
511 6306	(PL)MECHANICAL SPLICES	140.000	EA
511 (A) 1332	REINFORCING STEEL	1,499.140	LB
511 (B) 6010	EPOXY COATED REINFORCING STEEL	183,501.760	LB
514 (A) 6010	PILES, FURNISHED (HP 10X42)	238.190	LF
514 (A) 6011	PILES, FURNISHED (HP 12X53)	925.850	LF
514 (B) 6292	PILES, DRIVEN (HP 10X42)	238.190	LF
514 (B) 6294	PILES, DRIVEN (HP 12X53)	925.850	LF
514 (F) 6354	PILE LOAD TEST (DYNAMIC)	34.000	EA
515 (A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	1,076.390	SY
516 (A) 6096	DRILLED SHAFTS 60" DIAMETER	446.190	LF
523 (A) 6550	(SP) SEALER CRACK PREPARATION	95.140	LF
523 (B) 6560	(SP) SEALER RESIN	0.590	GAL
535 6164	(PL)FIXED BEARING ASSEMBLY	16.000	EA
535 6165	(PL)EXPANSION BEARING ASSEMBLY	32.000	EA
601 (A-1) 1353	TYPE I-A PLAIN RIPRAP	4,257.000	TON
601 (A-2) 1355	TYPE I-A FILTER BLANKET	797.500	TON
613 (P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	196.190	LF
613 (Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	61.680	LF
619 (D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

CALL ORDER : 120
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : POTTAWATOMIE CLEVELAND

CONTRACT ID : 040149
 PCN : 0634604
 PROJECTS : BRFY-14B(321)
 DBE GOALS : 4.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 74.78
 CALENDAR DAYS : 310
 RES. ENG. :
 LIQ. DAM. : \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002 BRIDGE "A"			
640	1398 FIELD OFFICE	1.000	EA
641	1399 MOBILIZATION	1.000	LSUM
643	0087 (SP) CONTRACTORS QUALITY CONTROL	1.000	LSUM
SECTION NO. 0003 TRAFFIC			
627 (H)	5856 DEL. PORT. TYPE PREC. CONCRETE MEDIAN BARR	2,800.000	LF
850 (A)	8110 SHEET ALUMINUM SIGNS	12.900	SF
851 (C)	8327 2 1/4" SQUARE TUBE POST	28.010	LF
855 (A)	8812 TRAFFIC STRIPE (PLASTIC) (4" WIDE)	11,811.000	LF
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890 (A)	8722 (PL) REMOVAL OF EXISTING SIGNS	1.000	LSUM
SECTION NO. 0004 STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 170
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : COMANCHE

CONTRACT ID : 040153
 PCN : 1998004
 PROJECTS : STP-116D(079)CO
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 7.59
 CALENDAR DAYS : 120
 RES. ENG.:
 LIQ. DAM.: \$ 500



CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES AN UNNAMED TRIBUTARY TO BLUE BEAVER
 CREEK 4.0 MILES SOUTH AND 2.4 MILES EAST OF CACHE.

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000-ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (G)	0185 EARTHWORK	1.000	LSUM
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,760.000	LF
227	0100 TEMPORARY SILT DIKE	270.000	LF
230 (A)	2806 SOLID SLAB SODDING	2,350.000	SY
233 (A)	2817 VEGETATIVE MULCHING	0.480	AC
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	765.000	TON
509 (D)	0325 CLASS C CONCRETE	10.000	CY
613 (D)	0689 18" CORR. GALV. STEEL PIPE	30.000	LF
613 (M)	5726 18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
SECTION NO. 0002 X081-BRIDGE			
501 (B)	1307 SUBSTRUCTURE EXCAVATION COMMON	68.000	CY
501 (D)	6353 UNCLASSIFIED BACKFILL	50.000	CY
503 (B)	6144 PRESTRESSED CONCRETE DOUBLE TEE	514.000	LF
504 (E)	1380 CONCRETE RAIL (TR1)	316.000	LF
509 (A)	1326 CLASS AA CONCRETE	92.500	CY
509 (B)	1328 CLASS A CONCRETE	67.800	CY
511 (A)	1332 REINFORCING STEEL	24,899.000	LB
514 (A)	6010 PILES, FURNISHED (HP 10X42)	370.000	LF
514 (B)	6292 PILES, DRIVEN (HP 10X42)	370.000	LF
516 (A)	6092 DRILLED SHAFTS 36" DIAMETER	164.000	LF
601 (A-1)	1353 TYPE I-A PLAIN RIPRAP	426.000	TON
601 (A-2)	1355 TYPE I-A FILTER BLANKET	96.000	TON
619 (D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623 (F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 190
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : DELAWARE
 OSAGE

MAYES
 TULSA

CONTRACT ID : 040154
 PCN : 1970405
 PROJECTS : STPY-172H(241)
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 10.84
 CALENDAR DAYS : 40
 RES. ENG. :
 LIQ. DAM. : \$ 300

CONTRACT DESCRIPTION:
 BRIDGE WATERPROOF SEAL VARIOUS LOCATIONS IN DIVISION VIII.
 PROJECT LENGTH = 0.00 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	X031-BRIDGE A', 'B', 'C', 'D', 'E', 'F', 'G'		
515 (B) 6014	WATER REPELLENT (PERFORMANCE TESTED)	10,759.000	SY
523 (A) 6550	(SP) SEALER CRACK PREPARATION	1,506.000	LF
523 (B) 6560	(SP) SEALER RESIN	12.100	GAL
641 1399	MOBILIZATION	1.000	LSUM
876 (C) 8482	(PL) TRUCK MOUNTED ATTENUATOR	20.000	SD
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 210
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : CUSTER

CONTRACT ID : 040155
 PCN : 2025804
 PROJECTS : IMY-40-3(66)69
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 0.00
 CALENDAR DAYS : 20
 RES. ENG. :
 LIQ. DAM. : \$ 800

CONTRACT DESCRIPTION:
 RESURFACE I-40: BEGIN AT MILE MARKER 69 & EXTEND EAST TO
 MILE MARKER 77, EAST OF CLINTON. PROJECT LENGTH = 8.0 MILES
 FLEXIBLE ESALS =21.1 MILLION

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 F000-ROADWAY			
411 4280	(SP)ULTRATHIN BONDED WEARING COURSE	244,054.000	SY
SECTION NO. 0002 Y000-TRAFFIC			
855(A) 8815	TRAFFIC STR. (PLAST.) (THIN-LINE) (4" WIDE)	191,500.000	LF
857(A) 8947	PAVE.MARKERS CLASS C TYPE 2-C	940.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 230
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : GARFIELD

CONTRACT ID : 040156
 PCN : 1902204
 PROJECTS : BRO-124D(31) CO
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 13.01
 CALENDAR DAYS : 120
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY ROAD; OVER TURKEY CREEK, 4.0
 MILES SOUTH AND 2.5 MILES EAST OF LAHOMA. PROJECT LENGTH =0.
 203 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000 - ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (G)	0185 EARTHWORK	1.000	LSUM
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,145.000	LF
227	0100 TEMPORARY SILT DIKE	565.000	LF
230 (A)	2806 SOLID SLAB SODDING	6,170.000	SY
233 (A)	2817 VEGETATIVE MULCHING	1.280	AC
403 (E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	590.000	TON
509 (D)	0325 CLASS C CONCRETE	16.000	CY
613 (CC)	7187 TYPE B4 CULVERT END TREATMENT	2.000	EA
613 (CC)	7189 TYPE D4 CULVERT END TREATMENT	2.000	EA
613 (D)	0690 24" CORR. GALV. STEEL PIPE	42.000	LF
613 (D)	0692 36" CORR. GALV. STEEL PIPE	68.000	LF
SECTION NO. 0002 X081 - BRIDGE 'A'			
501 (B)	1307 SUBSTRUCTURE EXCAVATION COMMON	60.000	CY
501 (D)	6353 UNCLASSIFIED BACKFILL	40.000	CY
503 (B)	6144 PRESTRESSED CONCRETE DOUBLE TEE	817.500	LF
504 (E)	1380 CONCRETE RAIL (TR1)	375.000	LF
509 (A)	1326 CLASS AA CONCRETE	108.700	CY
509 (B)	1328 CLASS A CONCRETE	59.600	CY
511 (A)	1332 REINFORCING STEEL	27,140.000	LB
514 (A)	6010 PILES, FURNISHED (HP 10X42)	345.000	LF
514 (B)	6292 PILES, DRIVEN (HP 10X42)	345.000	LF
516 (A)	6092 DRILLED SHAFTS 36" DIAMETER	110.800	LF
601 (A-1)	1353 TYPE I-A PLAIN RIPRAP	950.000	TON
601 (A-2)	1355 TYPE I-A FILTER BLANKET	255.000	TON
619 (D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623 (F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 250
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : GARVIN LINCOLN
 JOHNSTON

CONTRACT ID : 040157
 PCN : 1944704
 PROJECTS : BRFY-NBIP(228)
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 6.50
 CALENDAR DAYS : 115
 RES. ENG. :
 LIQ. DAM. : \$ 500

CONTRACT DESCRIPTION:
 BRIDGE PAINTING DIVISION 3: SH-19 OVER WASHITA RIVER,
 SH-99 OVER WASHITA RIVER & SH-18 OVER WEST BEAVER CREEK.
 PROJECT LENGTH = 0.00 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	X031-BRIDGE 'A'		
512 (A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512 (B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
641 1399	MOBILIZATION	1.000	LSUM
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	X031-BRIDGE 'B'		
512 (A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512 (B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
SECTION NO. 0003	X031-BRIDGE 'C'		
512 (A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512 (B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM

CALL ORDER : 270
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : KAY

CONTRACT ID : 040159
 PCN : 2115604
 PROJECTS : IMG-35-4(203)213 TR
 DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 18.42
 CALENDAR DAYS : 210
 RES. ENG.:
 LIQ. DAM.: \$ 700

CONTRACT DESCRIPTION:
 GUARDRAIL I-35; FROM NOBLE COUNTY LINE NORTH TO THE KANSAS
 STATE LINE. PROJECT LENGTH = 0.00 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SFTY-TRAFFIC			
202 (C) 0184	UNCLASSIFIED BORROW	10,000.000	CY
209 0120	MACHINE GRADING	222.500	STA
230 (A) 2806	SOLID SLAB SODDING	12,338.000	SY
411 (S4) 5960	(SP) ASPH.CONC., TYPE S4 (PG 64-22 OK)	2,482.500	TON
509 (B) 0321	CLASS A CONCRETE	99.710	CY
509 (D) 0325	CLASS C CONCRETE	63.640	CY
511 (A) 0332	REINFORCING STEEL	12,839.000	LB
613 (CC) 7187	TYPE B4 CULVERT END TREATMENT	4.000	EA
619 (B) 0291	REMOVAL OF HEADWALL	4.000	EA
619 (B) 4780	REMOVAL OF GUARD RAIL	9,112.500	LF
619 (C) 0924	SAWING PAVEMENT	22,157.500	LF
623 (A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	11,700.000	LF
623 (F) 4447	GUARD RAIL ANCHOR UNIT (TYPE B)	11.000	EA
623 (F) 4453	GUARD RAIL ANCHOR UNIT (TYPE GE)	2.000	EA
623 (G) 0940	GUARD RAIL BLOCKOUT REPLACEMENT	11,375.000	LF
623 (H) 8571	(SP) G.E.T. GUARD RAIL END SECTION	63.000	EA
623 (I) 8675	(PL) BRIDGE GUARD RAIL CONNECTION-TYPE A	24.000	EA
623 (I) 8680	(PL) BRIDGE-GUARD RAIL CONNECTION-TYPE B	34.000	EA
641 1552	MOBILIZATION	1.000	LSUM
853 9066	GUARDRAIL DELINEATORS (TYPE 1, CODE 1)	548.000	EA
870 (A) 8011	SAND FILLED IMPACT ATTN.MODULE	646.000	EA
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890 (A) 8714	(PL) REMOVAL OF WINGWALLS	42.000	EA

CALL ORDER : 290
LETTING DATE : April 22, 2004
LETTING TIME : 10:30 A.M.
COUNTIES : LEFLORE

CONTRACT ID : 040158
PCN : 1965105
PROJECTS : STPY-164H(61)
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : 5.42
CALENDAR DAYS : 90
RES. ENG. :
LIQ. DAM.: \$ 300

CONTRACT DESCRIPTION:
BRIDGE WATERPROOF SEAL VARIOUS LOCATIONS IN DIVISION II.
PROJECT LENGTH = 0.00 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	X031-BRIDGE 'A', 'B', 'C', 'D', 'E', 'F'		
515 (B) 6014	WATER REPELLENT (PERFORMANCE TESTED)	9,145.000	SY
523 (A) 6550	(SP) SEALER CRACK PREPARATION	4,600.000	LF
523 (B) 6560	(SP) SEALER RESIN	28.500	GAL
641 1399	MOBILIZATION	1.000	LSUM
876 (C) 8482	(PL) TRUCK MOUNTED ATTENUATOR	90.000	SD
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 300
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : LINCOLN

CONTRACT ID : 040055
 PCN : 1253906
 PROJECTS : NHY-012N(029)
 DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 109.46
 CALENDAR DAYS : 400
 RES. ENG.:
 LIQ. DAM.: \$ 2000

CONTRACT DESCRIPTION:
 GRADE, DRAIN, SURFACE & BRIDGE (RCB) SH-99: FROM 15 MI. N.
 OF THE S. PRAGUE CITY LIMITS NORTH TO SH-66 IN STROUD.
 PROJECT LENGTH = 6.187 KM FLEXIBLE ESALS = 3.51 MILLION
 ASPHALT GRADE = PG 64-22 OK, PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
201	M0102	CLEARING AND GRUBBING	1.000 LSUM
202 (A)	M0183	UNCLASSIFIED EXCAVATION	592,923.000 M3
202 (C)	M0184	UNCLASSIFIED BORROW	500.000 M3
205	M4229	TYPE A-SALVAGED TOPSOIL	1.000 LSUM
222	M2801	TEMPORARY BALE BARRIER	168.000 M
223	M2802	TEMPORARY SILT FENCE	1,354.000 M
224	M2803	TEMPORARY SEDIMENT FILTER	32.000 EA
225	M2804	TEMPORARY SEDIMENT BASIN	2.000 EA
226	M2805	TEMPORARY SEDIMENT REMOVAL	75.000 M3
227	M0100	TEMPORARY SILT DIKE	256.000 M
229	M4318	DITCH LINER PROTECTION	2,816.000 M
230 (A)	M2806	SOLID SLAB SODDING	24,590.000 M2
230 (B)	M2807	MULCH SODDING	130,540.000 M2
230 (F)	M2812	WATERING	27,925.000 KL
232 (B)	M2814	SEEDING METHOD B	33.000 HA
233 (A)	M2817	VEGETATIVE MULCHING	33.000 HA
234 (A)	M2824	FERTILIZING (10-20-10)	20.000 T
234 (A)	M4406	FERTILIZING (0-46-0)	5.000 T
235 (A)	M0100	(PL)ROCK FILTER DAM, TYPE 1	61.000 M3
241	M2832	MOWING	25.000 HA
326 (A)	M4200	(SP)FLY ASH	9,885.000 T
326 (B)	M4210	(SP)LIME	1,641.000 T
326 (E)	M4240	(SP)CEMENTITIOUS STABILIZED SUBGRADE	171,421.000 M2
326 (F)	M4250	(SP)LIME STABILIZED SUBGRADE	85,357.000 M2
403 (A)	M0217	TRAFFIC BOUND SURFACE COURSE TYPE A	2,054.000 T
407	M0250	TACK COAT	147,659.000 L
408	M5774	PRIME COAT	145,544.000 L
411 (S2)	M5930	(SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	63,786.000 T
411 (S3)	M5940	(SP)ASPH.CONC.,TYPE S3(PG 70-28 OK)	19,125.000 T
411 (S3)	M5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	13,325.000 T
411 (S4)	M5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	13,032.000 T
411 (S4)	M5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	5,751.000 T
413 (A)	M4861	RUMBLE STRIP-METHOD AC-CON	20,619.000 M
417	M5267	COLD MILLING PAVEMENT	7,344.000 M2
501 (A)	M0313	STRUCTURAL EXCAVATION UNCLASSIFIED	325.000 M3
509 (B)	M0321	CLASS A CONCRETE	687.600 M3

CALL ORDER : 300
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : LINCOLN

CONTRACT ID : 040055
 PCN : 1253906
 PROJECTS : NHY-012N(029)
 DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 109.46
 CALENDAR DAYS : 400
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
509 (C) M0322	CLASS A CONCRETE FOR SMALL STRUCTURES	11.240	M3
509 (D) M0325	CLASS C CONCRETE	1,266.010	M3
511 (A) M0332	REINFORCING STEEL	57,092.000	KG
609 (B) M1525	800MM COMB.CRB.& GUT.(150MM BAR.)	1,909.000	M
610 (A) M0602	100MM CONCRETE SIDEWALK	2,631.000	M2
610 (B) M0604	150MM CONCRETE DRIVEWAY	474.000	M2
611 (E) M5106	INLET CICI DES. 1 (2A)	1.000	EA
611 (E) M5109	INLET CICI DES. 1 (2B)	1.000	EA
611 (E) M5113	INLET CICI DES. 2 (B)	2.000	EA
611 (E) M5115	INLET CICI DES. 2 (D)	4.000	EA
611 (E) M5123	INLET CICI DES. 3 (2B)	1.000	EA
611 (E) M6000	INLET (SMD-TYPE 1)	7.000	EA
611 (E) M6002	INLET (SMD-TYPE 2)	20.000	EA
611 (E) M6006	INLET (SMD-TYPE 2B)	2.000	EA
611 (F) M5320	INLET CICI DES 1 (ADD'L DEPTH)	0.250	M
611 (F) M5330	INLET CICI DES 3 (ADD'L DEPTH)	0.920	M
611 (G) M4488	INLET FRM&GRT (SSIF-FRM,CIG-GRT-VG-F)	18.000	EA
611 (K) M4488	CAST IRON CURB INLETS	48.000	EA
613 (B) M0405	450MM R.C.PIPE CLASS III	266.000	M
613 (B) M0409	600MM R.C.PIPE CLASS III	697.000	M
613 (B) M0415	900MM R.C.PIPE CLASS III	100.000	M
613 (B) M4411	725MM X 460MM R.C.PIPE ARCH CLASS A-III	101.000	M
613 (B) M4415	920MM X 570MM R.C.PIPE ARCH CLASS A-III	47.000	M
613 (B) M4419	1110MM X 675MM R.C.PIPE ARCH CLASS A-III	238.000	M
613 (B) M4423	1300MM X 795MM R.C.PIPE ARCH CLASS A-III	36.000	M
613 (B) M4431	1650MM X 1015MM R.C.PIPE ARCH CL. A-III	60.000	M
613 (CC)M7187	TYPE B4 CULVERT END TREATMENT	6.000	EA
613 (CC)M7197	TYPE B6 CULVERT END TREATMENT	96.000	EA
613 (CC)M7198	TYPE C6 CULVERT END TREATMENT	4.000	EA
613 (CC)M7199	TYPE D6 CULVERT END TREATMENT	8.000	EA
613 (CC)M7202	TYPE BB6 CULVERT END TREATMENT	2.000	EA
613 (CC)M7204	TYPE DD6 CULVERT END TREATMENT	1.000	EA
613 (CC)M7205	TYPE EE6 CULVERT END TREATMENT	2.000	EA
613 (D) M0690	600MM CORR. GALV. STEEL PIPE	1,067.000	M
613 (D) M0691	750MM CORR. GALV. STEEL PIPE	21.000	M
613 (D) M0692	900MM CORR. GALV. STEEL PIPE	43.000	M
613 (D) M5205	510MM X 380MM CORR. GALV. ST. PIPE ARCH	219.000	M
613 (D) M5214	680MM X 500MM CORR. GALV. ST. PIPE ARCH	858.000	M
613 (D) M5226	1030MM X 740MM CORR. GALV. ST. PIPE ARCH	25.000	M
613 (D) M5236	1390MM X 970MM CORR. GALV. ST. PIPE ARCH	53.000	M
613 (M) M0897	450MM PREFAB. CULVERT END SEC., ROUND	8.000	EA
613 (M) M0898	600MM PREFAB. CULVERT END SEC., ROUND	5.000	EA
613 (M) M4534	1110MM X 675MM PREFAB.CULV.END SEC.,ARCH	1.000	EA

CALL ORDER : 300
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : LINCOLN

CONTRACT ID : 040055
 PCN : 1253906
 PROJECTS : NHY-012N(029)
 DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 109.46
 CALENDAR DAYS : 400
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
613 (M) M4540	1300MM X 795MM PREFAB.CULV.END SEC.,ARCH	1.000	EA
613 (M) M4556	1650MM X 1015MM PREFAB.CULV.END SEC.,ARC	2.000	EA
613 (P) M1092	200MM PERFORATED PIPE UNDERDRAIN ROUND	464.000	M
613 (Q) M1097	200MM NON-PERF.PIPE UNDERDRAIN RND.	155.000	M
613 (R) M1100	PIPE UNDERDRAIN COVER MAT'L.	116.000	M3
613 (S) M1180	TRENCH EXCAVATION	3,900.000	M3
613 (T) M1181	STANDARD BEDDING MATERIAL	2,128.000	M3
619 (A) M0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619 (B) M0291	REMOVAL OF HEADWALL	11.000	EA
619 (B) M4728	REMOVAL OF ASPHALT PAVEMENT	36,147.000	M2
619 (C) M0924	SAWING PAVEMENT	2,040.000	M
624 (A) M4281	FENCE-STYLE WWF	697.000	M
624 (B) M4284	GATES-STYLE WWF(1350MM HI X 3600MM LONG)	1.000	EA
624 (C) M4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	2,356.000	M
624 (D) M4288	FENCE-STYLE CLF (1200MM HIGH, CLASS A)	100.000	M
624 (D) M4289	FENCE-STYLE CLF (1200MM HIGH, CLASS B)	51.000	M
624 (D) M4293	FENCE-STYLE CLF (1800MM HIGH, CLASS B)	41.000	M
624 (E) M5847	GATES-STYLE CLF(1200MM HI X 3600MM LONG)	1.000	EA
629 (A) M4958	MAILBOX INSTALLATION-SINGLE	16.000	EA
629 (B) M4959	MAILBOX INSTALLATION-MULTIPLE	5.000	EA
629 (C) M4960	MAILBOX	27.000	EA
629 (D) M4961	REMOVAL OF MAILBOX INSTALLATION	21.000	EA
640 M1426	FIELD OFFICE	1.000	EA
641 M1552	MOBILIZATION	1.000	LSUM
643 M0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
653 (C) M5946	OUTLET LATERAL HEADWALL	6.000	EA
SECTION NO. 0002 BRIDGE A			
202 (A) M1301	UNCLASSIFIED EXCAVATION	21,690.000	M3
501 (A) M1306	STRUCTURAL EXCAVATION UNCLASSIFIED	357.000	M3
509 (B) M1328	CLASS A CONCRETE	828.900	M3
511 (A) M1332	REINFORCING STEEL	145,910.000	KG
601 (B) M1357	TYPE II SP. PLAIN RIPRAP	150.000	T
619 (D) M1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
SECTION NO. 0003 TRAFFIC			
850 (A) M8110	SHEET ALUMINUM SIGNS	50.850	M2
851 (C) M8327	57MM SQUARE TUBE POST	431.910	M
851 (C) M8330	64MM SQUARE TUBE POST	27.420	M
855 (A) M8812	TRAFFIC STRIPE(PLASTIC)(100MM WIDE)	28,750.000	M
855 (B) M8824	TRAFFIC STRIPE(PLASTIC)(SYMBOLS)	4.000	EA

CALL ORDER : 300
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : LINCOLN

CONTRACT ID : 040055
 PCN : 1253906
 PROJECTS : NHY-012N(029)
 DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 109.46
 CALENDAR DAYS : 400
 RES. ENG. :
 LIQ. DAM. : \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 TRAFFIC			
856 (A) M8839	CONSTR.TRAFF.STR.(PAINT) (100MM WIDE)	41,000.000	M
880 (J) M8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
882 (B) M8306	PORTABLE CHANGEABLE MESSAGE SIGN	279.000	SD
SECTION NO. 0004 STAKING			
642 M0098	STAKING	1.000	LSUM

CALL ORDER : 310
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : MCCLAIN

CONTRACT ID : 040160
 PCN : 2022204
 PROJECTS : STPY-144C(61)TR
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 11.92
 COMPLETION DATE : 08/13/04

RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 TRAFFIC SIGNAL AND INTERSECTION MODIFICATION US-62;
 INTERSECTION OF US-62 AND SH-130. PROJECT LENGTH = 0.00
 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
303	0192	AGGREGATE BASE	630.730 CY
408	5774	PRIME COAT	126.150 GAL
411(S3)	5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	62.790 TON
414(B)	0301	9" H.E.S. CONCRETE PAVEMENT	210.200 SY
509(C)	0322	CLASS A CONCRETE FOR SMALL STRUCTURES	0.780 CY
609(B)	1513	1'-8" COMB.CRB.& GUT.(6" BARRIER)	456.000 LF
610(A)	0602	4" CONCRETE SIDEWALK	146.150 SY
611(E)	5117	INLET CICI DES. 2 (2B)	1.000 EA
611(G)	4488	INLET FRM&GRT (SSIF-FRM,CIG-GRT-VG-F)	2.000 EA
611(J)	0487	JUNCTION BOXES	33.790 CF
611(K)	4488	CAST IRON CURB INLETS	6.000 EA
619(A)	0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000 LSUM
619(B)	4726	REMOVAL OF CURB AND GUTTER	254.000 LF
619(B)	4727	REMOVAL OF CONCRETE PAVEMENT	750.000 SY
619(B)	4766	REMOVAL OF CONCRETE DRIVEWAY	217.000 SY
619(B)	4792	REMOVAL OF SIDEWALK	362.000 SY
619(C)	0924	SAWING PAVEMENT	480.000 LF
SECTION NO. 0002 Y031-TRAFFIC SIGNALS			
641	1552	MOBILIZATION	1.000 LSUM
802(B)	8334	1" PVC SCH.40 PLASTIC CONDUIT TRENCHED	90.000 LF
802(B)	8336	1 1/2" PVC SCH.40 PLASTIC CONDUIT BORED	55.000 LF
802(B)	8338	1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCH	250.000 LF
802(B)	8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	140.000 LF
802(B)	8344	3" PVC SCH.40 PLASTIC CONDUIT BORED	200.000 LF
803	8065	PULL BOX(SIZE I)	1.000 EA
803	8066	PULL BOX(SIZE II)	2.000 EA
803	8067	PULL BOX(SIZE III)	2.000 EA
804(A)	2915	STRUCTURAL CONCRETE	5.200 CY
804(B)	2916	REINFORCING STEEL	791.700 LB
828(B)	8138	LOOP DETECTOR WIRE	1,140.000 LF
834(A)	8207	5/C TRAF.SIG.EL.CABLE	230.000 LF
834(A)	8209	9/C TRAF.SIG.EL.CABLE	180.000 LF
834(B)	8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	650.000 LF
855(A)	8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	4,611.000 LF

CALL ORDER : 310
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : MCCLAIN

CONTRACT ID : 040160
 PCN : 2022204
 PROJECTS : STPY-144C(61)TR
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 11.92
 COMPLETION DATE : 08/13/04

RES. ENG.:
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	Y031-TRAFFIC SIGNALS		
855 (B) 8818	TRAFFIC STRIPE (PLASTIC) (ARROWS)	2.000	EA
855 (B) 8821	TRAFFIC STRIPE (PLASTIC) (WORDS)	2.000	EA
859 (A) 8006	PAVEMENT MRKNG.REMOVAL (TRAF.STRP)	4,611.000	LF
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890 (A) 8704	(PL)REMOVAL OF PULL BOX	3.000	EA
890A/B 8742	(PL)REMOVE & RESET TRAF.SIG.EQUIPMENT	2.000	LSUM

CALL ORDER : 330
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : MUSKOGEE

MCINTOSH

CONTRACT ID : 040161
 PCN : 1970305
 PROJECTS : STPY-151H(121)
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 8.67
 CALENDAR DAYS : 30
 RES. ENG. :
 LIQ. DAM. : \$ 300

CONTRACT DESCRIPTION:
 BRIDGE WATERPROOF SEAL VARIOUS LOCATIONS IN DIVISION I.
 PROJECT LENGTH = 0.00 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	X031-BRIDGE 'A', 'B', 'C', 'D', 'E', 'F'		
515 (A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	1,514.000	SY
515 (B) 6014	WATER REPELLENT (PERFORMANCE TESTED)	9,263.000	SY
523 (A) 6550	(SP) SEALER CRACK PREPARATION	1,645.000	LF
523 (B) 6560	(SP) SEALER RESIN	12.900	GAL
641 1399	MOBILIZATION	1.000	LSUM
876 (C) 8482	(PL) TRUCK MOUNTED ATTENUATOR	15.000	SD
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 350
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : NOBLE PONTOTOC
 SEMINOLE

CONTRACT ID : 040162
 PCN : 2118704M
 PROJECTS : BPMY-NBIP(337)3B
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 5.42
 CALENDAR DAYS : 85
 RES. ENG. :
 LIQ. DAM. : \$ 500

CONTRACT DESCRIPTION:
 BRIDGE PAINTING VARIOUS LOCATIONS IN DIVISION III. PROJECT
 LENGTH = 0.00 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	X031-BRIDGE 'A' BPMY-NBIP(337)3B		
512 (A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512 (B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
641 1399	MOBILIZATION	1.000	LSUM
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	X231-BRIDGE 'B' BHFY-NBIP(174)		
512 (A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512 (B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
641 1399	MOBILIZATION	1.000	LSUM
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	X031-BRIDGE 'C' NHY-NBIP(163)		
512 (A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512 (B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM

CALL ORDER : 360
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 040163
 PCN : 1798305
 PROJECTS : NHY-12N(76)
 BHFY-17N(101)
 BPMY-154C(67)3B
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 8.67
 CALENDAR DAYS : 75
 RES. ENG.:
 LIQ. DAM.: \$ 300

COUNTIES : OKFUSKEE

CONTRACT DESCRIPTION:
 JOINT SEAL/REPAIR VARIOUS LOCATIONS IN DIVISION III.
 PROJECT LENGTH = 0.00 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 X031-BRIDGE 'A' BPMY-154C(67)3B			
520 (A) 6058	PREPARATION OF CRACKS ABOVE WATER	110.000	LF
520 (C) 6060	EPOXY RESIN ABOVE WATER	11.000	GAL
641 1399	MOBILIZATION	1.000	LSUM
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002 X231-BRIDGE 'B' BHFY-17N(101)			
501 (G) 6309	CLSM BACKFILL	5.000	CY
504 (H) 6390	RAPID CURE JOINT SEALANT	61.000	LF
504 (I) 6389	ELASTOMERIC MORTAR	16.000	CF
520 (A) 6058	PREPARATION OF CRACKS ABOVE WATER	10.000	LF
520 (C) 6060	EPOXY RESIN ABOVE WATER	1.000	GAL
521 (A) 6210	PNEUMATICALLY PLACED MORTAR	2.000	SY
535 6130	(SP)CORROSION INHIBITOR(SURFACE APPLIED)	2.000	SY
535 6386	(PL)SILICONE CONSTRUCTION JOINT	95.000	LF
641 1399	MOBILIZATION	1.000	LSUM
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 X031-BRIDGE 'C' NHY-12N(76)			
504 (H) 6390	RAPID CURE JOINT SEALANT	86.000	LF
505 (B) 6019	CLASS B BRIDGE DECK REPAIR	15.000	SY
521 (A) 6210	PNEUMATICALLY PLACED MORTAR	15.000	SY
535 6130	(SP)CORROSION INHIBITOR(SURFACE APPLIED)	15.000	SY
535 6386	(PL)SILICONE CONSTRUCTION JOINT	258.000	LF

CALL ORDER : 375
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : OKLAHOMA

CONTRACT ID : 040112
 PCN : 2118804
 PROJECTS : BPMIY-NBIP(338) 3B
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 5.42
 CALENDAR DAYS : 45
 RES. ENG. :
 LIQ. DAM. : \$ 800

CONTRACT DESCRIPTION:
 BRIDGE PAINTING I-40 RAMP; BRIDGES AT I-44; "K" INTERCHANGE.
 PROJECT LENGTH = 0.00 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	X271-BRIDGE "A" & "B"		
512 (A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512 (B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
641 1399	MOBILIZATION	1.000	LSUM
876 (C) 8482	(PL) TRUCK MOUNTED ATTENUATOR	30.000	SD
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880 (L) 8911	TRAFFIC SURVEILLANCE, POLICE	100.000	HOURL
882 (B) 8306	PORT.CHANGEABLE MESSAGE SIGN	90.000	SD

CALL ORDER : 390
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : OKLAHOMA

CONTRACT ID : 040164
 PCN : 1557504
 PROJECTS : BRO-55D(906)CO
 DBE GOALS : 7.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 11.92
 CALENDAR DAYS : 120
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY ROAD;0.50 MILE NORTH OF US-62
 AND 6.0 MILES WEST OF LINCOLN COUNTY LINE. PROJECT LENGTH =
 0.080 MILE FLEXIBLE ESALS = 0.27 MILLION ASPHALT GRADE = PG
 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000 - ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202 (G)	0185 EARTHWORK	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	213.000	LF
223	2801 TEMPORARY SILT FENCE	853.000	LF
230 (A)	2806 SOLID SLAB SODDING	807.000	SY
233 (A)	2817 VEGETATIVE MULCHING	0.770	AC
303	0192 AGGREGATE BASE	170.000	CY
407	0250 TACK COAT	209.000	GAL
408	5774 PRIME COAT	54.000	GAL
411 (S3)	5940 (SP) ASPH. CONC., TYPE S3 (PG 70-28 OK)	106.000	TON
411 (S4)	5955 (SP) ASPH. CONC., TYPE S4 (PG 70-28 OK)	214.000	TON
619 (B)	4728 REMOVAL OF ASPHALT PAVEMENT	749.000	SY
619 (C)	0924 SAWING PAVEMENT	50.000	LF
855 (A)	8815 TRAFFIC STR. (PLAST.) (THIN-LINE) (4" WIDE)	1,706.000	LF
SECTION NO. 0002 X081-BRIDGE 'A'			
501 (B)	1307 SUBSTRUCTURE EXCAVATION COMMON	126.000	CY
501 (D)	6353 UNCLASSIFIED BACKFILL	320.000	CY
503 (B)	6144 PRESTRESSED CONCRETE DOUBLE TEE	395.000	LF
504 (E)	1380 CONCRETE RAIL (TR1)	257.670	LF
506 (A)	1322 STRUCTURAL STEEL	2,580.000	LB
509 (A)	1326 CLASS AA CONCRETE	77.000	CY
509 (B)	1328 CLASS A CONCRETE	118.000	CY
511 (A)	1332 REINFORCING STEEL	21,570.000	LB
514 (A)	6010 PILES, FURNISHED (HP 10X42)	760.000	LF
514 (B)	6292 PILES, DRIVEN (HP 10X42)	760.000	LF
601 (A-1)	1353 TYPE I-A PLAIN RIPRAP	454.000	TON
601 (A-2)	1355 TYPE I-A FILTER BLANKET	193.000	TON
619 (D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623 (F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880 (J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 401
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : OKLAHOMA

CONTRACT ID : 040058
 PCN : 2044104
 PROJECTS : NHG-025N(004)TR
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 66.65
 CALENDAR DAYS : 150
 RES. ENG.:
 LIQ. DAM.: \$ 700

CONTRACT DESCRIPTION:
 SAFETY IMPROVEMENT I-44/SH-74; FROM I-240 NORTH TO THE
 KILPATRICK TURNPIKE IN OKLAHOMA CITY. PROJECT LENGTH = 0.00
 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SFTY-TRAFFIC ITEMS			
509(B)	0321 CLASS A CONCRETE	88.450	CY
641	1552 MOBILIZATION	1.000	LSUM
802(B)	8336 1 1/2" PVC SCH.40 PLASTIC CONDUIT BORED	5,205.000	LF
802(B)	8338 1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCH	12,000.000	LF
802(B)	8344 3" PVC SCH.40 PLASTIC CONDUIT BORED	1,250.000	LF
802(B)	8346 3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	4,375.000	LF
803	8066 PULL BOX(SIZE II)	16.000	EA
803	8071 GROUND BOX(SIZE II)	1.000	EA
803	8075 GROUND BOX, R1	18.000	EA
804(B)	2916 REINFORCING STEEL	8,175.720	LB
810(A)	3118 SERVICE POLE	20.000	EA
811	8032 1/C NO.0 ELECT.COND.	17,150.000	LF
815	8610 (PL)CCTV CAMERA, PAN-TILT-ZOOM	18.000	EA
815	8615 (PL)CCTV CAMERA, WEB	55.000	EA
815	8620 (PL)CCTV CAMERA POLE	15.000	EA
818	8715 (PL)FIBER OPTIC CABLE, 24, SMF-28	7,700.000	LF
818	8720 (PL)FIBER OPTIC CABLE, 48, SMF-28	1,200.000	LF
818	8735 (PL)FIBER OPTIC CABLE SPLICE	203.000	EA
818	8740 (PL)FIBER OPTIC CABLE TERMINATION	179.000	EA
818	8745 (PL)FIBER OPTIC PATCH PANEL, 24 PORT	19.000	EA
818	8760 (PL)FIBER OPTIC PATCH PANEL CABEL, 5'	81.000	EA
818	8780 (PL)FIBER OPTIC & COMMUNICATION EQUIP.	1.000	LSUM
877	5540 (PL)SOLAR POWER SYSTEM	17.000	EA
877	5545 (PL)NETWORK EQUIPMENT PACKAGE A	10.000	EA
877	5546 (PL)NETWORK EQUIPMENT PACKAGE B	3.000	EA
877	5547 (PL)NETWORK EQUIPMENT PACKAGE C	1.000	EA
877	5548 (PL)NETWORK EQUIPMENT PACKAGE D	4.000	EA
877	5550 (PL)INSTALLATION OF COMMUNICATION CABLE	1,500.000	LF
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
887	8370 (PL)SHIELD ISOLATION PEDESTAL	22.000	EA
895	6551 CABINET	16.000	EA

CALL ORDER : 410
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : PONTOTOC

CONTRACT ID : 040196
 PCN : 2122604
 PROJECTS : STPY-162B(111) 3R
 DBE GOALS : 3.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 0.00
 CALENDAR DAYS : 60
 RES. ENG. :
 LIQ. DAM. : \$ 500

CONTRACT DESCRIPTION:
 PAVEMENT REHAB(PATCHING) SH-3W: BEG. AT THE POTTAWATOMIE
 COUNTY LINE, EXTEND SOUTH. PROJECT LENGTH = 1.43 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
414 (B) 5913	H.E.S. CONCRETE (FULL DEPTH PATCHING)	1,700.000	SY
417 4659	(PL) FOG SEAL	839.000	GAL
417 5267	COLD MILLING PAVEMENT	3,238.000	SY
425 5195	DIAMOND GRINDING CONCRETE PAVEMENT	20,134.000	SY
855 (A) 8812	TRAFFIC STRIPE(PLASTIC) (4" WIDE)	26,426.000	LF
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002 TRAFFIC			
619 (B) 4780	REMOVAL OF GUARD RAIL	220.000	LF
623 8572	(PL) CURVED APPROACH GUARD RAIL	1.000	EA
623 (A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	250.000	LF
623 (F) 4447	GUARD RAIL ANCHOR UNIT (TYPE B)	1.000	EA
623 (F) 4450	GUARD RAIL ANCHOR UNIT (TYPE E)	4.000	EA
623 (H) 8571	(SP) G.E.T. GUARD RAIL END SECTION	3.000	EA
853 9066	GUARDRAIL DELINEATORS (TYPE 1, CODE 1)	24.000	EA

CALL ORDER : 420
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : SEQUOYAH

CONTRACT ID : 040166
 PCN : 2028104
 PROJECTS : IMY-40-6(335)303
 DBE GOALS : 7.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 22.76
 CALENDAR DAYS : 180
 RES. ENG.:
 LIQ. DAM.: \$ 1000

CONTRACT DESCRIPTION:
 RESURFACING I-40: FROM DWIGHT MISSION RD. TO JUST EAST OF
 US-59 PROJECT LENGTH = 4.968 MILES FLEXIBLE ESALS = 79.44
 MILLION ASPHALT GRADE = PG 64-22 OK, PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
202 (A)	4349 (PL)UNCLASSIFIED EXCAVATION	1.000	LSUM
202 (C)	4812 (PL)UNCLASSIFIED BORROW	1.000	LSUM
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
209	0120 MACHINE GRADING	82.960	STA
223	2801 TEMPORARY SILT FENCE	6,400.000	LF
226	2805 TEMPORARY SEDIMENT REMOVAL	50.000	CY
227	0100 TEMPORARY SILT DIKE	1,080.000	LF
230 (A)	2806 SOLID SLAB SODDING	15,896.000	SY
233 (A)	2817 VEGETATIVE MULCHING	3.290	AC
303	0192 AGGREGATE BASE	2,526.000	CY
326 (A)	4200 (SP)FLY ASH	663.000	TON
326 (B)	4210 (SP)LIME	89.000	TON
326 (E)	4240 (SP)CEMENTITIOUS STABILIZED SUBGRADE	12,264.000	SY
326 (F)	4250 (SP)LIME STABILIZED SUBGRADE	6,120.000	SY
407	0250 TACK COAT	23,201.000	GAL
408	5774 PRIME COAT	4,870.000	GAL
411 (S2)	5930 (SP)ASPH.CONC.,TYPE S2 (PG 64-22 OK)	2,487.000	TON
411 (S3)	5935 (SP)ASPH.CONC.,TYPE S3 (PG 76-28 OK)	28,086.000	TON
411 (S3)	5945 (SP)ASPH.CONC.,TYPE S3 (PG 64-22 OK)	9,474.000	TON
411 (S4)	5950 (SP)ASPH.CONC.,TYPE S4 (PG 76-28 OK)	19,288.000	TON
411 (S4)	5960 (SP)ASPH.CONC.,TYPE S4 (PG 64-22 OK)	7,111.000	TON
413 (A)	4861 RUMBLE STRIP-METHOD AC-CON	96,691.000	LF
417	5267 COLD MILLING PAVEMENT	148,470.000	SY
504 (A)	1304 APPROACH SLAB	169.000	SY
504 (H)	6390 RAPID CURE JOINT SEALANT	138.000	LF
509 (B)	0321 CLASS A CONCRETE	28.000	CY
613 (D)	0690 24" CORR. GALV. STEEL PIPE	512.000	LF
613 (M)	5730 24" PREFAB. CULVERT END SEC., ROUND	4.000	EA
619 (B)	4763 REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	10,134.000	SY
619 (B)	4780 REMOVAL OF GUARD RAIL	3,263.000	LF
619 (C)	0924 SAWING PAVEMENT	152.000	LF
623 (A)	0932 BEAM GUARD RAIL-W-BEAM-SINGLE	5,025.000	LF
623 (E)	7114 THRIE BEAM BRIDGE CONNECTION-TYPE A	15.000	EA
623 (F)	4447 GUARD RAIL ANCHOR UNIT (TYPE B)	4.000	EA
623 (H)	8571 (SP)G.E.T. GUARD RAIL END SECTION	19.000	EA
641	1552 MOBILIZATION	1.000	LSUM
643	0087 (SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM

CALL ORDER : 420
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : SEQUOYAH

CONTRACT ID : 040166
 PCN : 2028104
 PROJECTS : IMY-40-6(335)303
 DBE GOALS : 7.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 22.76
 CALENDAR DAYS : 180
 RES. ENG.:
 LIQ. DAM.: \$ 1000

SECTION NO. 0002 TRAFFIC CONTROL

627 (G)	4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	4,580.000	LF
627 (H)	5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	3,320.000	LF
856 (G)	8887	(PL)CONST.ZONE PAV.MKRS (FLEX TAB) TYP.2-1	2,307.000	EA
876 (C)	8482	(PL)TRUCK MOUNTED ATTENUATOR	240.000	SD
880 (A)	8812	ARROW DISPLAY (TYPE C)	300.000	SD
880 (B)	8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	5,880.000	SD
880 (B)	8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,620.000	SD
880 (B)	8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	5,040.000	SD
880 (C)	8842	BARRICADES (TYPE III)	680.000	SD
880 (C)	8848	WING BARRICADES	1,260.000	SD
880 (E)	8860	WARNING LIGHTS (TYPE A)	6,400.000	SD
880 (E)	8872	WARNING LIGHTS (TYPE C)	8,120.000	SD
880 (F)	8878	DRUMS	8,120.000	SD
880 (H)	8896	CONES (36" LARGE)	94,080.000	SD
880 (L)	8911	TRAFFIC SURVEILLANCE, POLICE	150.000	HOURL
880 (M)	8325	(PL)SPEED MONITORING DEVICE	210.000	SD
882 (B)	8306	PORT.CHANGEABLE MESSAGE SIGN	210.000	SD

SECTION NO. 0003 STRIPING

804 (B)	2916	REINFORCING STEEL	1,124.000	LB
855 (A)	8812	TRAFFIC STRIPE (PLASTIC) (4" WIDE)	154,991.000	LF
857 (A)	8947	PAVE.MARKERS CLASS C TYPE 2-C	819.000	EA
870	8011	SAND FILLED IMPACT ATTEN.MODULE REMOVAL	1.000	LSUM
870 (A)	8011	SAND FILLED IMPACT ATTEN.MODULE	76.000	EA

SECTION NO. 0004 STAKING

642	0098	STAKING	1.000	LSUM
-----	------	---------	-------	------

CALL ORDER : 440
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : CADDO

LOVE

CONTRACT ID : 040167
 PCN : 2131804
 PROJECTS : STPY-169H(92)
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 7.59
 CALENDAR DAYS : 30
 RES. ENG. :
 LIQ. DAM.: \$ 200

CONTRACT DESCRIPTION:
 BRIDGE WATERPROOF SEAL VARIOUS LOCATIONS IN DIVISION VII.
 PROJECT LENGTH = 0.00 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	X031-BRIDGE 'A', 'B', 'C', 'D', 'E'		
515 (B) 6014	WATER REPELLENT (PERFORMANCE TESTED)	4,469.000	SY
523 (A) 6550	(SP) SEALER CRACK PREPARATION	825.000	LF
523 (B) 6560	(SP) SEALER RESIN	5.700	GAL
641 1399	MOBILIZATION	1.000	LSUM
876 (C) 8482	(PL) TRUCK MOUNTED ATTENUATOR	20.000	SD
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 460
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : WOODWARD WOODS
 TEXAS

CONTRACT ID : 040168
 PCN : 1965505
 PROJECTS : STPY-130H(62)
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 5.42
 CALENDAR DAYS : 10
 RES. ENG. :
 LIQ. DAM. : \$ 200

CONTRACT DESCRIPTION:
 BRIDGE WATERPROOF SEAL VARIOUS LOCATIONS IN DIVISION VI.
 PROJECT LENGTH = 0.00 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	X031-BRIDGE 'A', 'B', 'C'		
515 (B) 6014	WATER REPELLENT (PERFORMANCE TESTED)	2,113.000	SY
523 (A) 6550	(SP) SEALER CRACK PREPARATION	2,094.000	LF
523 (B) 6560	(SP) SEALER RESIN	14.100	GAL
641 1399	MOBILIZATION	1.000	LSUM
876 (C) 8482	(PL) TRUCK MOUNTED ATTENUATOR	6.000	SD
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 465
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : TEXAS

CONTRACT ID : 040129
 PCN : 1949005
 PROJECTS : BHFY-176C(054)
 BHFY-170C(095)
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 6.50
 CALENDAR DAYS : 45
 RES. ENG. :
 LIQ. DAM. : \$ 300

CONTRACT DESCRIPTION:
 JOINT SEAL/REPAIR SH-136; OVER FRISCO CREEK., 7 MI.
 NORTH OF TEXAS S/L/ SH-14; OVER EAGLE CHIEF, 5.0 MI SOUTH
 OF US-64. PROJECT LENGTH = 0.00 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE 'B' - BHFY-170C(95)			
504(H) 6390	RAPID CURE JOINT SEALANT	65.000	LF
504(I) 6389	ELASTOMERIC MORTAR	16.000	CF
520(A) 6058	PREPARATION OF CRACKS ABOVE WATER	860.000	LF
520(C) 6060	EPOXY RESIN ABOVE WATER	57.000	GAL
521(A) 6210	PNEUMATICALLY PLACED MORTAR	65.000	SY
535 6386	(PL)SILICONE CONSTRUCTION JOINT	391.000	LF
SECTION NO. 0002 TRAFFIC - BHFY-170C(95)			
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 BRIDGE 'A' - BHFY-176C(54)			
202(G) 6181	EARTHWORK	1.000	LSUM
411(S4) 6310	(SP)ASPH.CONC.,TYPE S4(PATCH)(PG64-22OK)	4.000	TON
504(H) 6390	RAPID CURE JOINT SEALANT	52.000	LF
504(I) 6389	ELASTOMERIC MORTAR	8.700	CF
505 6139	(PL)MEMBRANE	17.400	SY
520(A) 6058	PREPARATION OF CRACKS ABOVE WATER	460.000	LF
520(C) 6060	EPOXY RESIN ABOVE WATER	30.000	GAL
521(A) 6210	PNEUMATICALLY PLACED MORTAR	38.000	SY
535 6386	(PL)SILICONE CONSTRUCTION JOINT	20.000	LF
641 1399	MOBILIZATION	1.000	LSUM
SECTION NO. 0004 TRAFFIC - BHFY-176C(54)			
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 480
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : TULSA

CONTRACT ID : 040169
 PCN : 2028004
 PROJECTS : BHFY-172C(234)
 DBE GOALS : 10.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 15.17
 CALENDAR DAYS : 45
 RES. ENG. :
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE REPAIR/JOINT SEAL SH-151: OVER KEYSTONE DAM.
 PROJECT LENGTH = 0.00 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE A			
504 (H) 6390	RAPID CURE JOINT SEALANT	710.000	LF
505 (C) 6020	CLASS C BRIDGE DECK REPAIR	150.000	SY
505 (E) 6250	(SP)ELASTOMERIC MORTAR (PATCHING)	1,285.000	CF
523 (C) 6570	(SP) DECK AREA SEALED (FLOODCOATS)	2,664.000	SY
641 1399	MOBILIZATION	1.000	LSUM
SECTION NO. 0002 TRAFFIC			
627 (G) 4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	100.000	LF
627 (H) 5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	200.000	LF
823 8478	(PL)PORTABLE TRAFFIC SIGNAL SYSTEM	45.000	SD
823 8495	(PL)DELIVER PORTABLE TRAFFIC SIGNAL SYS.	1.000	LSUM
855 (A) 8812	TRAFFIC STRIPE (PLASTIC) (4" WIDE)	18,440.000	LF
859 (A) 8006	PAVEMENT MRKNG.REMOVAL (TRAF.STRP)	18,440.000	LF
870 (A) 8485	SAND FILLED IMPACT ATTEN.MODULE	20.000	SD
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
882 (B) 8306	PORT.CHANGEABLE MESSAGE SIGN	180.000	SD
SECTION NO. 0003 GUARDRAIL			
230 (A) 2806	SOLID SLAB SODDING	300.000	SY
509 (D) 0325	CLASS C CONCRETE	8.520	CY
511 (A) 0332	REINFORCING STEEL	64.130	LB
619 (B) 4780	REMOVAL OF GUARD RAIL	6,040.000	LF
623 (A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	5,900.000	LF
623 (H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	4.000	EA
853 9066	GUARDRAIL DELINEATORS (TYPE 1, CODE 1)	120.000	EA

CALL ORDER : 600
 LETTING DATE : April 22, 2004
 LETTING TIME : 10:30 A.M.
 COUNTIES : COMANCHE

CONTRACT ID : 040200
 PCN : 2143604
 PROJECTS : MC-116C(107)
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 0.00
 CALENDAR DAYS : 30
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE REPAIR SH-17: AT SHETTLERS CR, BEAVER CR, TRIB TO
 COTTONWOOD CR & WHISKEY CR NEAR STERLING, OK. PROJECT
 LENGTH = 0.00 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGES A, B, C - BASE BID		
540 4505	(PL)REPAIR BRIDGE ITEMS	24.000	EA
641 1399	MOBILIZATION	1.000	LSUM
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	BRIDGE "D" ADD ALTERNATE #1		
540 4505	(PL)REPAIR BRIDGE ITEMS	16.000	EA
641 1399	MOBILIZATION	1.000	LSUM
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM