

Notice

Electronic bid packages are available for the [January 19, 2006](#) Letting. Instructions for using the electronic bidding system (EBS) are available from the Office Engineer's office. The printed bid sheets created from the EBS system must be placed in front of the bid item pages in the bidding proposal and will be turned in with the bid documents along with the proper disk. They should be placed and attached there without detaching the original proposal. (The paper copy of the bid items is the official bid document.) Please remember that you must use the electronic bidding system (EBS) when bidding projects in the highway Letting. Failure to use the EBS system could mean possible rejection of bids. Plans and proposals should be ready for sale on [December 29, 2005](#).

If ordering plans only please call the Reproduction Branch at 521-2586.

A Pre-Bid Conference will be held at [10:00 a.m.](#) on [January 6, 2005](#) concerning this [January](#) Bid Opening at the Oklahoma Department of Transportation (ODOT) Commission Room. Please review plans and proposals and send your comments and questions to the Office Engineer Division (attn: Masoud Pajoh) as early as possible at Fax: (405) 522-0972 or phone: (405) 521-2625. This will help both ODOT and Contractor.

All proposals not mailed must be turned into the Reproduction office off the main lobby of the ODOT building until 30 minutes before the Opening. From 30 minutes before the Bid Opening until the time of the Bid Opening, bid proposals must be turned in directly to the ODOT Commission Room on the east side of the lobby.

Please write the call order number of the jobs you are bidding electronically on the disk label of the original disk. Be sure to save your work and any revisions you receive to your original disk and submit that disk with your bid.

Questions and concerns regarding projects on the Letting should
be faxed to:

Office Engineer Division at 405-522-0972

or emailed to:

mpajoh@odot.org with copy to bschmitt@odot.org

Please include words ***“Pre-bid question(s)”*** in the subject line.

**Until further notice all projects which include a pay item for Contractors
Quality Control (Item 643) will require the bidder to bid a minimum
amount for that item.**

This minimum will be specified at the end of the Special Provision 648-1QA(a)99,
Payment for Contractor's Quality Control. You may increase this amount as necessary
to cover the estimated Quality Control expenses.

***Failure to include at least this amount will be considered grounds for
rejection of Contractor's bid as nonresponsive.***

Note:

ODOT will no longer allow DBE credit towards project DBE goals for the supplying
of liquid asphalt cement or other bituminous materials.

**Long Form and Short Form Notices, Order Forms, Bid Tabs and Awards, can be accessed on ODOT's Web site
<http://www.okladot.state.ok.us/contracts/index.htm>**

Reminder

The low bidder must submit to the Office Engineer Division written confirmation from the DBE that it is participating in the contract as provided in the prime contractor's commitment. This may be submitted with the bid or not later than the Department's close of business on the Wednesday following the bid opening. Otherwise the bid shall be considered nonresponsive and shall be rejected by the Department.

**Only DBE firms listed for the Letting month on the following web site are eligible for DBE credit:
<http://www.okladot.state.ok.us/regserv/dbeinfo/dcf2005.htm>**

Reminder

*Please be sure that bid bonds are stapled to the **back** of the proposal as instructed on the cover sheet of all proposals.*

Do not disassemble the bidding proposal in any way.

Note:

Only written, Email, Fax and in-person orders will be accepted.

The **Order Form** included in this Short Form Notice may be used to order plans and proposals for this letting.

Please check off the proposal(s) in which you are interested and fax to:

405-522-0972 attention Order Desk

Or email your requests to:

aruschenberg@odot.org

The Bid Opening can be heard from the AGC website which is:
<http://www.okagchwy.com/>

DATE : December 23, 2005 LAHOMA DEPARTMENT OF TRANSPORTATION
NOTICE TO CONTRACTORS -- January 19, 2006

LNTCNCA
LETTING

LNTCNCA-D

SEALED PROPOSALS SENT BY REGISTERED MAIL WILL BE RECEIVED THROUGH THE ODOT REPRODUCTION BRANCH UNTIL 30 MINUTES PRIOR TO THE SCHEDULED BID OPENING. FROM 30 MINUTES PRIOR TO THE BID OPENING UNTIL THE TIME OF THE BID OPENING, BID PROPOSALS MUST BE TURNED IN DIRECTLY TO THE ODOT COMMISSION ROOM LOCATED ON THE EAST SIDE OF THE LOBBY. THE SCHEDULED BID OPENING OF 10:30 A.M. January 19, 2006 , FOR THE WORK LISTED BELOW.

NO PROPOSAL FOR CONSTRUCTION OR MAINTENANCE WORK OF THE DEPARTMENT WILL BE ISSUED TO ANY CONTRACTOR AFTER 10:30 A.M. ON THE WORKING DAY PRECEDING OPENING OF BIDS FOR ANY CONTRACT.

EACH SEPARATE PROPOSAL SHALL BE ACCOMPANIED BY A CERTIFIED OR CASHIER'S CHECK OR BID BOND EQUAL TO 5% OF THE BID MADE PAYABLE TO THE STATE OF OKLAHOMA, DEPARTMENT OF TRANSPORTATION, AS A PROPOSAL GUARANTY. PROPOSAL CHECKS WILL BE HELD OR RETURNED BY THE DEPARTMENT AS PER SECTION 103.04 OF THE STATE STANDARD SPECIFICATIONS.

THIS WORK WILL BE DONE UNDER THE OKLAHOMA DEPARTMENT OF TRANSPORTATION COMMISSION'S APPLICABLE SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.

THE MINIMUM WAGE TO BE PAID LABORERS AND MECHANICS EMPLOYED ON THIS PROJECT WILL BE INCLUDED IN THE PROPOSAL.

PROPOSALS MUST BE PREPARED AS DIRECTED BY THE STATE STANDARD SPECIFICATIONS.

THIS WORK WILL BE DONE UNDER THE OKLAHOMA DEPARTMENT OF TRANSPORTATION COMMISSION'S APPLICABLE SPECIFICATIONS FOR HIGHWAY CONSTRUCTION AS DEPICTED ON THE LOWER LEFT CORNER OF THE PLAN'S TITLE SHEET.

PLANS, FORMS OF PROPOSALS, CONTRACTS AND SPECIFICATIONS MAY BE EXAMINED AT THE DIVISION HEADQUARTERS IN THE DIVISION THE WORK IS TO BE PERFORMED OR AT THE OKLAHOMA DEPARTMENT OF TRANSPORTATION OFFICE ENGINEER'S DIVISION IN OKLAHOMA CITY, OKLAHOMA.

PLANS AND PROPOSAL FORMS MAY BE ORDERED FROM THE OFFICE ENGINEER DIVISION, OKLAHOMA DEPARTMENT OF TRANSPORTATION BUILDING, 200 N.E. 21ST STREET, OKLAHOMA CITY, OKLAHOMA 73105. COST OF BIDDING DOCUMENTS ARE \$25.00 + tax FOR EACH BIDDING PROPOSAL. STATE STANDARD SPECIFICATION 1988 EDITION (RED BOOK) AND 1991 SUPPLEMENT MAY BE PURCHASED FOR \$8.00 + tax, OR 1996 METRIC STANDARD SPECIFICATION \$27.00 + TAX, OR 1999 METRIC AND ENGLISH STANDARD SPECIFICATION \$55.00 + TAX. (OKLAHOMA TAX IS 8.375%). MAKE CHECKS PAYABLE TO OKLAHOMA DEPARTMENT OF TRANSPORTATION.

NO REFUNDS WILL BE MADE FOR BIDDING DOCUMENTS OR SPECIFICATION BOOKS PURCHASED BY PROSPECTIVE BIDDERS.

UPON AWARD OF CONTRACT TO A SUCCESSFUL BIDDER, THE CONTRACT WILL BE COMPLETELY AND CORRECTLY EXECUTED BY THE CONTRACTOR AND RETURNED TO THE DEPARTMENT WITHIN TEN (10) WORKING DAYS FROM THE DATE OF AWARD. THE DEPARTMENT WILL HAVE FOURTEEN (14) WORKING DAYS FROM THE DATE OF AWARD TO COMPLETE ITS EXECUTION OF THE CONTRACT.

THE OKLAHOMA DEPARTMENT OF TRANSPORTATION HEREBY NOTIFIES ALL BIDDERS THAT IT WILL AFFIRMATIVELY INSURE THAT IN ANY CONTRACT ENTERED INTO PURSUANT TO THIS ADVERTISEMENT, DISADVANTAGED BUSINESS ENTERPRISES WILL BE AFFORDED FULL OPPORTUNITY TO SUBMIT BIDS IN RESPONSE TO THIS INVITATION AND WILL NOT BE DISCRIMINATED AGAINST ON THE GROUNDS OF RACE, COLOR, SEX, RELIGION, NATIONAL ORIGIN, OR DISABILITY IN CONSIDERATION FOR AN AWARD.

BIDDERS ARE HEREBY NOTIFIED THAT ALL BIDS ARE LIKELY TO BE REJECTED IF THE LOWEST RESPONSIVE BID RECEIVED EXCEEDS THE ENGINEER'S ESTIMATE BY MORE THAN SEVEN (7) PERCENT. IN THE EVENT ALL BIDS ARE REJECTED FOR THIS REASON, THIS PROJECT MAY BE DEFERRED FOR READVERTISING FOR BIDS UNTIL A MORE COMPETITIVE SITUATION EXISTS.

DESCRIPTION OF WORK AND LOCATION OF PROJECT:

CALL ORDER : 020
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : BEAVER

CONTRACT ID : 050724
 PCN : 2120904
 PROJECTS : BRO-104D(035)CO
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 10.84
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES COUNTY ROAD: OVER FULTON CREEK, 2.0
 MILES SOUTH AND 4.8 MILES WEST OF THE US-83/US-412 JCT. AT
 BRYANS CORNER. PROJECT LENGTH = 0.264 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	ROADWAY - BRO-104D(35)CO		
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,000.000	LF
227	0100 TEMPORARY SILT DIKE	400.000	LF
230(A)	2806 SOLID SLAB SODDING	7,600.000	SY
232(D)	2816 WATERING	608.000	MGAL
233(A)	2817 VEGETATIVE MULCHING	1.430	AC
234(A)	2824 FERTILIZING (10-20-10)	0.760	TON
403(A)	0217 TRAFFIC BOUND SURFACE COURSE TYPE A	751.000	TON
509(D)	0325 CLASS C CONCRETE	43.500	CY
613(CC)	7187 TYPE B4 CULVERT END TREATMENT	2.000	EA
613(D)	0690 24" CORR. GALV. STEEL PIPE	42.000	LF
SECTION NO. 0002	BRIDGE 'A' - BRO-104D(35)CO		
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	40.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	50.000	CY
503(B)	6144 PRESTRESSED CONCRETE DOUBLE TEE	817.500	LF
504(E)	1380 CONCRETE RAIL (TR1)	331.000	LF
509(A)	1326 CLASS AA CONCRETE	108.700	CY
509(B)	1328 CLASS A CONCRETE	64.100	CY
511(A)	1332 REINFORCING STEEL	26,370.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	310.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	310.000	LF
516(A)	6093 DRILLED SHAFTS 42" DIAMETER	92.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	395.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	125.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	STAKING - BRO-104D(35)CO		
642	0098 STAKING	1.000	LSUM
SECTION NO. 0004	CONSTRUCTION - BRO-104D(35)CO		
641	1399 MOBILIZATION	1.000	LSUM

CALL ORDER : 021
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : BEAVER

CONTRACT ID : 050725
 PCN : 2121104
 PROJECTS : BRF-104C(037)CO
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 9.75
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES COUNTY ROAD: OVER HOME CREEK, 4.0
 MILES SOUTH AND 1.5 MILES WEST OF BEAVER. PROJECT LENGTH =
 0.236 MILES FLEXIBLE ESALS = 0.1 MILLION ASPHALT GRADE = PG
 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 ROADWAY - BRF104C(37)CO			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,600.000	LF
227	0100 TEMPORARY SILT DIKE	100.000	LF
230(A)	2806 SOLID SLAB SODDING	4,850.000	SY
232(D)	2816 WATERING	388.000	MGAL
233(A)	2817 VEGETATIVE MULCHING	1.000	AC
234(A)	2824 FERTILIZING (10-20-10)	0.490	TON
403(A)	0217 TRAFFIC BOUND SURFACE COURSE TYPE A	26.000	TON
407	0250 TACK COAT	160.000	GAL
408	5774 PRIME COAT	492.000	GAL
411(S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	685.000	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	336.000	TON
509(D)	0325 CLASS C CONCRETE	10.000	CY
613(CC)	7187 TYPE B4 CULVERT END TREATMENT	4.000	EA
613(D)	0690 24" CORR. GALV. STEEL PIPE	120.000	LF
629(E)	5048 REMOVE AND RESET MAILBOX	1.000	EA
854(A)	8800 TRAFFIC STRIPE(PAINT)(4" WIDE)	2,550.000	LF
SECTION NO. 0002 BRIDGE - BRF-104C(37)CO			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	84.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	82.000	CY
503(A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	416.670	LF
504(E)	1380 CONCRETE RAIL (TR1)	275.000	LF
506(A)	1322 STRUCTURAL STEEL	1,810.000	LB
509(A)	1326 CLASS AA CONCRETE	80.600	CY
509(B)	1328 CLASS A CONCRETE	53.800	CY
511(A)	1332 REINFORCING STEEL	25,420.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	148.000	LF
514(A)	6011 PILES, FURNISHED (HP 12X53)	470.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	148.000	LF
514(B)	6294 PILES, DRIVEN (HP 12X53)	470.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	620.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	210.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA

CALL ORDER : 021
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : BEAVER

CONTRACT ID : 050725
 PCN : 2121104
 PROJECTS : BRF-104C(037)CO
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 9.75
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	BRIDGE - BRF-104C(37)CO		
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	STAKING - BRF-104C(37)CO		
642 0098	STAKING	1.000	LSUM
SECTION NO. 0004	CONSTRUCTION - BRF-104C(37)CO		
641 1399	MOBILIZATION	1.000	LSUM

CALL ORDER : 022
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 050726
 PCN : 2120904C
 PROJECTS : BRO-104D(035)CO
 BRF-104C(037)CO
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 20.59
 CALENDAR DAYS : 120
 RES. ENG.:
 LIQ. DAM.: \$ 750

COUNTIES : BEAVER

CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES COUNTY ROAD: AT VARIOUS LOCATIONS IN
 BEAVER COUNTY. PROJECT LENGTH = 0.500 MILES FLEXIBLE ESALS
 = 0.1 MILLION ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY - BRO-104D(35)CO			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,000.000	LF
227	0100 TEMPORARY SILT DIKE	400.000	LF
230(A)	2806 SOLID SLAB SODDING	7,600.000	SY
232(D)	2816 WATERING	608.000	MGAL
233(A)	2817 VEGETATIVE MULCHING	1.430	AC
234(A)	2824 FERTILIZING (10-20-10)	0.760	TON
403(A)	0217 TRAFFIC BOUND SURFACE COURSE TYPE A	751.000	TON
509(D)	0325 CLASS C CONCRETE	43.500	CY
613(CC)	7187 TYPE B4 CULVERT END TREATMENT	2.000	EA
613(D)	0690 24" CORR. GALV. STEEL PIPE	42.000	LF
SECTION NO. 0002 BRIDGE 'A' - BRO-104D(35)CO			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	40.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	50.000	CY
503(B)	6144 PRESTRESSED CONCRETE DOUBLE TEE	817.500	LF
504(E)	1380 CONCRETE RAIL (TR1)	331.000	LF
509(A)	1326 CLASS AA CONCRETE	108.700	CY
509(B)	1328 CLASS A CONCRETE	64.100	CY
511(A)	1332 REINFORCING STEEL	26,370.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	310.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	310.000	LF
516(A)	6093 DRILLED SHAFTS 42" DIAMETER	92.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	395.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	125.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAKING - BRO-104D(35)CO			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 022
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 050726
 PCN : 2120904C
 PROJECTS : BRO-104D(035)CO
 BRF-104C(037)CO
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 20.59
 CALENDAR DAYS : 120
 RES. ENG.:
 LIQ. DAM.: \$ 750

COUNTIES : BEAVER

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0004 MOBILIZATION - BRO-104D(35)CO			
641	1399 MOBILIZATION	1.000	LSUM
SECTION NO. 0005 ROADWAY - BRF104C(37)CO			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,600.000	LF
227	0100 TEMPORARY SILT DIKE	100.000	LF
230(A)	2806 SOLID SLAB SODDING	4,850.000	SY
232(D)	2816 WATERING	388.000	MGAL
233(A)	2817 VEGETATIVE MULCHING	1.000	AC
234(A)	2824 FERTILIZING (10-20-10)	0.490	TON
403(A)	0217 TRAFFIC BOUND SURFACE COURSE TYPE A	26.000	TON
407	0250 TACK COAT	160.000	GAL
408	5774 PRIME COAT	492.000	GAL
411(S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	685.000	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	336.000	TON
509(D)	0325 CLASS C CONCRETE	10.000	CY
613(CC)	7187 TYPE B4 CULVERT END TREATMENT	4.000	EA
613(D)	0690 24" CORR. GALV. STEEL PIPE	120.000	LF
629(E)	5048 REMOVE AND RESET MAILBOX	1.000	EA
854(A)	8800 TRAFFIC STRIPE(PAINT)(4" WIDE)	2,550.000	LF
SECTION NO. 0006 BRIDGE - BRF-104C(37)CO			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	84.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	82.000	CY
503(A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	416.670	LF
504(E)	1380 CONCRETE RAIL (TR1)	275.000	LF
506(A)	1322 STRUCTURAL STEEL	1,810.000	LB
509(A)	1326 CLASS AA CONCRETE	80.600	CY
509(B)	1328 CLASS A CONCRETE	53.800	CY
511(A)	1332 REINFORCING STEEL	25,420.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	148.000	LF
514(A)	6011 PILES, FURNISHED (HP 12X53)	470.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	148.000	LF
514(B)	6294 PILES, DRIVEN (HP 12X53)	470.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	620.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	210.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 022
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 050726
 PCN : 2120904C
 PROJECTS : BRO-104D(035)CO
 BRF-104C(037)CO
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 20.59
 CALENDAR DAYS : 120
 RES. ENG.:
 LIQ. DAM.: \$ 750

COUNTIES : BEAVER

SECTION NO. 0007	STAKING - BRF-104C(37)CO		
642	0098	STAKING	1.000 LSUM
SECTION NO. 0008	CONSTRUCTION - BRF-104C(37)CO		
641	1399	MOBILIZATION	1.000 LSUM

CALL ORDER : 040
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : BECKHAM

CONTRACT ID : 050684
 PCN : 2051304
 PROJECTS : BRO-105D(078)CO
 DBE GOALS : 4.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 9.75
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES COUNTY ROAD (EW-111): OVER WEST
 BUFFALO CREEK, APPROX. 13.5 MILES NORTH & 1.3 MILES WEST OF
 ERICK. PROJECT LENGTH = 0.142 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
202(G) 0185	EARTHWORK	1.000	LSUM
223 2801	TEMPORARY SILT FENCE	1,045.000	LF
230(A) 2806	SOLID SLAB SODDING	6,765.000	SY
233(A) 2817	VEGETATIVE MULCHING	1.400	AC
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	437.000	TON
509(D) 0325	CLASS C CONCRETE	76.000	CY
SECTION NO. 0002 BRIDGE			
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	88.000	CY
501(D) 6353	UNCLASSIFIED BACKFILL	90.000	CY
503(A) 1312	PRESTRESSED CONCRETE BEAMS (TYPE III)	256.170	LF
504(E) 1380	CONCRETE RAIL (TR1)	195.160	LF
506(A) 1322	STRUCTURAL STEEL	1,800.000	LB
509(A) 1326	CLASS AA CONCRETE	51.300	CY
509(B) 1328	CLASS A CONCRETE	58.400	CY
511(A) 1332	REINFORCING STEEL	19,898.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	520.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	520.000	LF
601(A-1) 1353	TYPE I-A PLAIN RIPRAP	450.000	TON
601(A-2) 1355	TYPE I-A FILTER BLANKET	110.000	TON
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAKING			
642 0098	STAKING	1.000	LSUM
SECTION NO. 0004 CONSTRUCTION			
641 1399	MOBILIZATION	1.000	LSUM

CALL ORDER : 100
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : CANADIAN

CONTRACT ID : 050687
 PCN : 2156904
 PROJECTS : BRO-109D(092)CO
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 7.59
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE & APPROACHES COUNTY ROAD: OVER TRIBUTARY OF NORTH
 CANADIAN RIVER, APPROX. 2.5 MILE NORTH AND 1.6 MILE EAST OF
 GEARY. PROJECT LENGTH = 0.207 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	3,460.000	CY
202(C)	0184 UNCLASSIFIED BORROW	1,828.000	CY
222	2801 TEMPORARY BALE BARRIER	150.000	LF
223	2801 TEMPORARY SILT FENCE	2,040.000	LF
227	0100 TEMPORARY SILT DIKE	220.000	LF
230(A)	2806 SOLID SLAB SODDING	6,000.000	SY
233(A)	2817 VEGETATIVE MULCHING	2.500	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	538.000	TON
509(D)	0325 CLASS C CONCRETE	10.000	CY
601(A)	0297 TYPE I PLAIN RIPRAP	110.000	TON
602(C)	4155 FILTER FABRIC	240.000	SY
613(D)	0690 24" CORR. GALV. STEEL PIPE	56.000	LF
613(M)	5730 24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
SECTION NO. 0002 BRIDGE 'A'			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	96.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	114.000	CY
503(A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	356.170	LF
504(E)	1380 CONCRETE RAIL (TR1)	253.180	LF
506(A)	1322 STRUCTURAL STEEL	2,020.000	LB
509(A)	1326 CLASS AA CONCRETE	70.000	CY
509(B)	1328 CLASS A CONCRETE	63.800	CY
511(A)	1332 REINFORCING STEEL	24,630.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	516.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	516.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	650.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	190.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	5686 GUARD RAIL ANCHOR UNIT (TYPE D-BF)	1.000	EA
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	3.000	EA
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 100
LETTING DATE : January 19, 2006
LETTING TIME : 10:30 A.M.
COUNTIES : CANADIAN

CONTRACT ID : 050687
PCN : 2156904
PROJECTS : BRO-109D(092)CO
DBE GOALS : 5.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : 7.59
CALENDAR DAYS : 90
RES. ENG.:
LIQ. DAM.: \$ 500

SECTION NO. 0004 CONSTRUCTION

641 1399 MOBILIZATION

1.000 LSUM

CALL ORDER : 115
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 050736
 PCN : 1885104
 PROJECTS : ACNHY-22N(75)GB
 ACNHY-22N (76) GB
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 121.38
 CALENDAR DAYS : 300
 RES. ENG.:
 LIQ. DAM.: \$ 2000

COUNTIES : CHOCTAW

CONTRACT DESCRIPTION:

GRADE, DRAIN, SURFACE AND BRIDGE US-70: BEGIN 5.4 MILES
 EAST OF SH-147 AND EXTEND EAST IN FORT TOWSON. PROJECT
 LENGTH = 1.426 MILES ASPHALT GRADE = PG 64-22 OK, PG 70-28
 OK FLEXIBLE ESALS = 7.89 MILLION

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	ROADWAY ACNHY-22N(75)GB		
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	45,563.000	CY
202(C)	0184 UNCLASSIFIED BORROW	53,482.000	CY
202(F)	0189 PRESPLITTING OF ROCK	943.000	F DR
202(H)	6391 (PL)EMBANKMENT SURCHARGE	6,461.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	4,096.000	LF
224	2803 TEMPORARY SEDIMENT FILTER	14.000	EA
225	2804 TEMPORARY SEDIMENT BASIN	6.000	EA
227	0100 TEMPORARY SILT DIKE	1,360.000	LF
229	4318 DITCH LINER PROTECTION	2,059.000	LF
230(A)	2806 SOLID SLAB SODDING	8,138.000	SY
230(D)	2810 BROADCAST SPRIGGING (METHOD A)	36,506.000	SY
230(F)	2812 WATERING	744.000	MGAL
234(A)	2824 FERTILIZING (10-20-10)	4.000	TON
241	2832 MOWING	9.000	AC
303	0192 AGGREGATE BASE	15,037.000	CY
325	5271 SEPARATOR FABRIC	74,232.000	SY
326(B)	4210 (SP)LIME	2,084.000	TON
326(F)	4250 (SP)LIME STABILIZED SUBGRADE	64,878.000	SY
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	4,045.000	TON
407	0250 TACK COAT	14,284.000	GAL
408	5774 PRIME COAT	21,037.000	GAL
411(S2)	5930 (SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	17,057.000	TON
411(S3)	5935 (SP)ASPH.CONC.,TYPE S3(PG 76-28 OK)	13,468.000	TON
411(S4)	5950 (SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	8,760.000	TON
413(A)	4861 RUMBLE STRIP-METHOD AC-CON	7,269.000	LF
420(A)	4242 FABRIC REINFORCEMENT	2,364.000	SY
501(A)	0313 STRUCTURAL EXCAVATION UNCLASSIFIED	22.000	CY
509(B)	0321 CLASS A CONCRETE	123.200	CY
509(D)	0325 CLASS C CONCRETE	288.000	CY
510(A)	6333 RETAINING WALL	220.000	SY
511(A)	0332 REINFORCING STEEL	8,897.000	LB
601(A)	0533 TYPE I PLAIN RIPRAP	1,313.000	CY
601(E)	6312 FILTER FABRIC (RIPRAP)	1,707.000	SY

CALL ORDER : 115
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 050736
 PCN : 1885104
 PROJECTS : ACNHY-22N(75)GB
 ACNHY-22N (76) GB
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 121.38
 CALENDAR DAYS : 300
 RES. ENG.:
 LIQ. DAM.: \$ 2000

COUNTIES : CHOCTAW

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADWAY ACNHY-22N(75)GB		
609(B) 1525	2'-8" COMB.CRB.& GUT.(6" BARRIER)	6,468.000	LF
610(A) 0602	4" CONCRETE SIDEWALK	3,242.000	SY
610(B) 0399	6" CONCRETE DRIVEWAY (H.E.S.)	563.000	SY
611(A) 2657	MANHOLE (4' DIA.)	5.000	EA
611(B) 2680	ADD'L.DEPTH IN MANHOLE (4' DIA.)	23.000	VF
611(D) 4215	MANHOLE FRAME & COVER	19.000	EA
611(E) 5952	INLET W/SMALL JCT.BOX,CICI-JB-1,DES.1(A)	3.000	EA
611(E) 5954	INLET W/SMALL JCT.BOX,CICI-JB-1,DES.1(B)	4.000	EA
611(E) 5956	INLET W/SMALL JCT.BOX,CICI-JB-1,DES.1(C)	4.000	EA
611(E) 6000	INLET (SMD-TYPE 1)	1.000	EA
611(E) 7080	INLET W/SMALL JCT.BOX,CICI-JB-1,DES.1(D)	2.000	EA
611(E) 7083	INLET W/SMALL JCT.BOX,CICI-JB-1,DES.2(C)	1.000	EA
611(F) 5950	INLET W/SJB,CICI-JB-1,DES.1(ADD.DPTH)	14.300	VF
611(G) 4489	INLET FRM&GRT (SSIF-FRM,CIG-GRT-RVG-F)	15.000	EA
611(K) 4488	CAST IRON CURB INLETS	49.000	EA
613(B) 0491	18" R.C.PIPE CLASS III	1,732.000	LF
613(B) 0492	24" R.C.PIPE CLASS III	214.000	LF
613(B) 4504	19" X 30" R.C.PIPE ELL. CLASS HE-III	54.000	LF
613(C) 5157	SP. END SECTION OF 19" X 30" RCP ELL.	2.000	EA
613(D) 0689	18" CORR. GALV. STEEL PIPE	67.000	LF
613(D) 0690	24" CORR. GALV. STEEL PIPE	132.000	LF
613(D) 4527	21" X 15" CORR. GALV. STEEL PIPE ARCH	104.000	LF
613(M) 4504	21" X 15" PREFAB. CULVERT END SEC., ARCH	6.000	EA
613(M) 5726	18" PREFAB. CULVERT END SEC., ROUND	7.000	EA
613(M) 5730	24" PREFAB. CULVERT END SEC., ROUND	6.000	EA
613(S) 1180	TRENCH EXCAVATION	756.000	CY
613(T) 1181	STANDARD BEDDING MATERIAL	581.000	CY
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 4725	REMOVAL OF FENCE	639.000	LF
619(B) 4726	REMOVAL OF CURB AND GUTTER	4,329.000	LF
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	9,640.000	SY
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	29,902.000	SY
619(B) 4766	REMOVAL OF CONCRETE DRIVEWAY	110.000	SY
619(B) 4780	REMOVAL OF GUARD RAIL	1,341.000	LF
619(B) 4792	REMOVAL OF SIDEWALK	739.000	SY
619(B) 5113	REMOVAL OF RIPRAP	446.000	SY
619(C) 0924	SAWING PAVEMENT	9,309.000	LF
622(A) 4746	PIPE RAILING	262.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	571.000	LF
623(E) 7113	BEAM GUARD RAIL-THRIE-BEAM TRANS. SECT.	4.000	EA
623(E) 7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	4.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	4.000	EA

CALL ORDER : 115
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 050736
 PCN : 1885104
 PROJECTS : ACNHY-22N(75)GB
 ACNHY-22N (76) GB
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 121.38
 CALENDAR DAYS : 300
 RES. ENG.:
 LIQ. DAM.: \$ 2000

COUNTIES : CHOCTAW

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADWAY ACNHY-22N(75)GB		
653(A) 5915	EDGE DRAIN CONDUIT-PERFORATED	5,920.000	LF
653(B) 5916	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	217.000	LF
653(C) 5946	OUTLET LATERAL HEADWALL	7.000	EA
SECTION NO. 0002	BRIDGE 'A' ACNHY-22N(75)GB		
202(A) 1301	UNCLASSIFIED EXCAVATION	590.000	CY
501(A) 1306	STRUCTURAL EXCAVATION UNCLASSIFIED	154.000	CY
508(A) 6335	REMOVAL OF CULVERT END	2.000	EA
509(B) 1328	CLASS A CONCRETE	382.600	CY
511(A) 1332	REINFORCING STEEL	59,590.000	LB
SECTION NO. 0003	TRAFFIC ACNHY-22N(75)GB		
627(G) 4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	2,210.000	LF
627(H) 5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	5,080.000	LF
850(A) 8110	SHEET ALUMINUM SIGNS	590.000	SF
851(C) 8321	1 3/4" SQUARE TUBE POST	26.000	LF
851(C) 8327	2 1/4" SQUARE TUBE POST	923.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	49,526.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	40.000	EA
855(B) 8824	TRAFFIC STRIPE(PLASTIC)(SYMBOLS)	1.000	EA
856(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	73,360.000	LF
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	46,546.000	LF
871 8705	(PL)CONST.ZONE IMPACT ATTEN.	792.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	4,800.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	10,092.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,600.000	SD
880(C) 8842	BARRICADES(TYPE III)	13,428.000	SD
880(C) 8845	BARRICADES(TYPE III)	15.000	EA
880(C) 8848	WING BARRICADES	600.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	26,856.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	43,800.000	SD
880(F) 8878	DRUMS	43,800.000	SD
880(G) 8887	TUBE CHANNELIZERS	83.000	EA
890(A) 8722	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
SECTION NO. 0004	STAKING ACNHY-22N(75)GB		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 115
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 050736
 PCN : 1885104
 PROJECTS : ACNHY-22N(75)GB
 ACNHY-22N (76) GB
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 121.38
 CALENDAR DAYS : 300
 RES. ENG.:
 LIQ. DAM.: \$ 2000

COUNTIES : CHOCTAW

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005 CONSTRUCTION ACNHY-22N(75)GB			
640	1426 FIELD OFFICE	1.000	EA
641	1552 MOBILIZATION	1.000	LSUM
643	0087 (SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
SECTION NO. 0006 BRIDGE "B" ACHNY-22N(76)GB			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	192.000	CY
501(F)	6352 GRANULAR BACKFILL	200.000	CY
503(A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	1,672.700	LF
504(A)	1304 APPROACH SLAB	365.200	SY
504(E)	6245 CONCRETE RAIL (TR4)	501.500	LF
504(H)	6390 RAPID CURE JOINT SEALANT	210.750	LF
506(A)	1322 STRUCTURAL STEEL	2,274.000	LB
509(A)	1326 CLASS AA CONCRETE	555.100	CY
509(B)	1328 CLASS A CONCRETE	202.000	CY
511	6306 (PL)MECHANICAL SPLICES	88.000	EA
511(B)	6010 EPOXY COATED REINFORCING STEEL	119,795.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	1,032.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	1,032.000	LF
514(F)	6354 PILE LOAD TEST (DYNAMIC)	24.000	EA
515(A)	6013 WATER REPELLENT (VISUALLY INSPECTED)	1,054.000	SY
516(A)	6094 DRILLED SHAFTS 48" DIAMETER	673.600	LF
523(A)	6550 (SP) SEALER CRACK PREPARATION	328.700	LF
523(B)	6560 (SP) SEALER RESIN	2.000	GAL
535	6164 (PL)FIXED BEARING ASSEMBLY	48.000	EA
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	2,270.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	568.000	TON
613(P)	6204 6" PERFORATED PIPE UNDERDRAIN ROUND	170.000	LF
613(Q)	6207 6" NON-PERF.PIPE UNDERDRAIN RND.	60.000	LF
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

CALL ORDER : 120
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : CHOCTAW

CONTRACT ID : 050506
 PCN : 1885504
 PROJECTS : BRFY-022N(108)
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 110.54
 CALENDAR DAYS : 300
 RES. ENG.:
 LIQ. DAM.: \$ 2000

CONTRACT DESCRIPTION:

GRADE, DRAIN, BRIDGE AND SURFACING US-70: OVER ROCK AND BIRD CREEK, APPROXIMATELY 2 MILES WEST OF FORT TOWSON.
 PROJECT LENGTH = 1.794 MILES FLEXIBLE ESALS = 8.9 MILLION
 ASPHALT GRADE = PG 64-22 OK, PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADWAY		
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	62,842.300	CY
202(B)	0182 ROCK EXCAVATION	377.700	CY
202(C)	0184 UNCLASSIFIED BORROW	39,048.800	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	3,380.000	LF
224	2803 TEMPORARY SEDIMENT FILTER	4.000	EA
225	2804 TEMPORARY SEDIMENT BASIN	2.000	EA
227	0100 TEMPORARY SILT DIKE	3,225.000	LF
229	4318 DITCH LINER PROTECTION	480.000	LF
230(A)	2806 SOLID SLAB SODDING	48,766.600	SY
232(B)	2814 SEEDING METHOD B	34.500	AC
233(A)	2817 VEGETATIVE MULCHING	34.500	AC
234(A)	4406 FERTILIZING (0-46-0)	2.600	TON
241	2832 MOWING	34.500	AC
303	0192 AGGREGATE BASE	8,914.300	CY
325	5271 SEPARATOR FABRIC	77,880.300	SY
326(B)	4210 (SP)LIME	747.800	TON
326(F)	4250 (SP)LIME STABILIZED SUBGRADE	41,576.700	SY
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	4,405.000	TON
407	0250 TACK COAT	5,645.700	GAL
408	5774 PRIME COAT	11,534.800	GAL
411(S2)	5930 (SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	12,275.400	TON
411(S3)	5935 (SP)ASPH.CONC.,TYPE S3(PG 76-28 OK)	7,704.300	TON
411(S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	1,704.700	TON
411(S4)	5950 (SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	5,204.700	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	1,614.400	TON
413(A)	4861 RUMBLE STRIP-METHOD AC-CON	14,610.000	LF
417	5267 COLD MILLING PAVEMENT	1,428.100	SY
501(A)	0313 STRUCTURAL EXCAVATION UNCLASSIFIED	58.700	CY
509(B)	0321 CLASS A CONCRETE	127.700	CY
509(C)	0322 CLASS A CONCRETE FOR SMALL STRUCTURES	3.500	CY
509(D)	0325 CLASS C CONCRETE	94.800	CY
511(A)	0332 REINFORCING STEEL	18,402.000	LB
601(A-1)	0536 TYPE I-A PLAIN RIPRAP	48.700	TON
601(A-2)	0538 TYPE I-A FILTER BLANKET	19.500	TON

CALL ORDER : 120
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : CHOCTAW

CONTRACT ID : 050506
 PCN : 1885504
 PROJECTS : BRFY-022N(108)
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 110.54
 CALENDAR DAYS : 300
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
611(E) 6002	INLET (SMD-TYPE 2)	4.000	EA
611(J) 0487	JUNCTION BOXES	95.600	CF
611(L) 4210	DROP INLET GRATE (SMD-TYPE 2)	4.000	EA
613(B) 0491	18" R.C.PIPE CLASS III	332.000	LF
613(CC) 7196	TYPE A6 CULVERT END TREATMENT	4.000	EA
613(CC) 7197	TYPE B6 CULVERT END TREATMENT	2.000	EA
613(D) 4527	21" X 15" CORR. GALV. STEEL PIPE ARCH	160.000	LF
613(D) 4528	28" X 20" CORR. GALV. STEEL PIPE ARCH	130.000	LF
613(D) 4529	35" X 24" CORR. GALV. STEEL PIPE ARCH	15.000	LF
613(M) 4516	28" X 20" PREFAB. CULVERT END SEC., ARCH	6.000	EA
613(M) 4522	35" X 24" PREFAB. CULVERT END SEC., ARCH	1.000	EA
613(M) 5726	18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
613(P) 1091	6" PERFORATED PIPE UNDERDRAIN ROUND	500.000	LF
613(Q) 1096	6" NON-PERF.PIPE UNDERDRAIN RND.	500.000	LF
613(R) 1100	PIPE UNDERDRAIN COVER MAT'L.	50.000	CY
613(S) 1180	TRENCH EXCAVATION	118.000	CY
613(T) 1181	STANDARD BEDDING MATERIAL	94.900	CY
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 0291	REMOVAL OF HEADWALL	8.000	EA
619(B) 4725	REMOVAL OF FENCE	5,627.000	LF
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	32,598.000	SY
619(B) 4780	REMOVAL OF GUARD RAIL	1,388.000	LF
619(B) 5918	REMOVAL OF EXISTING PIPE	204.000	LF
619(C) 0924	SAWING PAVEMENT	3,914.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	1,980.000	LF
623(E) 7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	12.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	8.000	EA
624(C) 4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	5,115.000	LF
624(D) 4292	FENCE-STYLE CLF (6'HIGH, CLASS A)	989.000	LF
624(E) 5962	GATES-STYLE CLF (6'HIGH X 14'LONG)	2.000	EA
629(E) 5048	REMOVE AND RESET MAILBOX	2.000	EA
SECTION NO. 0002 BRIDGE 'A'			
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	210.000	CY
501(G) 6309	CLSM BACKFILL	234.000	CY
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	398.670	LF
504(A) 1304	APPROACH SLAB	315.700	SY
504(C) 6250	SEALED EXPANSION JOINT	40.230	LF
504(F) 6190	42" F-SHAPED PARAPET	342.000	LF
506(A) 1322	STRUCTURAL STEEL	500.000	LB
509(A) 1326	CLASS AA CONCRETE	112.900	CY
509(B) 1328	CLASS A CONCRETE	108.400	CY

CALL ORDER : 120
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : CHOCTAW

CONTRACT ID : 050506
 PCN : 1885504
 PROJECTS : BRFY-022N(108)
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 110.54
 CALENDAR DAYS : 300
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0002 BRIDGE 'A'			
511(B) 6010	EPOXY COATED REINFORCING STEEL	38,140.000	LB
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	559.000	SY
516(A) 6090	DRILLED SHAFTS 24" DIAMETER	56.000	LF
516(A) 6091	DRILLED SHAFTS 30" DIAMETER	96.000	LF
535 6164	(PL)FIXED BEARING ASSEMBLY	4.000	EA
535 6165	(PL)EXPANSION BEARING ASSEMBLY	4.000	EA
601(A-1)1353	TYPE I-A PLAIN RIPRAP	1,420.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	320.000	TON
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	86.000	LF
613(Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	52.000	LF
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
SECTION NO. 0003 BRIDGE 'B'			
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	210.000	CY
501(G) 6309	CLSM BACKFILL	234.000	CY
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	398.670	LF
504(A) 1304	APPROACH SLAB	315.700	SY
504(C) 6250	SEALED EXPANSION JOINT	40.230	LF
504(F) 6190	42" F-SHAPED PARAPET	342.000	LF
506(A) 1322	STRUCTURAL STEEL	500.000	LB
509(A) 1326	CLASS AA CONCRETE	112.900	CY
509(B) 1328	CLASS A CONCRETE	108.000	CY
511(B) 6010	EPOXY COATED REINFORCING STEEL	38,140.000	LB
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	559.000	SY
516(A) 6090	DRILLED SHAFTS 24" DIAMETER	72.000	LF
516(A) 6091	DRILLED SHAFTS 30" DIAMETER	144.000	LF
535 6164	(PL)FIXED BEARING ASSEMBLY	4.000	EA
535 6165	(PL)EXPANSION BEARING ASSEMBLY	4.000	EA
601(A-1)1353	TYPE I-A PLAIN RIPRAP	1,120.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	250.000	TON
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	86.000	LF
613(Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	52.000	LF
SECTION NO. 0004 BRIDGE 'C'			
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	230.000	CY
501(G) 6309	CLSM BACKFILL	218.000	CY
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	498.340	LF
504(A) 1304	APPROACH SLAB	353.400	SY
504(C) 6250	SEALED EXPANSION JOINT	51.000	LF
504(F) 6190	42" F-SHAPED PARAPET	322.900	LF
506(A) 1322	STRUCTURAL STEEL	620.000	LB

CALL ORDER : 120
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : CHOCTAW

CONTRACT ID : 050506
 PCN : 1885504
 PROJECTS : BRFY-022N(108)
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 110.54
 CALENDAR DAYS : 300
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0004	BRIDGE 'C'		
509(A) 1326	CLASS AA CONCRETE	143.600	CY
509(B) 1328	CLASS A CONCRETE	124.500	CY
511(B) 6010	EPOXY COATED REINFORCING STEEL	44,560.000	LB
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	594.000	SY
516(A) 6090	DRILLED SHAFTS 24" DIAMETER	70.000	LF
516(A) 6091	DRILLED SHAFTS 30" DIAMETER	156.000	LF
535 6164	(PL)FIXED BEARING ASSEMBLY	5.000	EA
535 6165	(PL)EXPANSION BEARING ASSEMBLY	5.000	EA
601(A-1)1353	TYPE I-A PLAIN RIPRAP	1,280.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	285.000	TON
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	108.000	LF
613(Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	52.000	LF
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
SECTION NO. 0005	BRIDGE 'D'		
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	200.000	CY
501(G) 6309	CLSM BACKFILL	168.000	CY
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	398.670	LF
504(A) 1304	APPROACH SLAB	273.400	SY
504(C) 6250	SEALED EXPANSION JOINT	39.000	LF
504(F) 6190	42" F-SHAPED PARAPET	322.900	LF
506(A) 1322	STRUCTURAL STEEL	470.000	LB
509(A) 1326	CLASS AA CONCRETE	111.200	CY
509(B) 1328	CLASS A CONCRETE	104.600	CY
511(B) 6010	EPOXY COATED REINFORCING STEEL	37,600.000	LB
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	498.000	SY
516(A) 6090	DRILLED SHAFTS 24" DIAMETER	78.000	LF
516(A) 6091	DRILLED SHAFTS 30" DIAMETER	138.000	LF
535 6164	(PL)FIXED BEARING ASSEMBLY	4.000	EA
535 6165	(PL)EXPANSION BEARING ASSEMBLY	4.000	EA
601(A-1)1353	TYPE I-A PLAIN RIPRAP	1,010.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	225.000	TON
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	84.000	LF
613(Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	52.000	LF
SECTION NO. 0006	TRAFFIC		
850(A) 8110	SHEET ALUMINUM SIGNS	87.500	SF
851(C) 8327	2 1/4" SQUARE TUBE POST	168.000	LF
855(A) 8812	TRAFFIC STRIPE (PLASTIC) (4" WIDE)	4,990.000	LF
856(A) 8839	CONSTRUCTION TRAFF.STR. (PAINT) (4" WIDE)	54,980.000	LF
856(C) 8851	REMOVABLE PAVEMENT MARKING TAPE (4" WIDE)	39,800.000	LF

CALL ORDER : 120
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : CHOCTAW

CONTRACT ID : 050506
 PCN : 1885504
 PROJECTS : BRFY-022N(108)
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 110.54
 CALENDAR DAYS : 300
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0006 TRAFFIC			
856(G) 8887	(PL)CONST.ZONE PAV.MKRS (FLEX TAB) TYP.2-1	1,600.000	EA
859(A) 8006	PAVEMENT MRKNG.REMOVAL (TRAF.STRP)	1,000.000	LF
870(A) 8011	SAND FILLED IMPACT ATTEN.MODULE	2.000	EA
871 8705	(PL)CONST.ZONE IMPACT ATTEN.	1,440.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	6,300.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	7,560.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	5,400.000	SD
880(C) 8830	BARRICADES (TYPE I)	1,260.000	SD
880(C) 8836	BARRICADES (TYPE II)	1,260.000	SD
880(C) 8842	BARRICADES (TYPE III)	6,840.000	SD
880(C) 8848	WING BARRICADES	900.000	SD
880(D) 8854	VERTICAL PANELS	9,000.000	SD
880(E) 8860	WARNING LIGHTS (TYPE A)	20,700.000	SD
880(E) 8872	WARNING LIGHTS (TYPE C)	6,300.000	SD
880(F) 8878	DRUMS	5,760.000	SD
890(A) 8722	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
SECTION NO. 0007 STAKING			
642 0098	STAKING	1.000	LSUM
SECTION NO. 0008 CONSTRUCTION			
640 1398	FIELD OFFICE	1.000	EA
641 1399	MOBILIZATION	1.000	LSUM

CALL ORDER : 121
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 060012
 PCN : 1885104C
 PROJECTS : ACNHY-22N(75)GB
 ACNHY-22N (76) GB
 BRFY-022N(108)
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 231.92
 CALENDAR DAYS : 450
 RES. ENG.:
 LIQ. DAM.: \$ 2000

COUNTIES : CHOCTAW

CONTRACT DESCRIPTION:

GRADE, DRAIN, SURFACE AND BRIDGE US-70: BEG 5.4 MI E. OF
 SH-147 & EXT. E. IN FORT TOWSON/ OVER ROCK & BIRD CR APPROX.
 2 MI W. OF FORT TOWSON. PROJECT LENGTH = 3.220 ASPHALT
 GRADE = PG 64-22 OK, PG 70-28 OK FLEXIBLE ESALS = 8.9
 MILLION

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADWAY ACNHY-22N(75)GB		
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	45,563.000	CY
202(C)	0184 UNCLASSIFIED BORROW	53,482.000	CY
202(F)	0189 PRESPLITTING OF ROCK	943.000	F DR
202(H)	6391 (PL)EMBANKMENT SURCHARGE	6,461.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	4,096.000	LF
224	2803 TEMPORARY SEDIMENT FILTER	14.000	EA
225	2804 TEMPORARY SEDIMENT BASIN	6.000	EA
227	0100 TEMPORARY SILT DIKE	1,360.000	LF
229	4318 DITCH LINER PROTECTION	2,059.000	LF
230(A)	2806 SOLID SLAB SODDING	8,138.000	SY
230(D)	2810 BROADCAST SPRIGGING (METHOD A)	36,506.000	SY
230(F)	2812 WATERING	744.000	MGAL
234(A)	2824 FERTILIZING (10-20-10)	4.000	TON
241	2832 MOWING	9.000	AC
303	0192 AGGREGATE BASE	15,037.000	CY
325	5271 SEPARATOR FABRIC	74,232.000	SY
326(B)	4210 (SP)LIME	2,084.000	TON
326(F)	4250 (SP)LIME STABILIZED SUBGRADE	64,878.000	SY
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	4,045.000	TON
407	0250 TACK COAT	14,284.000	GAL
408	5774 PRIME COAT	21,037.000	GAL
411(S2)	5930 (SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	17,057.000	TON
411(S3)	5935 (SP)ASPH.CONC.,TYPE S3(PG 76-28 OK)	13,468.000	TON
411(S4)	5950 (SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	8,760.000	TON
413(A)	4861 RUMBLE STRIP-METHOD AC-CON	7,269.000	LF
420(A)	4242 FABRIC REINFORCEMENT	2,364.000	SY
501(A)	0313 STRUCTURAL EXCAVATION UNCLASSIFIED	22.000	CY
509(B)	0321 CLASS A CONCRETE	123.200	CY
509(D)	0325 CLASS C CONCRETE	288.000	CY
510(A)	6333 RETAINING WALL	220.000	SY
511(A)	0332 REINFORCING STEEL	8,897.000	LB

CALL ORDER : 121
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 060012
 PCN : 1885104C
 PROJECTS : ACNHY-22N(75)GB
 ACNHY-22N (76) GB
 BRFY-022N(108)
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 231.92
 CALENDAR DAYS : 450
 RES. ENG.:
 LIQ. DAM.: \$ 2000

COUNTIES : CHOCTAW

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADWAY ACNHY-22N(75)GB		
601(A) 0533	TYPE I PLAIN RIPRAP	1,313.000	CY
601(E) 6312	FILTER FABRIC (RIPRAP)	1,707.000	SY
609(B) 1525	2'-8" COMB.CRB.& GUT.(6" BARRIER)	6,468.000	LF
610(A) 0602	4" CONCRETE SIDEWALK	3,242.000	SY
610(B) 0399	6" CONCRETE DRIVEWAY (H.E.S.)	563.000	SY
611(A) 2657	MANHOLE (4' DIA.)	5.000	EA
611(B) 2680	ADD'L.DEPTH IN MANHOLE (4' DIA.)	23.000	VF
611(D) 4215	MANHOLE FRAME & COVER	19.000	EA
611(E) 5952	INLET W/SMALL JCT.BOX,CICI-JB-1,DES.1(A)	3.000	EA
611(E) 5954	INLET W/SMALL JCT.BOX,CICI-JB-1,DES.1(B)	4.000	EA
611(E) 5956	INLET W/SMALL JCT.BOX,CICI-JB-1,DES.1(C)	4.000	EA
611(E) 6000	INLET (SMD-TYPE 1)	1.000	EA
611(E) 7080	INLET W/SMALL JCT.BOX,CICI-JB-1,DES.1(D)	2.000	EA
611(E) 7083	INLET W/SMALL JCT.BOX,CICI-JB-1,DES.2(C)	1.000	EA
611(F) 5950	INLET W/SJB,CICI-JB-1,DES.1(ADD.DPTH)	14.300	VF
611(G) 4489	INLET FRM&GRT (SSIF-FRM,CIG-GRT-RVG-F)	15.000	EA
611(K) 4488	CAST IRON CURB INLETS	49.000	EA
613(B) 0491	18" R.C.PIPE CLASS III	1,732.000	LF
613(B) 0492	24" R.C.PIPE CLASS III	214.000	LF
613(B) 4504	19" X 30" R.C.PIPE ELL. CLASS HE-III	54.000	LF
613(C) 5157	SP. END SECTION OF 19" X 30" RCP ELL.	2.000	EA
613(D) 0689	18" CORR. GALV. STEEL PIPE	67.000	LF
613(D) 0690	24" CORR. GALV. STEEL PIPE	132.000	LF
613(D) 4527	21" X 15" CORR. GALV. STEEL PIPE ARCH	104.000	LF
613(M) 4504	21" X 15" PREFAB. CULVERT END SEC., ARCH	6.000	EA
613(M) 5726	18" PREFAB. CULVERT END SEC., ROUND	7.000	EA
613(M) 5730	24" PREFAB. CULVERT END SEC., ROUND	6.000	EA
613(S) 1180	TRENCH EXCAVATION	756.000	CY
613(T) 1181	STANDARD BEDDING MATERIAL	581.000	CY
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 4725	REMOVAL OF FENCE	639.000	LF
619(B) 4726	REMOVAL OF CURB AND GUTTER	4,329.000	LF
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	9,640.000	SY
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	29,902.000	SY
619(B) 4766	REMOVAL OF CONCRETE DRIVEWAY	110.000	SY
619(B) 4780	REMOVAL OF GUARD RAIL	1,341.000	LF
619(B) 4792	REMOVAL OF SIDEWALK	739.000	SY
619(B) 5113	REMOVAL OF RIPRAP	446.000	SY
619(C) 0924	SAWING PAVEMENT	9,309.000	LF
622(A) 4746	PIPE RAILING	262.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	571.000	LF

CALL ORDER : 121
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 060012
 PCN : 1885104C
 PROJECTS : ACNHY-22N(75)GB
 ACNHY-22N (76) GB
 BRFY-022N(108)
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 231.92
 CALENDAR DAYS : 450
 RES. ENG.:
 LIQ. DAM.: \$ 2000

COUNTIES : CHOCTAW

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY ACNHY-22N(75)GB			
623(E) 7113	BEAM GUARD RAIL-THRIE-BEAM TRANS. SECT.	4.000	EA
623(E) 7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	4.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	4.000	EA
653(A) 5915	EDGE DRAIN CONDUIT-PERFORATED	5,920.000	LF
653(B) 5916	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	217.000	LF
653(C) 5946	OUTLET LATERAL HEADWALL	7.000	EA
SECTION NO. 0002 BRIDGE 'A' ACNHY-22N(75)GB			
202(A) 1301	UNCLASSIFIED EXCAVATION	590.000	CY
501(A) 1306	STRUCTURAL EXCAVATION UNCLASSIFIED	154.000	CY
508(A) 6335	REMOVAL OF CULVERT END	2.000	EA
509(B) 1328	CLASS A CONCRETE	382.600	CY
511(A) 1332	REINFORCING STEEL	59,590.000	LB
SECTION NO. 0003 TRAFFIC ACNHY-22N(75)GB			
627(G) 4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	2,210.000	LF
627(H) 5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	5,080.000	LF
850(A) 8110	SHEET ALUMINUM SIGNS	590.000	SF
851(C) 8321	1 3/4" SQUARE TUBE POST	26.000	LF
851(C) 8327	2 1/4" SQUARE TUBE POST	923.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	49,526.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	40.000	EA
855(B) 8824	TRAFFIC STRIPE(PLASTIC)(SYMBOLS)	1.000	EA
856(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	73,360.000	LF
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	46,546.000	LF
871 8705	(PL)CONST.ZONE IMPACT ATTEN.	792.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	4,800.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	10,092.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,600.000	SD
880(C) 8842	BARRICADES(TYPE III)	13,428.000	SD
880(C) 8845	BARRICADES(TYPE III)	15.000	EA
880(C) 8848	WING BARRICADES	600.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	26,856.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	43,800.000	SD
880(F) 8878	DRUMS	43,800.000	SD
880(G) 8887	TUBE CHANNELIZERS	83.000	EA
890(A) 8722	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM

CALL ORDER : 121
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 060012
 PCN : 1885104C
 PROJECTS : ACNHY-22N(75)GB
 ACNHY-22N (76) GB
 BRFY-022N(108)
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 231.92
 CALENDAR DAYS : 450
 RES. ENG.:
 LIQ. DAM.: \$ 2000

COUNTIES : CHOCTAW

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0004 STAKING ACNHY-22N(75)GB			
642	0098 STAKING	1.000	LSUM
SECTION NO. 0005 CONSTRUCTION ACNHY-22N(75)GB			
640	1426 FIELD OFFICE	1.000	EA
641	1552 MOBILIZATION	1.000	LSUM
643	0087 (SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
SECTION NO. 0006 BRIDGE "B" ACHNY-22N(76)GB			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	192.000	CY
501(F)	6352 GRANULAR BACKFILL	200.000	CY
503(A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	1,672.700	LF
504(A)	1304 APPROACH SLAB	365.200	SY
504(E)	6245 CONCRETE RAIL (TR4)	501.500	LF
504(H)	6390 RAPID CURE JOINT SEALANT	210.750	LF
506(A)	1322 STRUCTURAL STEEL	2,274.000	LB
509(A)	1326 CLASS AA CONCRETE	555.100	CY
509(B)	1328 CLASS A CONCRETE	202.000	CY
511	6306 (PL)MECHANICAL SPLICES	88.000	EA
511(B)	6010 EPOXY COATED REINFORCING STEEL	119,795.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	1,032.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	1,032.000	LF
514(F)	6354 PILE LOAD TEST (DYNAMIC)	24.000	EA
515(A)	6013 WATER REPELLENT (VISUALLY INSPECTED)	1,054.000	SY
516(A)	6094 DRILLED SHAFTS 48" DIAMETER	673.600	LF
523(A)	6550 (SP) SEALER CRACK PREPARATION	328.700	LF
523(B)	6560 (SP) SEALER RESIN	2.000	GAL
535	6164 (PL)FIXED BEARING ASSEMBLY	48.000	EA
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	2,270.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	568.000	TON
613(P)	6204 6" PERFORATED PIPE UNDERDRAIN ROUND	170.000	LF
613(Q)	6207 6" NON-PERF.PIPE UNDERDRAIN RND.	60.000	LF
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
SECTION NO. 0007 ROADWAY - BRFY-22N(108)			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	62,842.300	CY
202(B)	0182 ROCK EXCAVATION	377.700	CY
202(C)	0184 UNCLASSIFIED BORROW	39,048.800	CY

CALL ORDER : 121
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 060012
 PCN : 1885104C
 PROJECTS : ACNHY-22N(75)GB
 ACNHY-22N (76) GB
 BRFY-022N(108)
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 231.92
 CALENDAR DAYS : 450
 RES. ENG.:
 LIQ. DAM.: \$ 2000

COUNTIES : CHOCTAW

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0007 ROADWAY - BRFY-22N(108)			
205	4229	TYPE A-SALVAGED TOPSOIL	1.000 LSUM
223	2801	TEMPORARY SILT FENCE	3,380.000 LF
224	2803	TEMPORARY SEDIMENT FILTER	4.000 EA
225	2804	TEMPORARY SEDIMENT BASIN	2.000 EA
227	0100	TEMPORARY SILT DIKE	3,225.000 LF
229	4318	DITCH LINER PROTECTION	480.000 LF
230(A)	2806	SOLID SLAB SODDING	48,766.600 SY
232(B)	2814	SEEDING METHOD B	34.500 AC
233(A)	2817	VEGETATIVE MULCHING	34.500 AC
234(A)	4406	FERTILIZING (0-46-0)	2.600 TON
241	2832	MOWING	34.500 AC
303	0192	AGGREGATE BASE	8,914.300 CY
325	5271	SEPARATOR FABRIC	77,880.300 SY
326(B)	4210	(SP)LIME	747.800 TON
326(F)	4250	(SP)LIME STABILIZED SUBGRADE	41,576.700 SY
403(E)	0225	TRAFFIC BOUND SURFACE COURSE TYPE E	4,405.000 TON
407	0250	TACK COAT	5,645.700 GAL
408	5774	PRIME COAT	11,534.800 GAL
411(S2)	5930	(SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	12,275.400 TON
411(S3)	5935	(SP)ASPH.CONC.,TYPE S3(PG 76-28 OK)	7,704.300 TON
411(S3)	5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	1,704.700 TON
411(S4)	5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	5,204.700 TON
411(S4)	5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	1,614.400 TON
413(A)	4861	RUMBLE STRIP-METHOD AC-CON	14,610.000 LF
417	5267	COLD MILLING PAVEMENT	1,428.100 SY
501(A)	0313	STRUCTURAL EXCAVATION UNCLASSIFIED	58.700 CY
509(B)	0321	CLASS A CONCRETE	127.700 CY
509(C)	0322	CLASS A CONCRETE FOR SMALL STRUCTURES	3.500 CY
509(D)	0325	CLASS C CONCRETE	94.800 CY
511(A)	0332	REINFORCING STEEL	18,402.000 LB
601(A-1)	0536	TYPE I-A PLAIN RIPRAP	48.700 TON
601(A-2)	0538	TYPE I-A FILTER BLANKET	19.500 TON
611(E)	6002	INLET (SMD-TYPE 2)	4.000 EA
611(J)	0487	JUNCTION BOXES	95.600 CF
611(L)	4210	DROP INLET GRATE (SMD-TYPE 2)	4.000 EA
613(B)	0491	18" R.C.PIPE CLASS III	332.000 LF
613(CC)	7196	TYPE A6 CULVERT END TREATMENT	4.000 EA
613(CC)	7197	TYPE B6 CULVERT END TREATMENT	2.000 EA
613(D)	4527	21" X 15" CORR. GALV. STEEL PIPE ARCH	160.000 LF
613(D)	4528	28" X 20" CORR. GALV. STEEL PIPE ARCH	130.000 LF
613(D)	4529	35" X 24" CORR. GALV. STEEL PIPE ARCH	15.000 LF

CALL ORDER : 121
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 060012
 PCN : 1885104C
 PROJECTS : ACNHY-22N(75)GB
 ACNHY-22N (76) GB
 BRFY-022N(108)
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 231.92
 CALENDAR DAYS : 450
 RES. ENG.:
 LIQ. DAM.: \$ 2000

COUNTIES : CHOCTAW

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0007 ROADWAY - BRFY-22N(108)			
613(M) 4516	28" X 20" PREFAB. CULVERT END SEC., ARCH	6.000	EA
613(M) 4522	35" X 24" PREFAB. CULVERT END SEC., ARCH	1.000	EA
613(M) 5726	18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
613(P) 1091	6" PERFORATED PIPE UNDERDRAIN ROUND	500.000	LF
613(Q) 1096	6" NON-PERF.PIPE UNDERDRAIN RND.	500.000	LF
613(R) 1100	PIPE UNDERDRAIN COVER MAT'L.	50.000	CY
613(S) 1180	TRENCH EXCAVATION	118.000	CY
613(T) 1181	STANDARD BEDDING MATERIAL	94.900	CY
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 0291	REMOVAL OF HEADWALL	8.000	EA
619(B) 4725	REMOVAL OF FENCE	5,627.000	LF
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	32,598.000	SY
619(B) 4780	REMOVAL OF GUARD RAIL	1,388.000	LF
619(B) 5918	REMOVAL OF EXISTING PIPE	204.000	LF
619(C) 0924	SAWING PAVEMENT	3,914.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	1,980.000	LF
623(E) 7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	12.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	8.000	EA
624(C) 4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	5,115.000	LF
624(D) 4292	FENCE-STYLE CLF (6'HIGH, CLASS A)	989.000	LF
624(E) 5962	GATES-STYLE CLF (6'HIGH X 14'LONG)	2.000	EA
629(E) 5048	REMOVE AND RESET MAILBOX	2.000	EA
SECTION NO. 0008 BRIDGE 'A' - BRFY-22N(108)			
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	210.000	CY
501(G) 6309	CLSM BACKFILL	234.000	CY
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	398.670	LF
504(A) 1304	APPROACH SLAB	315.700	SY
504(C) 6250	SEALED EXPANSION JOINT	40.230	LF
504(F) 6190	42" F-SHAPED PARAPET	342.000	LF
506(A) 1322	STRUCTURAL STEEL	500.000	LB
509(A) 1326	CLASS AA CONCRETE	112.900	CY
509(B) 1328	CLASS A CONCRETE	108.400	CY
511(B) 6010	EPOXY COATED REINFORCING STEEL	38,140.000	LB
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	559.000	SY
516(A) 6090	DRILLED SHAFTS 24" DIAMETER	56.000	LF
516(A) 6091	DRILLED SHAFTS 30" DIAMETER	96.000	LF
535 6164	(PL)FIXED BEARING ASSEMBLY	4.000	EA
535 6165	(PL)EXPANSION BEARING ASSEMBLY	4.000	EA
601(A-1)1353	TYPE I-A PLAIN RIPRAP	1,420.000	TON

CALL ORDER : 121
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 060012
 PCN : 1885104C
 PROJECTS : ACNHY-22N(75)GB
 ACNHY-22N (76) GB
 BRFY-022N(108)
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 231.92
 CALENDAR DAYS : 450
 RES. ENG.:
 LIQ. DAM.: \$ 2000

COUNTIES : CHOCTAW

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0008 BRIDGE 'A' - BRFY-22N(108)			
601(A-2)1355	TYPE I-A FILTER BLANKET	320.000	TON
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	86.000	LF
613(Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	52.000	LF
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
SECTION NO. 0009 BRIDGE 'B' - BRFY-22N(108)			
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	210.000	CY
501(G) 6309	CLSM BACKFILL	234.000	CY
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	398.670	LF
504(A) 1304	APPROACH SLAB	315.700	SY
504(C) 6250	SEALED EXPANSION JOINT	40.230	LF
504(F) 6190	42" F-SHAPED PARAPET	342.000	LF
506(A) 1322	STRUCTURAL STEEL	500.000	LB
509(A) 1326	CLASS AA CONCRETE	112.900	CY
509(B) 1328	CLASS A CONCRETE	108.000	CY
511(B) 6010	EPOXY COATED REINFORCING STEEL	38,140.000	LB
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	559.000	SY
516(A) 6090	DRILLED SHAFTS 24" DIAMETER	72.000	LF
516(A) 6091	DRILLED SHAFTS 30" DIAMETER	144.000	LF
535 6164	(PL)FIXED BEARING ASSEMBLY	4.000	EA
535 6165	(PL)EXPANSION BEARING ASSEMBLY	4.000	EA
601(A-1)1353	TYPE I-A PLAIN RIPRAP	1,120.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	250.000	TON
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	86.000	LF
613(Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	52.000	LF
SECTION NO. 0010 BRIDGE 'C' - BRFY-22N(108)			
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	230.000	CY
501(G) 6309	CLSM BACKFILL	218.000	CY
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	498.340	LF
504(A) 1304	APPROACH SLAB	353.400	SY
504(C) 6250	SEALED EXPANSION JOINT	51.000	LF
504(F) 6190	42" F-SHAPED PARAPET	322.900	LF
506(A) 1322	STRUCTURAL STEEL	620.000	LB
509(A) 1326	CLASS AA CONCRETE	143.600	CY
509(B) 1328	CLASS A CONCRETE	124.500	CY
511(B) 6010	EPOXY COATED REINFORCING STEEL	44,560.000	LB
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	594.000	SY
516(A) 6090	DRILLED SHAFTS 24" DIAMETER	70.000	LF

CALL ORDER : 121
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 060012
 PCN : 1885104C
 PROJECTS : ACNHY-22N(75)GB
 ACNHY-22N (76) GB
 BRFY-022N(108)
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 231.92
 CALENDAR DAYS : 450
 RES. ENG.:
 LIQ. DAM.: \$ 2000

COUNTIES : CHOCTAW

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0010 BRIDGE 'C' - BRFY-22N(108)			
516(A) 6091	DRILLED SHAFTS 30" DIAMETER	156.000	LF
535 6164	(PL)FIXED BEARING ASSEMBLY	5.000	EA
535 6165	(PL)EXPANSION BEARING ASSEMBLY	5.000	EA
601(A-1)1353	TYPE I-A PLAIN RIPRAP	1,280.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	285.000	TON
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	108.000	LF
613(Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	52.000	LF
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
SECTION NO. 0011 BRIDGE 'D' - BRFY-22N(108)			
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	200.000	CY
501(G) 6309	CLSM BACKFILL	168.000	CY
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	398.670	LF
504(A) 1304	APPROACH SLAB	273.400	SY
504(C) 6250	SEALED EXPANSION JOINT	39.000	LF
504(F) 6190	42" F-SHAPED PARAPET	322.900	LF
506(A) 1322	STRUCTURAL STEEL	470.000	LB
509(A) 1326	CLASS AA CONCRETE	111.200	CY
509(B) 1328	CLASS A CONCRETE	104.600	CY
511(B) 6010	EPOXY COATED REINFORCING STEEL	37,600.000	LB
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	498.000	SY
516(A) 6090	DRILLED SHAFTS 24" DIAMETER	78.000	LF
516(A) 6091	DRILLED SHAFTS 30" DIAMETER	138.000	LF
535 6164	(PL)FIXED BEARING ASSEMBLY	4.000	EA
535 6165	(PL)EXPANSION BEARING ASSEMBLY	4.000	EA
601(A-1)1353	TYPE I-A PLAIN RIPRAP	1,010.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	225.000	TON
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	84.000	LF
613(Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	52.000	LF
SECTION NO. 0012 TRAFFIC - BRFY-22N(108)			
850(A) 8110	SHEET ALUMINUM SIGNS	87.500	SF
851(C) 8327	2 1/4" SQUARE TUBE POST	168.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	4,990.000	LF
856(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	54,980.000	LF
856(C) 8851	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	39,800.000	LF
856(G) 8887	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	1,600.000	EA
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	1,000.000	LF
870(A) 8011	SAND FILLED IMPACT ATTEN.MODULE	2.000	EA

CALL ORDER : 121
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 060012
 PCN : 1885104C
 PROJECTS : ACNHY-22N(75)GB
 ACNHY-22N (76) GB
 BRFY-022N(108)
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 231.92
 CALENDAR DAYS : 450
 RES. ENG.:
 LIQ. DAM.: \$ 2000

COUNTIES : CHOCTAW

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0012 TRAFFIC - BRFY-22N(108)			
871	8705 (PL)CONST.ZONE IMPACT ATTEN.	1,440.000	SD
880(B)	8818 CONSTRUCTION SIGNS 0 TO 6.25 SF	6,300.000	SD
880(B)	8821 CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	7,560.000	SD
880(B)	8824 CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	5,400.000	SD
880(C)	8830 BARRICADES (TYPE I)	1,260.000	SD
880(C)	8836 BARRICADES (TYPE II)	1,260.000	SD
880(C)	8842 BARRICADES (TYPE III)	6,840.000	SD
880(C)	8848 WING BARRICADES	900.000	SD
880(D)	8854 VERTICAL PANELS	9,000.000	SD
880(E)	8860 WARNING LIGHTS (TYPE A)	20,700.000	SD
880(E)	8872 WARNING LIGHTS (TYPE C)	6,300.000	SD
880(F)	8878 DRUMS	5,760.000	SD
890(A)	8722 (PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
SECTION NO. 0013 STAKING - BRFY-22N(108)			
642	0098 STAKING	1.000	LSUM
SECTION NO. 0014 CONSTRUCTION - BRFY-22N(108)			
640	1398 FIELD OFFICE	1.000	EA
641	1399 MOBILIZATION	1.000	LSUM

CALL ORDER : 130
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : CLEVELAND

CONTRACT ID : 050688
 PCN : 1820704
 PROJECTS : STP-114D(044)AG
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 35.76
 CALENDAR DAYS : 120
 RES. ENG.:
 LIQ. DAM.: \$ 750

CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES CITY STREET.: 12 TH AVE. OVER LITTLE RIVER, LOCATED BETWEEN TECUMSEH AND FRANKLIN ROADS IN THE CITY OF NORMAN. PROJECT LENGTH = 0.373 MILES FLEXIBLE ESALS = 0.3 MILLION ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	31,450.000	CY
205	4230 TYPE A-SALVAGED TOPSOIL	1.000	CY
223	2801 TEMPORARY SILT FENCE	2,500.000	LF
227	0100 TEMPORARY SILT DIKE	250.000	LF
230(A)	2806 SOLID SLAB SODDING	22,500.000	SY
231(D)	4566 TREES-MACHINE PLANTED	225.000	EA
231(E)	5900 (PL)ESTABLISHMENT PERIOD	1.000	LSUM
233(A)	2817 VEGETATIVE MULCHING	4.600	AC
326(B)	4210 (SP)LIME	144.900	TON
326(F)	4250 (SP)LIME STABILIZED SUBGRADE	7,666.000	SY
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	250.000	TON
407	0250 TACK COAT	826.400	GAL
408	5774 PRIME COAT	1,239.600	GAL
411(S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	3,138.700	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	925.300	TON
509(D)	0325 CLASS C CONCRETE	25.000	CY
613(B)	0492 24" R.C.PIPE CLASS III	58.000	LF
613(D)	4528 28" X 20" CORR. GALV. STEEL PIPE ARCH	222.000	LF
613(G)	4571 28" X 20" GALV. STEEL CULV. END SEC.ARCH	12.000	EA
613(M)	5730 24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
619(B)	4725 REMOVAL OF FENCE	2,386.000	LF
619(B)	4728 REMOVAL OF ASPHALT PAVEMENT	4,915.700	SY
619(C)	0924 SAWING PAVEMENT	248.200	LF
624(C)	4459 (SP)FENCE-STYLE SWF (5 BARBED WIRE)	3,733.000	LF
850(A)	8110 SHEET ALUMINUM SIGNS	22.000	SF
851(B)	3216 2"@3.65 GALV.STL.PIPE POST	67.000	LF
855(A)	8812 TRAFFIC STRIPE(PLASTIC)(4" WIDE)	8,680.000	LF
857(A)	8950 PAVE.MARKERS CLASS C TYPE 2-D	44.000	EA
SECTION NO. 0002 BRIDGE 'A'			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	330.000	CY
501(G)	6309 CLSM BACKFILL	200.000	CY
503(A)	1312 PRESTRESSED CONCRETE BEAMS (TYPE III)	728.400	LF
504(A)	1304 APPROACH SLAB	526.000	SY

CALL ORDER : 130
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : CLEVELAND

CONTRACT ID : 050688
 PCN : 1820704
 PROJECTS : STP-114D(044)AG
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 35.76
 CALENDAR DAYS : 120
 RES. ENG.:
 LIQ. DAM.: \$ 750

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	BRIDGE 'A'		
504(C) 6250	SEALED EXPANSION JOINT	61.900	LF
504(E) 6239	CONCRETE RAIL (TR3)	474.800	LF
506(A) 1322	STRUCTURAL STEEL	2,100.000	LB
509(A) 1326	CLASS AA CONCRETE	245.400	CY
509(B) 1328	CLASS A CONCRETE	204.400	CY
511(A) 1332	REINFORCING STEEL	640.000	LB
511(B) 6010	EPOXY COATED REINFORCING STEEL	90,090.000	LB
514(A) 6011	PILES, FURNISHED (HP 12X53)	1,028.000	LF
514(B) 6294	PILES, DRIVEN (HP 12X53)	1,028.000	LF
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	1,000.000	SY
516(A) 6094	DRILLED SHAFTS 48" DIAMETER	360.000	LF
523(A) 6550	(SP) SEALER CRACK PREPARATION	62.000	LF
523(B) 6560	(SP) SEALER RESIN	1.000	GAL
535 6164	(PL)FIXED BEARING ASSEMBLY	20.000	EA
535 6165	(PL)EXPANSION BEARING ASSEMBLY	10.000	EA
601(A-1)1353	TYPE I-A PLAIN RIPRAP	1,180.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	340.000	TON
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	122.000	LF
613(Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	60.000	LF
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F) 5686	GUARD RAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	4.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	STAKING		
642 0098	STAKING	1.000	LSUM
SECTION NO. 0004	CONSTRUCTION		
641 1552	MOBILIZATION	1.000	LSUM

CALL ORDER : 135
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : CLEVELAND

CONTRACT ID : 050740
 PCN : 1967804
 PROJECTS : STP-114B(070)AG
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 16.26
 CALENDAR DAYS : 45
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

INTERSECTION MODIFICATION AND TRAFFIC SIGNALS CITY STREET:
 JENKINS AVE. AND IMHOFF RD. IN NORMAN. PROJECT LENGTH = 1.
 122 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	100.000	LF
223	2801 TEMPORARY SILT FENCE	1,500.000	LF
230(A)	2806 SOLID SLAB SODDING	900.000	SY
303	0192 AGGREGATE BASE	90.000	CY
407	0250 TACK COAT	30.000	GAL
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	40.000	TON
414(B)	0288 6" H.E.S. CONCRETE PAVEMENT	210.000	SY
609(B)	1513 1'-8" COMB.CRB.& GUT.(6" BARRIER)	1,190.000	LF
610(A)	0602 4" CONCRETE SIDEWALK	90.000	SY
619(B)	4726 REMOVAL OF CURB AND GUTTER	935.000	LF
619(B)	4728 REMOVAL OF ASPHALT PAVEMENT	425.000	SY
619(B)	4792 REMOVAL OF SIDEWALK	75.000	SY
619(C)	0924 SAWING PAVEMENT	1,150.000	LF
SECTION NO. 0002 TRAFFIC SIGNALS			
802(B)	8338 1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCH	275.000	LF
802(B)	8340 2" PVC SCH.40 PLASTIC CONDUIT BORED	600.000	LF
802(B)	8342 2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	3,375.000	LF
802(B)	8344 3" PVC SCH.40 PLASTIC CONDUIT BORED	325.000	LF
802(B)	8346 3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	150.000	LF
803	8065 PULL BOX(SIZE I)	29.000	EA
803	8066 PULL BOX(SIZE II)	2.000	EA
804(A)	2915 STRUCTURAL CONCRETE	9.100	CY
804(B)	2916 REINFORCING STEEL	1,357.000	LB
806(A)	8311 32'MH POLE 35'TS & 10'LMA(G.STL.)	1.000	EA
806(A)	8312 32'MH POLE 40'TS & 10'LMA(G.STL.)	1.000	EA
806(A)	8314 32'MH POLE 50'TS & 10'LMA(G.STL.)	1.000	EA
806(B)	8896 12' MTG.HT.TS PED.POLE(G.STL.)	1.000	EA
809(A)	8090 (PL)ROADWAY LUMINAIRE	3.000	EA
810(A)	3118 SERVICE POLE	1.000	EA
811	8040 1/C NO.6 ELECT.COND.	200.000	LF
811	8044 1/C NO.10 ELECT.COND.	500.000	LF
824	8340 (PL)MASTER CONTROLLER	1.000	EA
825	8550 VEH.ACT.SOL.ST.TRAF.SIG.CON.ASM	1.000	EA

CALL ORDER : 135
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : CLEVELAND

CONTRACT ID : 050740
 PCN : 1967804
 PROJECTS : STP-114B(070)AG
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 16.26
 CALENDAR DAYS : 45
 RES. ENG.:
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0002	TRAFFIC SIGNALS		
828 (A) 8135	SOL.STE.DIGITAL IND.VEH.LP.DET.	14.000	EA
828 (B) 8138	LOOP DETECTOR WIRE	3,350.000	LF
830 8000	PEDESTRIAN PUSH BUTTON	6.000	EA
831 8231	1WAY3SEC.ADJ.SIG.HD.S-6	4.000	EA
831 8252	1WAY3SEC.ADJ.SIG.HD.S-9	2.000	EA
831 8262	1WAY3SEC.ADJ.SIG.HD.S-10	1.000	EA
831 8286	1WAY5SEC.ADJ.SIG.HD.S-19	1.000	EA
831 8295	1WAY2SEC.ADJ.PED.SIG.HD.S-20	6.000	EA
833 3030	BACKPLATE	8.000	EA
834 8358	(PL)UNDERGROUND COMMUNICATION CABLE	4,250.000	LF
834 (A) 8207	5/C TRAF.SIG.EL.CABLE	600.000	LF
834 (A) 8208	7/C TRAF.SIG.EL.CABLE	380.000	LF
834 (A) 8209	9/C TRAF.SIG.EL.CABLE	340.000	LF
834 (A) 8210	12/C TRAF.SIG.EL.CABLE	100.000	LF
834 (B) 8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	4,400.000	LF
840 (A) 8592	(PL)E.P.S. OPTICAL EMITTER	5.000	EA
840 (B) 8593	(PL)E.P.S. OPTICAL DETECTOR	3.000	EA
840 (C) 8594	(PL)E.P.S. OPTICAL DETECTOR CABLE	500.000	LF
840 (D) 8595	(PL)E.P.S. 2 CHANNEL PHASE SELECTOR	2.000	EA
850 (C) 8118	MAST ARM MOUNTED SIGNS(ALUM.)	83.000	SF
890 7700	(PL)TRAFFIC ITEMS	1.000	LSUM
890 (B) 8728	(PL)RESET OF PULL BOX	2.000	EA
SECTION NO. 0003	TRAFFIC		
850 (A) 8110	SHEET ALUMINUM SIGNS	28.500	SF
851 (B) 3216	2"@3.65 GALV.STL.PIPE POST	61.500	LF
855 (A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	5,785.000	LF
855 (B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	8.000	EA
855 (B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	4.000	EA
857 (A) 8950	PAVE.MARKERS CLASS C TYPE 2-D	65.000	EA
880 (J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890 (A) 8712	(PL)REMOVAL OF LIGHT POLE	1.000	EA
890 (A) 8724	(PL)REMOVAL OF EXISTING SIGNS	3.000	EA
SECTION NO. 0004	STAKING		
642 0098	STAKING	1.000	LSUM
SECTION NO. 0005	CONSTRUCTION		
641 1552	MOBILIZATION	1.000	LSUM

CALL ORDER : 180
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 ID
 COUNTIES : COMANCHE

CONTRACT ID : 050509
 PCN : 2031305
 PROJECTS : IMDY-44-1(089)043
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 128.97
 CALENDAR DAYS : 255
 RES. ENG.:
 LIQ. DAM.: \$ 1000

CONTRACT DESCRIPTION:
 GRADE, DRAIN, SURFACE, BRIDGE AND EROSION CONTROL I-44,
 US-62; AT ROGERS LANE AND AT GATE 2 IN FORT SILL. PROJECT
 LENGTH = 0.647 MILE FLEXIBLE ESALS = 5.80 MILLION ASPHALT
 GRADE = PG 64-22 OK, PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	115,248.000	CY
202(C)	0184 UNCLASSIFIED BORROW	500.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	811.000	LF
224	2803 TEMPORARY SEDIMENT FILTER	7.000	EA
227	0100 TEMPORARY SILT DIKE	502.000	LF
229	4318 DITCH LINER PROTECTION	2,581.000	LF
230(A)	2806 SOLID SLAB SODDING	46,221.000	SY
325	5271 SEPARATOR FABRIC	16,115.000	SY
326(B)	4210 (SP)LIME	810.000	TON
326(F)	4250 (SP)LIME STABILIZED SUBGRADE	21,754.000	SY
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	300.000	TON
407	0250 TACK COAT	1,460.000	GAL
408	5774 PRIME COAT	14,871.000	GAL
411(S2)	5930 (SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	1,408.000	TON
411(S3)	5935 (SP)ASPH.CONC.,TYPE S3(PG 76-28 OK)	1,575.000	TON
411(S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	3,665.000	TON
411(S4)	5950 (SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	1,335.000	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	839.000	TON
414(A)	0210 (SP)P.C.CONCRETE PAVEMENT(PLACEMENT)	2,840.000	SY
414(D)	4425 (SP)CONT.REINF.P.C.C. PAVT.(PLACEMENT)	5,567.000	SY
414(P)	6000 (SP)P.C. CONCRETE FOR PAVEMENT	2,322.000	CY
501(A)	0313 STRUCTURAL EXCAVATION UNCLASSIFIED	40.000	CY
509(A)	0319 CLASS AA CONCRETE	91.000	CY
509(C)	0322 CLASS A CONCRETE FOR SMALL STRUCTURES	7.000	CY
509(D)	0325 CLASS C CONCRETE	588.000	CY
511(A)	0332 REINFORCING STEEL	12,467.000	LB
609(A)	0288 CONC.CURB(6" MNTBLE-INTEGRAL)	1,609.000	LF
609(B)	1523 2'-8" COMB.CRB.& GUT.(4" MNTBLE)	317.000	LF
609(B)	1524 2'-8" COMB.CRB.& GUT.(6" MNTBLE)	427.000	LF
611(A)	2657 MANHOLE (4' DIA.)	3.000	EA
611(B)	2680 ADD'L.DEPTH IN MANHOLE (4' DIA.)	2.000	VF
611(D)	4215 MANHOLE FRAME & COVER	3.000	EA
611(E)	5117 INLET CICI DES. 2 (2B)	1.000	EA
611(E)	5124 INLET CICI DES. 3 (B-D)	1.000	EA

CALL ORDER : 180
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 ID
 COUNTIES : COMANCHE

CONTRACT ID : 050509
 PCN : 2031305
 PROJECTS : IMDY-44-1(089)043
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 128.97
 CALENDAR DAYS : 255
 RES. ENG.:
 LIQ. DAM.: \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
611(E) 6002	INLET (SMD-TYPE 2)	2.000	EA
611(E) 6004	INLET (SMD-TYPE 2A)	1.000	EA
611(K) 4488	CAST IRON CURB INLETS	16.000	EA
613(B) 0491	18" R.C.P.I.PE CLASS III	712.000	LF
613(B) 0492	24" R.C.P.I.PE CLASS III	246.000	LF
613(CC) 7197	TYPE B6 CULVERT END TREATMENT	1.000	EA
613(M) 5726	18" PREFAB. CULVERT END SEC., ROUND	1.000	EA
613(M) 5730	24" PREFAB. CULVERT END SEC., ROUND	4.000	EA
613(M) 5734	36" PREFAB. CULVERT END SEC., ROUND	1.000	EA
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 0291	REMOVAL OF HEADWALL	1.000	EA
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	17,737.000	SY
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	1,977.000	SY
619(B) 4780	REMOVAL OF GUARD RAIL	696.000	LF
619(C) 0924	SAWING PAVEMENT	2,185.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	1,388.000	LF
623(E) 7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	6.000	EA
623(F) 4447	GUARD RAIL ANCHOR UNIT (TYPE B)	1.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	7.000	EA
624(D) 4292	FENCE-STYLE CLF (6'HIGH, CLASS A)	1,200.000	LF
624(D) 4293	FENCE-STYLE CLF (6'HIGH, CLASS B)	4,134.000	LF
624(E) 5966	GATES-STYLE CLF (6'HIGH X 18'LONG)	1.000	EA
SECTION NO. 0002 BRIDGE 'A'			
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	220.000	CY
501(G) 6309	CLSM BACKFILL	93.000	CY
503(A) 1312	PRESTRESSED CONCRETE BEAMS (TYPE III)	756.000	LF
504(A) 1304	APPROACH SLAB	283.100	SY
504(C) 6250	SEALED EXPANSION JOINT	38.950	LF
504(F) 6190	42" F-SHAPED PARAPET	546.900	LF
506(A) 1322	STRUCTURAL STEEL	1,290.000	LB
509(A) 1326	CLASS AA CONCRETE	208.700	CY
509(B) 1328	CLASS A CONCRETE	169.000	CY
509(D) 1331	CLASS C CONCRETE	10.000	CY
510(C) 6138	SLOPE WALL (5")	621.000	SY
511(A) 1332	REINFORCING STEEL	3,350.000	LB
511(B) 6010	EPOXY COATED REINFORCING STEEL	75,410.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	1,525.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	1,525.000	LF
514(F) 6354	PILE LOAD TEST (DYNAMIC)	14.000	EA
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	719.000	SY
516(A) 6094	DRILLED SHAFTS 48" DIAMETER	242.000	LF

CALL ORDER : 180
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 ID
 COUNTIES : COMANCHE

CONTRACT ID : 050509
 PCN : 2031305
 PROJECTS : IMDY-44-1(089)043
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 128.97
 CALENDAR DAYS : 255
 RES. ENG.:
 LIQ. DAM.: \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002 BRIDGE 'A'			
523(A) 6550	(SP) SEALER CRACK PREPARATION	124.000	LF
523(B) 6560	(SP) SEALER RESIN	0.900	GAL
535 6164	(PL)FIXED BEARING ASSEMBLY	16.000	EA
535 6165	(PL)EXPANSION BEARING ASSEMBLY	8.000	EA
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	180.000	LF
613(Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	66.000	LF
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
SECTION NO. 0003 TRAFFIC CONTROL			
804(A) 2915	STRUCTURAL CONCRETE	7.400	CY
804(B) 2916	REINFORCING STEEL	1,388.000	LB
850(A) 8110	SHEET ALUMINUM SIGNS	71.400	SF
850(B) 8112	EXTRUDED ALUMINUM PANEL SIGNS	581.300	SF
850(B) 8114	EXTR.ALUM.PAN.SGN.(OVRHD SIGNS)	91.000	SF
851(A) 3206	4"@13 GALV.STL.WD.FLANGE BM.POST	322.800	LF
851(A) 3209	6"@25 GALV.STL.WD.FLANGE BM.POST	58.600	LF
851(C) 8324	2" SQUARE TUBE POST	28.000	LF
851(C) 8327	2 1/4" SQUARE TUBE POST	29.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	23,570.000	LF
856(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	3,600.000	LF
856(C) 8851	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	3,600.000	LF
856(G) 8887	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	6,880.000	EA
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	3,600.000	LF
871 8325	(PL)IMPACT ATTENUATOR	1.000	EA
880(A) 8812	ARROW DISPLAY(TYPE C)	720.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	21,160.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	14,400.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	12,600.000	SD
880(C) 8842	BARRICADES(TYPE III)	9,360.000	SD
880(C) 8848	WING BARRICADES	3,600.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	31,320.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	52,200.000	SD
880(F) 8878	DRUMS	52,200.000	SD
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	16.000	HOURL
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	720.000	SD
890(A) 8720	(PL)REMOVAL OF GROUND MOUNTED SIGNS	1.000	LSUM
890(A) 8724	(PL)REMOVAL OF EXISTING SIGNS	9.000	EA
SECTION NO. 0004 TRAFFIC SIGNALS			
802(B) 8332	1" PVC SCH.40 PLASTIC CONDUIT BORED	110.000	LF
802(B) 8338	1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCH	540.000	LF

CALL ORDER : 180
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 ID
 COUNTIES : COMANCHE

CONTRACT ID : 050509
 PCN : 2031305
 PROJECTS : IMDY-44-1(089)043
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 128.97
 CALENDAR DAYS : 255
 RES. ENG.:
 LIQ. DAM.: \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0004 TRAFFIC SIGNALS			
802(B) 8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	90.000	LF
802(B) 8344	3" PVC SCH.40 PLASTIC CONDUIT BORED	310.000	LF
802(B) 8346	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	75.000	LF
803 8065	PULL BOX(SIZE I)	4.000	EA
803 8066	PULL BOX(SIZE II)	1.000	EA
803 8067	PULL BOX(SIZE III)	5.000	EA
804(A) 2915	STRUCTURAL CONCRETE	11.600	CY
804(B) 2916	REINFORCING STEEL	1,766.200	LB
806(A) 8312	32'MH POLE 40'TS & 10'LMA(G.STL.)	1.000	EA
806(A) 8313	32'MH POLE 45'TS & 10'LMA(G.STL.)	2.000	EA
806(A) 8351	32'MH POLE 25',TS & 10'LMA(G.STL.)	1.000	EA
809(A) 8090	(PL)ROADWAY LUMINAIRE	4.000	EA
810(A) 3118	SERVICE POLE	1.000	EA
811 8040	1/C NO.6 ELECT.COND.	800.000	LF
811 8044	1/C NO.10 ELECT.COND.	1,470.000	LF
825 8550	VEH.ACT.SOL.ST.TRAF.SIG.CON.ASM	1.000	EA
828(A) 8135	SOL.STE.DIGITAL IND.VEH.LP.DET.	9.000	EA
828(B) 8138	LOOP DETECTOR WIRE	4,350.000	LF
831 8231	1WAY3SEC.ADJ.SIG.HD.S-6	8.000	EA
831 8252	1WAY3SEC.ADJ.SIG.HD.S-9	2.000	EA
831 8262	1WAY3SEC.ADJ.SIG.HD.S-10	1.000	EA
833 3030	BACKPLATE	11.000	EA
834(A) 8207	5/C TRAF.SIG.EL.CABLE	900.000	LF
834(A) 8208	7/C TRAF.SIG.EL.CABLE	170.000	LF
834(A) 8210	12/C TRAF.SIG.EL.CABLE	50.000	LF
834(A) 8211	15/C TRAF.SIG.EL.CABLE	300.000	LF
834(B) 8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	1,850.000	LF
850(A) 8110	SHEET ALUMINUM SIGNS	6.250	SF
850(C) 8118	MAST ARM MOUNTED SIGNS(ALUM.)	73.500	SF
851(C) 8327	2 1/4" SQUARE TUBE POST	14.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	3,100.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	8.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	5.000	EA
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	3,100.000	LF
859(B) 8007	PAVEMENT MARKING REMOVAL(ARROWS)	8.000	EA
859(B) 8008	PAVEMENT MARKING REMOVAL(WORDS)	5.000	EA
890(A) 8704	(PL)REMOVAL OF PULL BOX	10.000	EA
890(A) 8726	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
SECTION NO. 0005 STAKING			
642 0098	STAKING	1.000	LSUM

CALL ORDER : 180
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 ID
 COUNTIES : COMANCHE

CONTRACT ID : 050509
 PCN : 2031305
 PROJECTS : IMDY-44-1(089)043
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 128.97
 CALENDAR DAYS : 255
 RES. ENG.:
 LIQ. DAM.: \$ 1000

SECTION NO.	0006	CONSTRUCTION		
640	1426	FIELD OFFICE	1.000	EA
641	1552	MOBILIZATION	1.000	LSUM

CALL ORDER : 190
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : CUSTER

CONTRACT ID : 050630
 PCN : 2133704
 PROJECTS : BRO-120D(096)CO
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 13.01
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

GRADE, DRAIN SURFACE AND BRIDGE COUNTY ROAD: OVER OAK
 CREEK, 7.6 MILES WEST AND 3.6 MILES EAST OF STAFFORD.
 PROJECT LENGTH = 0.272 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,490.000	LF
230(A)	2806 SOLID SLAB SODDING	12,010.000	SY
233(A)	2817 VEGETATIVE MULCHING	2.480	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	872.000	TON
509(D)	0325 CLASS C CONCRETE	10.000	CY
613(CC)	7187 TYPE B4 CULVERT END TREATMENT	4.000	EA
613(D)	0690 24" CORR. GALV. STEEL PIPE	390.000	LF
SECTION NO. 0002 BRIDGE 'A'			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	78.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	64.000	CY
503(A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	296.670	LF
504(E)	1380 CONCRETE RAIL (TR1)	207.000	LF
506(A)	1322 STRUCTURAL STEEL	1,620.000	LB
509(A)	1326 CLASS AA CONCRETE	58.300	CY
509(B)	1328 CLASS A CONCRETE	48.800	CY
511(A)	1332 REINFORCING STEEL	20,076.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	240.000	LF
514(A)	6011 PILES, FURNISHED (HP 12X53)	650.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	240.000	LF
514(B)	6294 PILES, DRIVEN (HP 12X53)	650.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	1,390.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	391.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(A)	1418 BEAM GUARD RAIL-W-BEAM-SINGLE	50.250	LF
623(F)	5686 GUARD RAIL ANCHOR UNIT (TYPE D-BF)	1.000	EA
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	3.000	EA
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAKING			
642	0098 STAKING	1.000	LSUM

CALL ORDER : 190
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : CUSTER

CONTRACT ID : 050630
 PCN : 2133704
 PROJECTS : BRO-120D(096)CO
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 13.01
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0004	CONSTRUCTION		
641 1399	MOBILIZATION	1.000	LSUM

CALL ORDER : 200
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : DEWEY

CONTRACT ID : 050691
 PCN : 2141004
 PROJECTS : BRO-122D(40)CO
 DBE GOALS : 4.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 10.84
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES COUNTY ROAD; OVER AN UNNAMED CREEK, 6.
 5 MILES WEST OF TALOGA. PROJECT LENGTH = 0.179 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 ROADWAY			
202(G) 0185	EARTHWORK	1.000	LSUM
222 2801	TEMPORARY BALE BARRIER	140.000	LF
223 2801	TEMPORARY SILT FENCE	1,030.000	LF
230(A) 2806	SOLID SLAB SODDING	6,090.000	SY
233(A) 2817	VEGETATIVE MULCHING	1.260	AC
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	527.000	TON
509(D) 0325	CLASS C CONCRETE	10.000	CY
613(CC) 7188	TYPE C4 CULVERT END TREATMENT	2.000	EA
613(D) 4531	49" X 33" CORR. GALV. STEEL PIPE ARCH	55.000	LF
SECTION NO. 0002 BRIDGE 'A'			
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	88.000	CY
501(D) 6353	UNCLASSIFIED BACKFILL	90.000	CY
503(A) 1312	PRESTRESSED CONCRETE BEAMS (TYPE III)	296.170	LF
504(E) 1380	CONCRETE RAIL (TR1)	215.160	LF
506(A) 1322	STRUCTURAL STEEL	1,800.000	LB
509(A) 1326	CLASS AA CONCRETE	58.500	CY
509(B) 1328	CLASS A CONCRETE	58.400	CY
511(A) 1332	REINFORCING STEEL	21,408.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	100.000	LF
514(A) 6011	PILES, FURNISHED (HP 12X53)	250.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	100.000	LF
514(B) 6294	PILES, DRIVEN (HP 12X53)	250.000	LF
601(A-1) 1353	TYPE I-A PLAIN RIPRAP	641.000	TON
601(A-2) 1355	TYPE I-A FILTER BLANKET	176.000	TON
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAKING			
642 0098	STAKING	1.000	LSUM
SECTION NO. 0004 CONSTRUCTION			
641 1399	MOBILIZATION	1.000	LSUM

CALL ORDER : 210
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : ELLIS

CONTRACT ID : 050692
 PCN : 2022004
 PROJECTS : BRO-123D(028)CO
 DBE GOALS : 3.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 9.75
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES COUNTY ROAD: OVER WEST RED BLUFF
 CREEK, 5.3 MILES WEST AND 2.2 MILES SOUTH OF ARNETT.
 PROJECT LENGTH = 0.209 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	985.000	LF
227	0100 TEMPORARY SILT DIKE	50.000	LF
230(A)	2806 SOLID SLAB SODDING	3,676.000	SY
233(A)	2817 VEGETATIVE MULCHING	0.760	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	536.000	TON
509(D)	0325 CLASS C CONCRETE	10.000	CY
SECTION NO. 0002 BRIDGE 'A'			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	60.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	40.000	CY
503(B)	6144 PRESTRESSED CONCRETE DOUBLE TEE	272.500	LF
504(E)	1380 CONCRETE RAIL (TR1)	155.000	LF
509(A)	1326 CLASS AA CONCRETE	37.600	CY
509(B)	1328 CLASS A CONCRETE	28.200	CY
511(A)	1332 REINFORCING STEEL	10,700.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	955.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	955.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	400.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	150.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAKING			
642	0098 STAKING	1.000	LSUM
SECTION NO. 0004 CONSTRUCTION			
641	1399 MOBILIZATION	1.000	LSUM

CALL ORDER : 220
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : GARFIELD

CONTRACT ID : 050572
 PCN : 1080904
 PROJECTS : BRO-024D(173)CO
 DBE GOALS : 4.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 13.01
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE & APPROACHES COUNTY ROAD: OVER CLEAR CREEK, APPROX.
 3.0 MILE SOUTH AND 6.4 MILES WEST OF JCT US-412/US-81.
 PROJECT LENGTH = 0.169 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	100.000	LF
227	0100 TEMPORARY SILT DIKE	300.000	LF
230(A)	2806 SOLID SLAB SODDING	5,439.000	SY
233(A)	2817 VEGETATIVE MULCHING	1.130	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	398.000	TON
509(D)	0325 CLASS C CONCRETE	63.000	CY
SECTION NO. 0002 BRIDGE 'A'			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	68.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	50.000	CY
503(B)	6144 PRESTRESSED CONCRETE DOUBLE TEE	474.000	LF
504(E)	1380 CONCRETE RAIL (TR1)	297.000	LF
509(A)	1326 CLASS AA CONCRETE	87.100	CY
509(B)	1328 CLASS A CONCRETE	70.400	CY
511(A)	1332 REINFORCING STEEL	26,070.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	305.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	305.000	LF
516(A)	6092 DRILLED SHAFTS 36" DIAMETER	52.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	1,209.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	300.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAKING			
642	0098 STAKING	1.000	LSUM
SECTION NO. 0004 CONSTRUCTION			
641	1399 MOBILIZATION	1.000	LSUM

CALL ORDER : 230
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : GARFIELD

CONTRACT ID : 050693
 PCN : 2160904
 PROJECTS : STP-124C(059)CO
 DBE GOALS : 4.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 4.34
 CALENDAR DAYS : 60
 RES. ENG.:
 LIQ. DAM.: \$ 750

CONTRACT DESCRIPTION:

RESURFACE COUNTY ROAD(EW-51): BEGINNING AT US-81 IN
 WAUKOMIS, AND EXTEND EAST. PROJECT LENGTH = 5.951 MILES
 FLEXIBLE ESALS = 1.03 MILLION ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADWAY		
202(C) 0184	UNCLASSIFIED BORROW	1,536.000	CY
223 2801	TEMPORARY SILT FENCE	1,000.000	LF
227 0100	TEMPORARY SILT DIKE	500.000	LF
230(A) 2806	SOLID SLAB SODDING	20,834.000	SY
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	1,002.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	13,945.000	TON
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	100.000	LF
623(F) 4447	GUARD RAIL ANCHOR UNIT (TYPE B)	4.000	EA
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
850(A) 8110	SHEET ALUMINUM SIGNS	62.160	SF
851(D) 8597	FLANGE CHANNEL POSTS(4 LB/FT)	174.000	LF
853 9030	DELINEATORS(TYPE 1, CODE 3)	8.000	EA
853 9039	DELINEATORS(TYPE 2, CODE 3)	38.000	EA
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	30,379.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 240
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : HARPER

CONTRACT ID : 050694
 PCN : 2126104
 PROJECTS : BRO-130D(072)CO
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 8.67
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES COUNTY ROAD: OVER A TRIBUTARY TO
 DOBY CREEK, 2.0 MILES SOUTH AND 0.2 MILES WEST OF THE
 US-64/SH-46 JUNCTION. PROJECT LENGTH = 0.131 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	300.000	LF
227	0100 TEMPORARY SILT DIKE	150.000	LF
230(A)	2806 SOLID SLAB SODDING	3,097.000	SY
233(A)	2817 VEGETATIVE MULCHING	0.070	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	339.000	TON
509(D)	0325 CLASS C CONCRETE	16.000	CY
SECTION NO. 0002 BRIDGE 'A'			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	78.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	64.000	CY
503(A)	1312 PRESTRESSED CONCRETE BEAMS (TYPE III)	296.670	LF
504(A)	1380 CONCRETE RAIL (TR1)	207.000	LF
506(A)	1322 STRUCTURAL STEEL	1,620.000	LB
509(A)	1326 CLASS AA CONCRETE	58.300	CY
509(B)	1328 CLASS A CONCRETE	48.800	CY
511(A)	1332 REINFORCING STEEL	20,090.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	258.000	LF
514(A)	6011 PILES, FURNISHED (HP 12X53)	611.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	258.000	LF
514(B)	6294 PILES, DRIVEN (HP 12X53)	611.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	594.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	148.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAKING			
642	0098 STAKING	1.000	LSUM
SECTION NO. 0004 CONSTRUCTION			
641	1399 MOBILIZATION	1.000	LSUM

CALL ORDER : 250
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : KAY

CONTRACT ID : 050695
 PCN : 1559304
 PROJECTS : IMY-0035-4(168)222
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 149.56
 CALENDAR DAYS : 325
 RES. ENG.:
 LIQ. DAM.: \$ 2000

CONTRACT DESCRIPTION:

INTERCHANGE MODIFICATION/BRIDGE & APPROACHES I-35:
 INTERCHANGE AT I-35 AND SH-11. PROJECT LENGTH = 0.920 MILES
 FLEXIBLE ESALS = 136.2 MILLION ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	94,161.000	CY
202(C)	0184 UNCLASSIFIED BORROW	149,570.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	500.000	LF
223	2801 TEMPORARY SILT FENCE	5,486.000	LF
224	2803 TEMPORARY SEDIMENT FILTER	5.000	EA
225	2804 TEMPORARY SEDIMENT BASIN	2.000	EA
227	0100 TEMPORARY SILT DIKE	1,232.000	LF
230(A)	2806 SOLID SLAB SODDING	304,726.000	SY
232(A)	2813 SEEDING METHOD A	64.000	AC
233(A)	2817 VEGETATIVE MULCHING	64.000	AC
326(B)	4210 (SP)LIME	1,211.000	TON
326(F)	4250 (SP)LIME STABILIZED SUBGRADE	66,605.000	SY
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	448.000	TON
407	0250 TACK COAT	1,510.000	GAL
408	5774 PRIME COAT	11,456.000	GAL
411(S2)	5930 (SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	1,004.000	TON
411(S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	4,536.000	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	8,870.000	TON
414(A)	0210 (SP)P.C.CONCRETE PAVEMENT(PLACEMENT)	15,372.000	SY
414(A1)	5725 (SP)DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	40,309.000	SY
414(P)	6000 (SP)P.C. CONCRETE FOR PAVEMENT	12,370.000	CY
509(A)	1326 CLASS AA CONCRETE	278.000	CY
509(D)	0325 CLASS C CONCRETE	428.000	CY
511(A)	1332 REINFORCING STEEL	36,579.000	LB
610(B)	0399 6" CONCRETE DRIVEWAY (H.E.S.)	834.000	SY
611(E)	5327 INLET GPI TYPE 1 (DES. 1)	6.000	EA
613(B)	0491 18" R.C.PIPE CLASS III	536.000	LF
613(B)	0492 24" R.C.PIPE CLASS III	371.000	LF
613(B)	0494 36" R.C.PIPE CLASS III	596.000	LF
613(B)	4499 51" X 31" R.C.PIPE ARCH CLASS A-III	168.000	LF
613(D)	0690 24" CORR. GALV. STEEL PIPE	100.000	LF
613(D)	0691 30" CORR. GALV. STEEL PIPE	116.000	LF
613(D)	4527 21" X 15" CORR. GALV. STEEL PIPE ARCH	84.000	LF
613(M)	4540 51" X 31" PREFAB. CULVERT END SEC., ARCH	6.000	EA
613(M)	5726 18" PREFAB. CULVERT END SEC., ROUND	7.000	EA

CALL ORDER : 250
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : KAY

CONTRACT ID : 050695
 PCN : 1559304
 PROJECTS : IMY-0035-4(168)222
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 149.56
 CALENDAR DAYS : 325
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
613(M) 5730	24" PREFAB. CULVERT END SEC., ROUND	5.000	EA
613(M) 5734	36" PREFAB. CULVERT END SEC., ROUND	8.000	EA
613(P) 1092	8" PERFORATED PIPE UNDERDRAIN ROUND	1,260.000	LF
613(Q) 1097	8" NON-PERF.PIPE UNDERDRAIN RND.	315.000	LF
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	10,666.000	SY
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	33,475.000	SY
619(B) 4763	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	23,194.000	SY
619(B) 4780	REMOVAL OF GUARD RAIL	5,743.000	LF
619(C) 0924	SAWING PAVEMENT	7,384.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	1,013.000	LF
623(E) 7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	4.000	EA
623(F) 4447	GUARD RAIL ANCHOR UNIT (TYPE B)	1.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	5.000	EA
624(C) 4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	4,660.000	LF
629(E) 5048	REMOVE AND RESET MAILBOX	2.000	EA
653(C) 5946	OUTLET LATERAL HEADWALL	4.000	EA
SECTION NO. 0002 BRIDGE 'A'			
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	160.000	CY
501(F) 6352	GRANULAR BACKFILL	222.000	CY
504(A) 1304	APPROACH SLAB	291.600	SY
504(F) 6190	42" F-SHAPED PARAPET	604.000	LF
506(A) 1322	STRUCTURAL STEEL	272,040.000	LB
509(A) 1326	CLASS AA CONCRETE	397.700	CY
509(B) 1328	CLASS A CONCRETE	119.100	CY
510(C) 6138	SLOPE WALL (5")	2,145.000	SY
511(A) 1332	REINFORCING STEEL	520.000	LB
511(B) 6010	EPOXY COATED REINFORCING STEEL	95,780.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	1,240.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	1,240.000	LF
514(F) 6354	PILE LOAD TEST (DYNAMIC)	20.000	EA
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	850.000	SY
516(A) 6096	DRILLED SHAFTS 60" DIAMETER	119.000	LF
523(A) 6550	(SP) SEALER CRACK PREPARATION	82.000	LF
523(B) 6560	(SP) SEALER RESIN	2.000	GAL
535 6164	(PL)FIXED BEARING ASSEMBLY	16.000	EA
535 6282	(PL)ELASTOMERIC BEARING PADS	8.000	EA
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	576.000	LF
613(Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	160.000	LF

CALL ORDER : 250
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : KAY

CONTRACT ID : 050695
 PCN : 1559304
 PROJECTS : IMY-0035-4(168)222
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 149.56
 CALENDAR DAYS : 325
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 BRIDGE 'B'			
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	160.000	CY
501(F) 6352	GRANULAR BACKFILL	150.000	CY
504(A) 1304	APPROACH SLAB	291.600	SY
504(F) 6190	42" F-SHAPED PARAPET	604.000	LF
506(A) 1322	STRUCTURAL STEEL	272,040.000	LB
509(A) 1326	CLASS AA CONCRETE	309.700	CY
509(B) 1328	CLASS A CONCRETE	119.100	CY
511(A) 1332	REINFORCING STEEL	520.000	LB
511(B) 6010	EPOXY COATED REINFORCING STEEL	79,850.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	1,140.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	1,140.000	LF
514(F) 6354	PILE LOAD TEST (DYNAMIC)	20.000	EA
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	850.000	SY
516(A) 6096	DRILLED SHAFTS 60" DIAMETER	119.000	LF
523(A) 6550	(SP) SEALER CRACK PREPARATION	82.000	LF
523(B) 6560	(SP) SEALER RESIN	2.000	GAL
535 6164	(PL)FIXED BEARING ASSEMBLY	16.000	EA
535 6282	(PL)ELASTOMERIC BEARING PADS	8.000	EA
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	82.000	LF
613(Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	60.000	LF
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
SECTION NO. 0004 TRAFFIC - SIGNING & STRIPING			
804(A) 2915	STRUCTURAL CONCRETE	20.000	CY
804(B) 2916	REINFORCING STEEL	4,680.000	LB
850(A) 8110	SHEET ALUMINUM SIGNS	429.000	SF
850(B) 8112	EXTRUDED ALUMINUM PANEL SIGNS	1,344.000	SF
851(A) 3206	4"@13 GALV.STL.WD.FLANGE BM.POST	216.000	LF
851(A) 3207	6"@15 GALV.STL.WD.FLANGE BM.POST	99.000	LF
851(A) 3209	6"@25 GALV.STL.WD.FLANGE BM.POST	106.000	LF
851(A) 3210	8"@31 GALV.STL.WD.FLANGE BM.POST	232.000	LF
851(B) 3217	2 1/2"@5.79 GALV.STL.PIPE POST	56.000	LF
851(B) 3218	3"@7.58 GALV.STL.PIPE POST	28.000	LF
851(C) 8321	1 3/4" SQUARE TUBE POST	30.000	LF
851(C) 8324	2" SQUARE TUBE POST	116.000	LF
851(C) 8327	2 1/4" SQUARE TUBE POST	475.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	45,925.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	10.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	5.000	EA
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	2,000.000	LF

CALL ORDER : 250
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : KAY

CONTRACT ID : 050695
 PCN : 1559304
 PROJECTS : IMY-0035-4(168)222
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 149.56
 CALENDAR DAYS : 325
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005 TRAFFIC - SIGNAL			
802(B) 8338	1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCH	415.000	LF
803 8067	PULL BOX(SIZE III)	2.000	EA
828(B) 8138	LOOP DETECTOR WIRE	1,320.000	LF
834(B) 8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	825.000	LF
SECTION NO. 0006 CONSTRUCTION TRAFFIC CONTROL			
627(G) 4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	1,400.000	LF
627(H) 5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	2,800.000	LF
856(G) 8890	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-2	840.000	EA
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	6,000.000	LF
870(A) 8011	SAND FILLED IMPACT ATTEN.MODULE	38.000	EA
870(A) 8485	SAND FILLED IMPACT ATTEN.MODULE	24,700.000	SD
870(B) 8012	IMPACT ATTEN.MODULE(REPLACEMENT)	38.000	EA
880(A) 8812	ARROW DISPLAY(TYPE C)	1,300.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	39,000.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	9,750.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	6,500.000	SD
880(C) 8842	BARRICADES(TYPE III)	6,500.000	SD
880(C) 8848	WING BARRICADES	1,950.000	SD
880(D) 8854	VERTICAL PANELS	13,000.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	19,500.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	89,050.000	SD
880(F) 8878	DRUMS	76,050.000	SD
880(G) 8884	TUBE CHANNELIZERS	32,500.000	SD
880(K) 8908	SURVEILLANCE TRAFFIC CONTROL	325.000	SD
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	80.000	HOURL
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	650.000	SD
SECTION NO. 0007 HIGHWAY LIGHTING			
802(A) 8306	1 1/4" GALV.STEEL ELECT.COND. EXPOSED	375.000	LF
802(B) 8340	2" PVC SCH.40 PLASTIC CONDUIT BORED	648.000	LF
802(B) 8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	17,455.000	LF
802(D) 8370	JUNCTION BOX(6" X 6" X 4")	2.000	EA
803 8065	PULL BOX(SIZE I)	8.000	EA
804(A) 2915	STRUCTURAL CONCRETE	56.840	CY
804(B) 2916	REINFORCING STEEL	3,273.200	LB
806(C) 8924	40' MTG & 10' HLMA(G.STL.)	2.000	EA
806(C) 8928	40'MHP & 15' H.L.MST.ARM(G.STL.)	18.000	EA
807 8092	BREAKAWAY BASE (DES. B)	98.000	EA
809(A) 8090	(PL)ROADWAY LUMINAIRE	106.000	EA
810(A) 3118	SERVICE POLE	2.000	EA

CALL ORDER : 250
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : KAY

CONTRACT ID : 050695
 PCN : 1559304
 PROJECTS : IMY-0035-4(168)222
 DBE GOALS : 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 149.56
 CALENDAR DAYS : 325
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0007 HIGHWAY LIGHTING			
811 8038	1/C NO.4 ELECT.COND.	36,070.000	LF
811 8046	1/C NO.12 ELECT.COND.	11,690.000	LF
890(A) 8712	(PL)REMOVAL OF LIGHT POLE	94.000	EA
890(B) 8732	(PL)RESET OF LIGHT POLE	80.000	EA
SECTION NO. 0008 STAKING			
642 0098	STAKING	1.000	LSUM
SECTION NO. 0009 CONSTRUCTION			
640 1426	FIELD OFFICE	1.000	EA
641 1552	MOBILIZATION	1.000	LSUM
643 0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM

CALL ORDER : 260
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : MCCLAIN

CONTRACT ID : 050150
 PCN : 2197404
 PROJECTS : STPY-144C(89)
 DBE GOALS : 10.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 66.11
 CALENDAR DAYS : 180
 RES. ENG.:
 LIQ. DAM.: \$ 1000

CONTRACT DESCRIPTION:

INTERSECTION MODIFICATION & TRAFFIC SIGNALS US-62; AT 24TH
 ST. IN NEWCASTLE PROJECT LENGTH = 0.694 MILE FLEXIBLE ESALS
 = 43.1 MILLION ASPHALT GRADE = PG 64-22 OK, PG 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
202(A)	0183 UNCLASSIFIED EXCAVATION	1,723.000	CY
202(C)	0184 UNCLASSIFIED BORROW	7,399.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,810.500	LF
224	2803 TEMPORARY SEDIMENT FILTER	1.000	EA
227	0100 TEMPORARY SILT DIKE	127.500	LF
230(A)	2806 SOLID SLAB SODDING	13,428.000	SY
232(B)	2814 SEEDING METHOD B	3.000	AC
233(A)	2817 VEGETATIVE MULCHING	6.000	AC
235(B)	0101 (PL)ROCK FILTER DAM, TYPE 2	10.000	CY
326(A)	4200 (SP)FLY ASH	567.000	TON
326(E)	4240 (SP)CEMENTITIOUS STABILIZED SUBGRADE	13,025.000	SY
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	500.000	TON
408	5774 PRIME COAT	1,955.000	GAL
411(S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	2,578.000	TON
414(A1)	5760 11" P.C. DOWEL JOINTED CONCRETE PAVEMENT	12,651.000	SY
417	4267 COLD MILLING BITUMINOUS PAVEMENT	760.000	SY
509(D)	0325 CLASS C CONCRETE	10.000	CY
609(A)	0288 CONC.CURB(6" MNTBLE-INTEGRAL)	615.000	LF
609(B)	1513 1'-8" COMB.CRB.& GUT.(6" BARRIER)	360.000	LF
610(C)	0609 6" CONCRETE DIVIDING STRIP	167.000	SY
611(E)	M5112 INLET CICI DES. 2 (STD)	1.000	EA
611(G)	1391 INLET FRAME AND GRATE	2.000	EA
611(K)	4488 CAST IRON CURB INLETS	4.000	EA
613(B)	0491 18" R.C.PIPE CLASS III	76.000	LF
613(CC)	7186 TYPE A4 CULVERT END TREATMENT	1.000	EA
613(D)	0690 24" CORR. GALV. STEEL PIPE	60.000	LF
619(A)	0920 REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B)	4728 REMOVAL OF ASPHALT PAVEMENT	7,482.000	SY
619(B)	4763 REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	4,092.000	SY
619(B)	4791 REMOVAL OF CURB	800.000	LF
619(B)	6132 REMOVAL OF 6" CONCRETE DIVIDING STRIP	145.000	SY
619(C)	0924 SAWING PAVEMENT	1,162.000	LF
SECTION NO. 0002 ROADWAY (NON-PARTICIPATING)			
202(A)	0183 UNCLASSIFIED EXCAVATION	4,508.000	CY

CALL ORDER : 260
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : MCCLAIN

CONTRACT ID : 050150
 PCN : 2197404
 PROJECTS : STPY-144C(89)
 DBE GOALS : 10.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 66.11
 CALENDAR DAYS : 180
 RES. ENG.:
 LIQ. DAM.: \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0002 ROADWAY (NON-PARTICIPATING)				
205	4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801	TEMPORARY SILT FENCE	1,810.000	LF
224	2803	TEMPORARY SEDIMENT FILTER	1.000	EA
227	0100	TEMPORARY SILT DIKE	127.500	LF
230(A)	2806	SOLID SLAB SODDING	13,428.000	SY
232(B)	2814	SEEDING METHOD B	6.000	AC
233(A)	2817	VEGETATIVE MULCHING	12.000	AC
326(A)	4200	(SP)FLY ASH	2,012.000	TON
326(E)	4240	(SP)CEMENTITIOUS STABILIZED SUBGRADE	10,783.000	SY
403(E)	0225	TRAFFIC BOUND SURFACE COURSE TYPE E	500.000	TON
407	0250	TACK COAT	936.000	GAL
408	5774	PRIME COAT	1,617.000	GAL
411(S2)	5930	(SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	1,863.000	TON
411(S3)	5940	(SP)ASPH.CONC.,TYPE S3(PG 70-28 OK)	1,008.000	TON
411(S3)	5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	1,328.000	TON
411(S4)	5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	672.000	TON
414(A1)	5760	11" P.C. DOWEL JOINTED CONCRETE PAVEMENT	3,553.000	SY
501(A)	0313	STRUCTURAL EXCAVATION UNCLASSIFIED	10.000	CY
509(B)	0321	CLASS A CONCRETE	25.100	CY
509(C)	0322	CLASS A CONCRETE FOR SMALL STRUCTURES	18.500	CY
509(D)	0325	CLASS C CONCRETE	10.000	CY
511(A)	0332	REINFORCING STEEL	5,095.000	LB
609(A)	0380	CONC.CURB(8" BARRIER-INTEGRAL)	875.000	LF
609(B)	1526	2'-8" COMB.CRB.& GUT.(8" BARRIER)	2,254.000	LF
610(B)	0399	6" CONCRETE DRIVEWAY (H.E.S.)	166.000	SY
611(D)	4215	MANHOLE FRAME & COVER	3.000	EA
611(E)	5113	INLET CICI DES. 2 (B)	2.000	EA
611(E)	5114	INLET CICI DES. 2 (C)	2.000	EA
611(E)	5115	INLET CICI DES. 2 (D)	3.000	EA
611(E)	5119	INLET CICI DES. 2 (2D)	1.000	EA
611(G)	4488	INLET FRM&GRT (SSIF-FRM,CIG-GRT-VG-F)	16.000	EA
611(K)	4488	CAST IRON CURB INLETS	46.000	EA
613(B)	0491	18" R.C.PIPE CLASS III	242.000	LF
613(B)	0492	24" R.C.PIPE CLASS III	250.000	LF
613(B)	0493	30" R.C.PIPE CLASS III	640.000	LF
613(B)	4495	22" X 13" R.C.PIPE ARCH CLASS A-III	254.000	LF
613(B)	4497	36" X 22" R.C.PIPE ARCH CLASS A-III	260.000	LF
613(CC)	7186	TYPE A4 CULVERT END TREATMENT	1.000	EA
613(CC)	7191	TYPE AA4 CULVERT END TREATMENT	4.000	EA
613(CC)	7192	TYPE BB4 CULVERT END TREATMENT	2.000	EA
619(A)	0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B)	4725	REMOVAL OF FENCE	350.000	LF
619(B)	4726	REMOVAL OF CURB AND GUTTER	770.000	LF

CALL ORDER : 260
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : MCCLAIN

CONTRACT ID : 050150
 PCN : 2197404
 PROJECTS : STPY-144C(89)
 DBE GOALS : 10.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 66.11
 CALENDAR DAYS : 180
 RES. ENG.:
 LIQ. DAM.: \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002 ROADWAY (NON-PARTICIPATING)			
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	4,511.000	SY
619(B) 4766	REMOVAL OF CONCRETE DRIVEWAY	233.000	SY
619(C) 0924	SAWING PAVEMENT	50.000	LF
SECTION NO. 0003 TRAFFIC			
627(G) 4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	4,750.000	LF
627(H) 5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	2,400.000	LF
804(A) 2915	STRUCTURAL CONCRETE	0.720	CY
804(B) 2916	REINFORCING STEEL	130.000	LB
850(A) 8110	SHEET ALUMINUM SIGNS	97.750	SF
850(B) 8112	EXTRUDED ALUMINUM PANEL SIGNS	30.000	SF
851(A) 3206	4"@13 GALV.STL.WD.FLANGE BM.POST	29.000	LF
851(C) 8327	2 1/4" SQUARE TUBE POST	150.570	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	10,650.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	14.000	EA
855(B) M8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	6.000	EA
856(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	13,000.000	LF
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	4,000.000	LF
871 8707	(PL)RELOC.OF CONST.ZN.QUADGUARD IMP.ATTN	7.000	EA
871 8709	(PL)CONST.ZONE QUADGUARD IMPACT ATTEN.	480.000	SD
876(A) 8480	(PL)TRUCK MOUNTED ATTENUATOR	480.000	EA
880(A) 8812	ARROW DISPLAY(TYPE C)	960.000	SD
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	1,350.000	HOURL
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	960.000	SD
890(A) 8724	(PL)REMOVAL OF EXISTING SIGNS	12.000	EA
890A/B 8756	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
SECTION NO. 0004 TRAFFIC (NON-PARTICIPATING)			
627(G) 4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	500.000	LF
627(H) 5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	1,000.000	LF
850(A) 8110	SHEET ALUMINUM SIGNS	40.550	SF
851(C) 8327	2 1/4" SQUARE TUBE POST	73.350	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	4,786.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	9.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	5.000	EA
856(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	8,400.000	LF
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	1,000.000	LF
871 8707	(PL)RELOC.OF CONST.ZN.QUADGUARD IMP.ATTN	1.000	EA
871 8709	(PL)CONST.ZONE QUADGUARD IMPACT ATTEN.	240.000	SD
876(C) 8482	(PL)TRUCK MOUNTED ATTENUATOR	240.000	SD

CALL ORDER : 260
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : MCCLAIN

CONTRACT ID : 050150
 PCN : 2197404
 PROJECTS : STPY-144C(89)
 DBE GOALS : 10.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 66.11
 CALENDAR DAYS : 180
 RES. ENG.:
 LIQ. DAM.: \$ 1000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0004 TRAFFIC (NON-PARTICIPATING)			
880(A) 8812	ARROW DISPLAY(TYPE C)	480.000	SD
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	400.000	HOURL
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	480.000	SD
890(A) 8724	(PL)REMOVAL OF EXISTING SIGNS	6.000	EA
890A/B 8756	(PL)REMOVE & RESET EXISTING SIGNS	1.000	EA
SECTION NO. 0005 TRAFFIC SIGNALS			
802(B) 8332	1" PVC SCH.40 PLASTIC CONDUIT BORED	110.000	LF
802(B) 8338	1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCH	1,150.000	LF
802(B) 8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	130.000	LF
802(B) 8344	3" PVC SCH.40 PLASTIC CONDUIT BORED	360.000	LF
802(B) 8346	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	60.000	LF
803 8065	PULL BOX(SIZE I)	3.000	EA
803 8066	PULL BOX(SIZE II)	1.000	EA
803 8067	PULL BOX(SIZE III)	8.000	EA
804(A) 2915	STRUCTURAL CONCRETE	12.200	CY
804(B) 2916	REINFORCING STEEL	1,847.100	LB
806(A) 8838	40' MHP 25' TS & 12' LMA(G.STL.)	1.000	EA
806(A) 8868	40' MHP 45' TS & 12' LMA(G.STL.)	1.000	EA
806(A) 8882	40' MHP 55' TS & 12' LMA(G.STL.)	2.000	EA
809(A) 8090	(PL)ROADWAY LUMINAIRE	3.000	EA
811 8040	1/C NO.6 ELECT.COND.	125.000	LF
811 8044	1/C NO.10 ELECT.COND.	3,204.000	LF
825 8550	VEH.ACT.SOL.ST.TRAF.SIG.CON.ASM	1.000	EA
828(A) 8135	SOL.STE.DIGITAL IND.VEH.LP.DET.	12.000	EA
828(B) 8138	LOOP DETECTOR WIRE	2,776.000	LF
831 8231	1WAY3SEC.ADJ.SIG.HD.S-6	8.000	EA
831 8252	1WAY3SEC.ADJ.SIG.HD.S-9	3.000	EA
831 8286	1WAY5SEC.ADJ.SIG.HD.S-19	2.000	EA
833 3030	BACKPLATE	13.000	EA
834(A) 8207	5/C TRAF.SIG.EL.CABLE	630.000	LF
834(A) 8208	7/C TRAF.SIG.EL.CABLE	150.000	LF
834(A) 8209	9/C TRAF.SIG.EL.CABLE	675.000	LF
834(A) 8210	12/C TRAF.SIG.EL.CABLE	370.000	LF
834(A) 8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	1,532.000	LF
850(C) 8118	MAST ARM MOUNTED SIGNS(ALUM.)	33.360	SF
SECTION NO. 0006 STAKING			
642 0098	STAKING	1.000	LSUM

CALL ORDER : 260
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : MCCLAIN

CONTRACT ID : 050150
 PCN : 2197404
 PROJECTS : STPY-144C(89)
 DBE GOALS : 10.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 66.11
 CALENDAR DAYS : 180
 RES. ENG.:
 LIQ. DAM.: \$ 1000

SECTION NO. 0007	STAKING (NON-PARTICIPATING)		
642 0098	STAKING	1.000	LSUM
SECTION NO. 0008	CONSTRUCTION		
641 1399	MOBILIZATION	1.000	LSUM
SECTION NO. 0009	CONSTRUCTION (NON-PARTICIPATING)		
641 1399	MOBILIZATION	1.000	LSUM

CALL ORDER : 300
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : MCINTOSH

CONTRACT ID : 050727
 PCN : 2058304
 PROJECTS : BRO-146D(053)CO
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 5.42
 CALENDAR DAYS : 60
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE & APPROACHES COUNTY ROAD (EW-105): OVER TRIBUTARY
 OF SHADY GROVE, APPROXIMATELY 0.3 MILE WEST OF SHADY GROVE.
 PROJECT LENGTH = 0.142 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
202(G) 0185	EARTHWORK	1.000	LSUM
227 0100	TEMPORARY SILT DIKE	100.000	LF
230(A) 2806	SOLID SLAB SODDING	3,700.000	SY
233(A) 2817	VEGETATIVE MULCHING	1.400	AC
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	450.000	TON
509(D) 0325	CLASS C CONCRETE	10.000	CY
613(D) 0689	18" CORR. GALV. STEEL PIPE	60.000	LF
613(M) 5726	18" PREFAB. CULVERT END SEC., ROUND	4.000	EA
SECTION NO. 0002 BRIDGE 'A'			
202(A) 1301	UNCLASSIFIED EXCAVATION	450.000	CY
501(A) 1306	STRUCTURAL EXCAVATION UNCLASSIFIED	105.000	CY
509(B) 1328	CLASS A CONCRETE	236.400	CY
511(A) 1332	REINFORCING STEEL	38,049.000	LB
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(A) 1418	BEAM GUARD RAIL-W-BEAM-SINGLE	60.000	LF
623(F) 4446	GUARD RAIL ANCHOR UNIT (TYPE A)	4.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAKING			
641 1399	MOBILIZATION	1.000	LSUM
SECTION NO. 0004 CONSTRUCTION			
642 0098	STAKING	1.000	LSUM

CALL ORDER : 307
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : STATEWIDE

CONTRACT ID : 050738
 PCN : 1984804
 PROJECTS : ITSY-0QT8(004) DC
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 3.25
 CALENDAR DAYS : 150
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 SAFETY IMPROVEMENT VARIOUS HIGHWAYS; VARIOUS LOCATIONS IN
 STATE.

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC			
818	8780 (PL) FIBER OPTIC & COMMUNICATION EQUIP.	1.000	LSUM
877	5550 (PL) INSTALLATION OF COMMUNICATION CABLE	3,000.000	LF
SECTION NO. 0002 MOBILIZATION			
641	1552 MOBILIZATION	1.000	LSUM

CALL ORDER : 310
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 050728
 PCN : 2143904
 PROJECTS : STP-151C (126)CO
 BRF-151C (136)CO
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 15.17
 CALENDAR DAYS : 120
 RES. ENG.:
 LIQ. DAM.: \$ 750

COUNTIES : MUSKOGEE

CONTRACT DESCRIPTION:

RESURFACING COUNTY ROAD (EW-87): FROM JAMESVILLE, EXTEND EAST TO TAFT. PROJECT LENGTH = 5.034 MILES FLEXIBLE ESALS = 1.5 MILLION ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY - STP-151C(126)CO			
202(G) 0185	EARTHWORK	1.000	LSUM
227 0100	TEMPORARY SILT DIKE	150.000	LF
303 0192	AGGREGATE BASE	73.200	CY
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	1,279.000	TON
407 0250	TACK COAT	6,015.000	GAL
408 5774	PRIME COAT	249.000	GAL
411(S3) 6210	(SP)ASPH.CONC.,TYPE S3(PATCH)(PG64-22OK)	197.100	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	6,877.000	TON
411(S5) 5975	(SP)ASPH.CONC.,TYPE S5(PG 64-22 OK)	3,342.000	TON
417 5267	COLD MILLING PAVEMENT	840.000	SY
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 4763	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	399.900	SY
619(C) 0924	SAWING PAVEMENT	1,250.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	40.000	LF
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	8.000	EA
850(A) 8110	SHEET ALUMINUM SIGNS	98.750	SF
851(D) 8597	FLANGE CHANNEL POSTS(4 LB/FT)	221.000	LF
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	79,350.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
884(A) 8403	(PL)BR.G.RAIL RETROFIT TYPE II	40.000	LF
SECTION NO. 0002 CONSTRUCTION - STP-151C(126)CO			
641 1399	MOBILIZATION	1.000	LSUM
SECTION NO. 0003 ROADWAY -BRF-151C(136)CO			
201 0102	CLEARING AND GRUBBING	1.000	LSUM
202(G) 0185	EARTHWORK	1.000	LSUM
227 0100	TEMPORARY SILT DIKE	100.000	LF
230(A) 2806	SOLID SLAB SODDING	1,800.000	SY
233(A) 2817	VEGETATIVE MULCHING	1.000	AC
303 0192	AGGREGATE BASE	438.000	CY
407 0250	TACK COAT	150.000	GAL
408 5774	PRIME COAT	725.000	GAL
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	332.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	186.000	TON

CALL ORDER : 310
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 050728
 PCN : 2143904
 PROJECTS : STP-151C (126) CO
 BRF-151C (136) CO
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 15.17
 CALENDAR DAYS : 120
 RES. ENG.:
 LIQ. DAM.: \$ 750

COUNTIES : MUSKOGEE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0003	ROADWAY -BRF-151C(136)CO		
509(D) 0325	CLASS C CONCRETE	15.000	CY
SECTION NO. 0004	BRIDGE 'A' - BRF-151C(136)CO		
202(A) 1301	UNCLASSIFIED EXCAVATION	450.000	CY
501(A) 1306	STRUCTURAL EXCAVATION UNCLASSIFIED	224.000	CY
509(A) 1326	CLASS AA CONCRETE	300.480	CY
509(B) 1328	CLASS A CONCRETE	78.600	CY
511(A) 1332	REINFORCING STEEL	58,795.000	LB
601(A) 1351	TYPE I PLAIN RIPRAP	40.000	TON
619(B) 4763	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	1,022.000	SY
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	100.000	LF
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
SECTION NO. 0005	STAKING - BRF-151C(136)CO		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 320
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : NOBLE

CONTRACT ID : 050698
 PCN : 2142304
 PROJECTS : BRF-152C(062)CO
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 8.67
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE & APPROACHES COUNTY ROAD: OVER WARREN CREEK,
 APPROX. 0.7 MILE EAST AND 1.3 MILE NORTH OF LUCIEN. PROJECT
 LENGTH = 0.169 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,300.000	LF
227	0100 TEMPORARY SILT DIKE	250.000	LF
230(A)	2806 SOLID SLAB SODDING	6,075.000	SY
233(A)	2817 VEGETATIVE MULCHING	1.260	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	410.000	TON
509(D)	0325 CLASS C CONCRETE	20.000	CY
601(A)	0297 TYPE I PLAIN RIPRAP	724.000	TON
602(C)	4155 FILTER FABRIC	1,455.000	SY
SECTION NO. 0002 BRIDGE 'A'			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	100.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	115.000	CY
503(A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	376.170	LF
504(E)	1380 CONCRETE RAIL (TR1)	263.170	LF
506(A)	1322 STRUCTURAL STEEL	2,020.000	LB
509(A)	1326 CLASS AA CONCRETE	73.600	CY
509(B)	1328 CLASS A CONCRETE	63.800	CY
511(A)	1332 REINFORCING STEEL	25,390.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	622.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	622.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	1,073.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	273.000	TON
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAKING			
642	0098 STAKING	1.000	LSUM
SECTION NO. 0004 CONSTRUCTION			
641	1399 MOBILIZATION	1.000	LSUM

CALL ORDER : 330
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : OKLAHOMA

CONTRACT ID : 050271
 PCN : 0009513
 PROJECTS : STPY-155A(408)
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 48.77
 CALENDAR DAYS : 230
 RES. ENG.:
 LIQ. DAM.: \$ 2000

CONTRACT DESCRIPTION:

GRADE DRAIN AND SURFACE SH-152: FROM COUNCIL ROAD EAST TO
 MACARTHUR BOULEVARD. PROJECT LENGTH = 3.741 km FLEXIBLE
 ESALS = 9.7 MILLION ASPHALT GRADE = PG 64-22 OK, PG 70-28
 OK, PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS	
SECTION NO. 0001 ROADWAY				
201	M0102	CLEARING AND GRUBBING	1.000	LSUM
202(A)	M0183	UNCLASSIFIED EXCAVATION	10,361.000	M3
202(C)	M0184	UNCLASSIFIED BORROW	12,634.000	M3
205	M4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	M2801	TEMPORARY BALE BARRIER	305.000	M
223	M2802	TEMPORARY SILT FENCE	9,882.000	M
224	M2803	TEMPORARY SEDIMENT FILTER	23.000	EA
226	M2805	TEMPORARY SEDIMENT REMOVAL	1,000.000	M3
227	M0100	TEMPORARY SILT DIKE	305.000	M
230(A)	M2806	SOLID SLAB SODDING	58,868.000	M2
326(A)	M4200	(SP)FLY ASH	6,460.000	T
326(B)	M4210	(SP)LIME	428.000	T
326(E)	M4240	(SP)CEMENTITIOUS STABILIZED SUBGRADE	112,160.000	M2
326(G)	M4260	(SP)LIME PRETREATMENT	22,432.000	M2
403(E)	M0225	TRAFFIC BOUND SURFACE COURSE TYPE E	20.000	T
407	M0250	TACK COAT	72,855.000	L
408	M5774	PRIME COAT	85,533.000	L
411(S2)	M5930	(SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	3,176.000	T
411(S3)	M5935	(SP)ASPH.CONC.,TYPE S3(PG 76-28 OK)	13,522.000	T
411(S3)	M5940	(SP)ASPH.CONC.,TYPE S3(PG 70-28 OK)	807.000	T
411(S3)	M5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	41,817.000	T
411(S4)	M5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	467.000	T
411(S4)	M5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	404.000	T
411(S4)	M5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	3,764.000	T
411(V)	M6010	(SP)ASPH.CONC. TYPE RBL(PG64-22OK)	12,319.000	T
413(A)	M4861	RUMBLE STRIP-METHOD AC-CON	14,967.000	M
414(A1)	M5755	250MM P.C. DOWEL JOINTED CONCRETE PAVE.	4,653.000	M2
418	M4200	(SP)SMA (13 MM NMS)	7,951.000	T
509(D)	M0325	CLASS C CONCRETE	34.000	M3
609(A)	M0287	CONC.CURB(100MM MNTBLE-INTEGRAL)	1,014.000	M
609(B)	M1526	800MM COMB.CRB.& GUT.(200MM BAR.)	469.000	M
610(B)	M0400	200MM CONCRETE DRIVEWAY (H.E.S.)	86.000	M2
611(A)	M2657	MANHOLE (1200MM DIA.)	2.000	EA
611(D)	M4215	MANHOLE FRAME & COVER	2.000	EA
611(E)	M5113	INLET CICI DES. 2 (B)	4.000	EA
611(E)	M5115	INLET CICI DES. 2 (D)	4.000	EA

CALL ORDER : 330
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : OKLAHOMA

CONTRACT ID : 050271
 PCN : 0009513
 PROJECTS : STPY-155A(408)
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 48.77
 CALENDAR DAYS : 230
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
611(G) M4488	INLET FRM&GRT (SSIF-FRM,CIG-GRT-VG-F)	16.000	EA
611(K) M4488	CAST IRON CURB INLETS	40.000	EA
613(B) M0405	450MM R.C.PIPES CLASS III	164.000	M
613(B) M0409	600MM R.C.PIPES CLASS III	99.000	M
613(M) M0897	450MM PREFAB. CULVERT END SEC., ROUND	2.000	EA
613(P) M1092	200MM PERFORATED PIPE UNDERDRAIN ROUND	200.000	M
613(Q) M1097	200MM NON-PERF.PIPES UNDERDRAIN RND.	75.000	M
619(A) M0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) M4725	REMOVAL OF FENCE	283.000	M
619(B) M4727	REMOVAL OF CONCRETE PAVEMENT	2,959.000	M2
619(B) M4728	REMOVAL OF ASPHALT PAVEMENT	15,715.000	M2
619(C) M0924	SAWING PAVEMENT	55.000	M
623(A) M0932	BEAM GUARD RAIL-W-BEAM-SINGLE	794.000	M
623(E) M7114	THREE BEAM BRIDGE CONNECTION-TYPE A	12.000	EA
623(H) M8571	(SP)G.E.T. GUARD RAIL END SECTION	12.000	EA
624(C) M4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	288.000	M
SECTION NO. 0002 TRAFFIC			
627(H) M5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	87.000	M
804(A) M2915	STRUCTURAL CONCRETE	15.000	M3
804(B) M2916	REINFORCING STEEL	1,115.000	KG
850(A) M8110	SHEET ALUMINUM SIGNS	57.000	M2
850(B) M8112	EXTRUDED ALUMINUM PANEL SIGNS	25.000	M2
851(A) M3206	100MM@19.3 GALV.STL.WD.FLANGE BM.POST	18.400	M
851(A) M3207	150MM@22.3 GALV.STL.WD.FLANGE BM.POST	13.400	M
851(A) M3208	150MM@29.8 GALV.STL.WD.FLANGE BM.POST	14.600	M
851(B) M3217	64MM@8.62 GALV.STL.PIPE POST	261.000	M
851(B) M3218	75MM@11.28 GALV.STL.PIPE POST	16.800	M
855(A) M8812	TRAFFIC STRIPE(PLASTIC)(100MM WIDE)	18,976.000	M
855(B) M8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	6.000	EA
855(B) M8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	3.000	EA
870 M8011	SAND FILLED IMPACT ATTEN.MODULE REMOVAL	1.000	LSUM
870(A) M8011	SAND FILLED IMPACT ATTEN.MODULE	6.000	EA
880(J) M8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890(A) M8722	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
SECTION NO. 0003 STAKING			
642 M0098	STAKING	1.000	LSUM

CALL ORDER : 330
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : OKLAHOMA

CONTRACT ID : 050271
 PCN : 0009513
 PROJECTS : STPY-155A(408)
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 48.77
 CALENDAR DAYS : 230
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0004	CONSTRUCTION		
640	M1426 FIELD OFFICE	1.000	EA
641	M1552 MOBILIZATION	1.000	LSUM
643	M0087 (SP) CONTRACTORS QUALITY CONTROL	1.000	LSUM

CALL ORDER : 335
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 TR
 COUNTIES : OKLAHOMA

CONTRACT ID : 050739
 PCN : 2044004
 PROJECTS : IMG-35-3(275) 128
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 34.13
 CALENDAR DAYS : 180
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 SAFETY IMPROVEMENT I-35/I-40; AT THE FT. SMITH INTERCHANGE.
 PROJECT LENGTH = 0.00 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC ITEMS			
509(B) 0321	CLASS A CONCRETE	6.630	CY
802(B) 8340	2" PVC SCH.40 PLASTIC CONDUIT BORED	800.000	LF
802(B) 8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	18,900.000	LF
802(B) 8344	3" PVC SCH.40 PLASTIC CONDUIT BORED	250.000	LF
802(B) 8346	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	600.000	LF
802(B) 8352	6" PVC SCH.40 PLASTIC CONDUIT TRENCHED	100.000	LF
803 8066	PULL BOX(SIZE II)	2.000	EA
803 8075	GROUND BOX, R1	3.000	EA
804(B) 2916	REINFORCING STEEL	34.620	LB
810(A) 3118	SERVICE POLE	2.000	EA
811 8032	1/C NO.0 ELECT.COND.	2,850.000	LF
815 8610	(PL)CCTV CAMERA, PAN-TILT-ZOOM	13.000	EA
815 8615	(PL)CCTV CAMERA, WEB	13.000	EA
815 8620	(PL)CCTV CAMERA POLE	4.000	EA
815 8630	(PL)PROVIDE SERVICE/MAINTENANCE FOR CCTV	120.000	HOURL
818 8715	(PL)FIBER OPTIC CABLE, 24, SMF-28	200.000	LF
818 8720	(PL)FIBER OPTIC CABLE, 48, SMF-28	10,100.000	LF
818 8735	(PL)FIBER OPTIC CABLE SPLICE	106.000	EA
818 8740	(PL)FIBER OPTIC CABLE TERMINATION	70.000	EA
818 8745	(PL)FIBER OPTIC PATCH PANEL, 24 PORT	5.000	EA
818 8760	(PL)FIBER OPTIC PATCH PANEL CABEL, 5'	24.000	EA
818 8780	(PL)FIBER OPTIC & COMMUNICATION EQUIP.	1.000	LSUM
877 5545	(PL)NETWORK EQUIPMENT PACKAGE A	3.000	EA
877 5546	(PL)NETWORK EQUIPMENT PACKAGE B	1.000	EA
877 5550	(PL)INSTALLATION OF COMMUNICATION CABLE	500.000	LF
877 5570	(PL)FIBER OPTIC ROUTE SIGN & INSTALLATIO	18.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	1.000	SD
887 8370	(PL)SHIELD ISOLATION PEDESTAL	10.000	EA
890(A) 8704	(PL)REMOVAL OF PULL BOX	2.000	EA
895 6551	CABINET	3.000	EA
SECTION NO. 0002 CONSTRUCTION			
641 1552	MOBILIZATION	1.000	LSUM

CALL ORDER : 360
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : OTTAWA

CONTRACT ID : 050700
 PCN : 1993304
 PROJECTS : BRO-158D(49)CO
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 8.67
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE & APPROACHES COUNTY ROAD; OVER ELM CREEK, APPROX. 0.
 9 MILE NORTH AND 2.0 MILES WEST OF JCT OF SH-10/SH-137.
 PROJECT LENGTH = 0.13 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	510.000	LF
227	0100 TEMPORARY SILT DIKE	400.000	LF
230(A)	2806 SOLID SLAB SODDING	3,240.000	SY
233(A)	2817 VEGETATIVE MULCHING	0.500	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	518.000	TON
509(D)	0325 CLASS C CONCRETE	10.000	CY
SECTION NO. 0002 BRIDGE 'A'			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	81.000	CY
501(C)	1308 SUBSTRUCTURE EXCAVATION ROCK	47.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	40.000	CY
503(B)	6144 PRESTRESSED CONCRETE DOUBLE TEE	440.000	LF
504(E)	1380 CONCRETE RAIL (TR1)	265.000	LF
509(A)	1326 CLASS AA CONCRETE	82.000	CY
509(B)	1328 CLASS A CONCRETE	67.000	CY
511(A)	1332 REINFORCING STEEL	20,722.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	110.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	110.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	520.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	180.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAKING			
642	0098 STAKING	1.000	LSUM
SECTION NO. 0004 CONSTRUCTION			
640	1398 FIELD OFFICE	1.000	EA
641	1399 MOBILIZATION	1.000	LSUM

CALL ORDER : 370
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : PONTOTOC

CONTRACT ID : 050717
 PCN : 0534604
 PROJECTS : BRFY-062B(231)
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 62.86
 CALENDAR DAYS : 270
 RES. ENG.:
 LIQ. DAM.: \$ 800

CONTRACT DESCRIPTION:

GRADE, DRAIN, BRIDGE & SURFACE SH-99: MILL CREEK BRIDGE
 SOUTH OF FITTSTOWN. PROJECT LENGTH = 0.554 MILE FLEXIBLE
 ESALS = N/A ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY ITEMS			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	43,787.000	CY
202(C)	0184 UNCLASSIFIED BORROW	6,176.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,100.000	LF
226	2805 TEMPORARY SEDIMENT REMOVAL	100.000	CY
227	0100 TEMPORARY SILT DIKE	147.000	LF
229	4318 DITCH LINER PROTECTION	2,129.000	LF
230(A)	2806 SOLID SLAB SODDING	19,532.000	SY
230(B)	2807 MULCH SODDING	28,158.000	SY
230(F)	2812 WATERING	1,908.000	MGAL
232(B)	2814 SEEDING METHOD B	10.760	AC
233(A)	2817 VEGETATIVE MULCHING	10.760	AC
234(A)	2824 FERTILIZING (10-20-10)	4.770	TON
234(A)	4406 FERTILIZING (0-46-0)	0.740	TON
235(A)	0100 (PL)ROCK FILTER DAM, TYPE 1	9.000	CY
238	0300 (PL)TEMPORARY SEDIMENT TRAP	6.000	EA
241	2832 MOWING	9.850	AC
303	0192 AGGREGATE BASE	3,992.000	CY
325	5271 SEPARATOR FABRIC	19,994.000	SY
326(A)	4200 (SP)FLY ASH	810.000	TON
326(B)	4210 (SP)LIME	82.000	TON
326(E)	4240 (SP)CEMENTITIOUS STABILIZED SUBGRADE	18,403.000	SY
326(G)	4260 (SP)LIME PRETREATMENT	7,504.000	SY
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	2,524.000	TON
407	0250 TACK COAT	2,464.000	GAL
408	5774 PRIME COAT	8,220.000	GAL
411(S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	9,400.000	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	2,799.000	TON
501(A)	0313 STRUCTURAL EXCAVATION UNCLASSIFIED	34.000	CY
509(B)	0321 CLASS A CONCRETE	65.770	CY
509(D)	0325 CLASS C CONCRETE	329.000	CY
511(A)	0332 REINFORCING STEEL	8,382.000	LB
601(A-1)	0536 TYPE I-A PLAIN RIPRAP	134.000	TON
613(B)	0491 18" R.C.PIPE CLASS III	339.000	LF
613(CC)	7196 TYPE A6 CULVERT END TREATMENT	28.000	EA
613(CC)	7197 TYPE B6 CULVERT END TREATMENT	2.000	EA

CALL ORDER : 370
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : PONTOTOC

CONTRACT ID : 050717
 PCN : 0534604
 PROJECTS : BRFY-062B(231)
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 62.86
 CALENDAR DAYS : 270
 RES. ENG.:
 LIQ. DAM.: \$ 800

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY ITEMS			
613(D) 0689	18" CORR. GALV. STEEL PIPE	312.000	LF
613(D) 0690	24" CORR. GALV. STEEL PIPE	80.000	LF
613(D) 4527	21" X 15" CORR. GALV. STEEL PIPE ARCH	254.000	LF
613(P) 1092	8" PERFORATED PIPE UNDERDRAIN ROUND	209.000	LF
613(Q) 1097	8" NON-PERF. PIPE UNDERDRAIN RND.	70.000	LF
613(R) 1100	PIPE UNDERDRAIN COVER MAT'L.	63.000	CY
613(S) 1180	TRENCH EXCAVATION	84.000	CY
613(T) 1181	STANDARD BEDDING MATERIAL	14.000	CY
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 0291	REMOVAL OF HEADWALL	3.000	EA
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	7,960.000	SY
619(C) 0924	SAWING PAVEMENT	2,622.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	612.500	LF
623(E) 7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	4.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	4.000	EA
624(A) 4281	FENCE-STYLE WWF	204.000	LF
624(C) 4459	(SP)FENCE-STYLE SWF (5 BARBED WIRE)	2,214.000	LF
653(C) 5946	OUTLET LATERAL HEADWALL	1.000	EA
SECTION NO. 0002 BRIDGE ITEMS			
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	100.000	CY
501(F) 6352	GRANULAR BACKFILL	440.000	CY
503(A) 6290	PRESTRESSED CONCRETE BEAMS (TYPE J BT)	479.000	LF
504(A) 1304	APPROACH SLAB	315.200	SY
504(E) 6245	CONCRETE RAIL (TR4)	383.000	LF
506(A) 1322	STRUCTURAL STEEL	800.000	LB
509(A) 1326	CLASS AA CONCRETE	212.300	CY
509(B) 1328	CLASS A CONCRETE	89.000	CY
511(B) 6010	EPOXY COATED REINFORCING STEEL	53,020.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	684.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	684.000	LF
514(F) 6354	PILE LOAD TEST (DYNAMIC)	24.000	EA
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	500.000	SY
523(A) 6550	(SP) SEALER CRACK PREPARATION	82.000	LF
523(B) 6560	(SP) SEALER RESIN	52.000	GAL
535 6164	(PL)FIXED BEARING ASSEMBLY	8.000	EA
601(A-1)1353	TYPE I-A PLAIN RIPRAP	420.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	85.000	TON
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	86.000	LF
613(Q) 6207	6" NON-PERF. PIPE UNDERDRAIN RND.	150.000	LF
619(B) 2500	(PL)REMOVAL OF BRIDGE ITEMS	1.000	LSUM

CALL ORDER : 370
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : PONTOTOC

CONTRACT ID : 050717
 PCN : 0534604
 PROJECTS : BRFY-062B(231)
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 62.86
 CALENDAR DAYS : 270
 RES. ENG.:
 LIQ. DAM.: \$ 800

SECTION NO. 0003		TRAFFIC ITEMS		
850(A)	8110	SHEET ALUMINUM SIGNS	53.220	SF
855(A)	8812	TRAFFIC STRIPE (PLASTIC) (4" WIDE)	13,900.000	LF
856(A)	8839	CONSTRUCTION TRAFF.STR. (PAINT) (4" WIDE)	12,400.000	LF
880(J)	8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0004		STAKING		
642	0098	STAKING	1.000	LSUM
SECTION NO. 0005		CONSTRUCTION		
640	1398	FIELD OFFICE	1.000	EA
641	1552	MOBILIZATION	1.000	LSUM
643	0087	(SP) CONTRACTORS QUALITY CONTROL	1.000	LSUM

CALL ORDER : 390
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : ROGERS

CONTRACT ID : 050702
 PCN : 2278304
 PROJECTS : STPY-166A(172)TR
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 6.50
 CALENDAR DAYS : 30
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 TRAFFIC SIGNAL SH-66; AT LOWERY ROAD IN THE CITY OF
 CLAREMORE. PROJECT LENGTH = 0.00 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNAL			
802(B) 8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	160.000	LF
802(B) 8344	3" PVC SCH.40 PLASTIC CONDUIT BORED	350.000	LF
802(B) 8346	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	100.000	LF
803 8065	PULL BOX(SIZE I)	3.000	EA
803 8066	PULL BOX(SIZE II)	1.000	EA
804(A) 2915	STRUCTURAL CONCRETE	11.200	CY
804(B) 2916	REINFORCING STEEL	1,705.000	LB
806(A) 8313	32'MH POLE 45'TS & 10'LMA(G.STL.)	2.000	EA
806(A) 8351	32'MH POLE 25',TS & 10'LMA(G.STL.)	2.000	EA
809(A) 8090	(PL)ROADWAY LUMINAIRE	4.000	EA
810(A) 3118	SERVICE POLE	1.000	EA
811 8040	1/C NO.6 ELECT.COND.	200.000	LF
811 8044	1/C NO.10 ELECT.COND.	1,690.000	LF
825 8550	VEH.ACT.SOL.ST.TRAF.SIG.CON.ASM	1.000	EA
831 8231	1WAY3SEC.ADJ.SIG.HD.S-6	11.000	EA
831 8252	1WAY3SEC.ADJ.SIG.HD.S-9	2.000	EA
833 3030	BACKPLATE	13.000	EA
834(A) 8207	5/C TRAF.SIG.EL.CABLE	710.000	LF
834(A) 8209	9/C TRAF.SIG.EL.CABLE	700.000	LF
834(B) 8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	260.000	LF
850(A) 8110	SHEET ALUMINUM SIGNS	21.900	SF
850(C) 8118	MAST ARM MOUNTED SIGNS(ALUM.)	43.500	SF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	8,100.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	6.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	7.000	EA
855(B) 8824	TRAFFIC STRIPE(PLASTIC)(SYMBOLS)	7.000	EA
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	3,800.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890(A) 8724	(PL)REMOVAL OF EXISTING SIGNS	5.000	EA
SECTION NO. 0002 ADD ALT. NO 1			
828 8132	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
SECTION NO. 0003 ADD ALT. NO 2			
802(B) 8334	1" PVC SCH.40 PLASTIC CONDUIT TRENCHED	85.000	LF
802(B) 8338	1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCH	795.000	LF

CALL ORDER : 390
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : ROGERS

CONTRACT ID : 050702
 PCN : 2278304
 PROJECTS : STPY-166A(172)TR
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 6.50
 CALENDAR DAYS : 30
 RES. ENG.:
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	ADD ALT. NO 2		
803 8067	PULL BOX(SIZE III)	4.000	EA
828(A) 8135	SOL.STE.DIGITAL IND.VEH.LP.DET.	8.000	EA
828(B) 8138	LOOP DETECTOR WIRE	3,810.000	LF
834(B) 8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	2,045.000	LF
SECTION NO. 0004	STAKING		
642 0098	STAKING	1.000	LSUM
SECTION NO. 0005	CONSTRUCTION		
641 1552	MOBILIZATION	1.000	LSUM

CALL ORDER : 430
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : STEPHENS

CONTRACT ID : 050705
 PCN : 2131504
 PROJECTS : BRO-169D(090)CO
 DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 8.67
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES COUNTY ROAD(EW-172): OVER STAGE STAND
 CREEK, APPROX. 0.7 MILE WEST AND 2.2 MILE NORTH OF JCT
 US-81/SH-7. PROJECT LENGTH = 0.283 MILES FLEXIBLE ESALS = 0.
 2 MILLION ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
223	2801 TEMPORARY SILT FENCE	1,750.000	LF
227	0100 TEMPORARY SILT DIKE	212.000	LF
230(A)	2806 SOLID SLAB SODDING	14,107.000	SY
233(A)	2817 VEGETATIVE MULCHING	5.800	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	21.000	TON
411(S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	839.000	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	411.000	TON
509(D)	0325 CLASS C CONCRETE	10.000	CY
613(D)	4527 21" X 15" CORR. GALV. STEEL PIPE ARCH	62.000	LF
613(M)	4504 21" X 15" PREFAB. CULVERT END SEC., ARCH	2.000	EA
850(A)	8110 SHEET ALUMINUM SIGNS	8.000	SF
851(C)	8321 1 3/4" SQUARE TUBE POST	26.000	LF
854(A)	8800 TRAFFIC STRIPE(PAINT)(4" WIDE)	3,000.000	LF
SECTION NO. 0002 BRIDGE 'A'			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	96.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	114.000	CY
503(A)	1313 PRESTRESSED CONCRETE BEAMS (TYPE IV)	416.170	LF
504(E)	1380 CONCRETE RAIL (TR1)	283.160	LF
506(A)	1322 STRUCTURAL STEEL	2,020.000	LB
509(A)	1326 CLASS AA CONCRETE	80.900	CY
509(B)	1328 CLASS A CONCRETE	63.800	CY
511(A)	1332 REINFORCING STEEL	26,881.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	160.000	LF
514(A)	6011 PILES, FURNISHED (HP 12X53)	680.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	160.000	LF
514(B)	6294 PILES, DRIVEN (HP 12X53)	680.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	1,108.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	322.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 430
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : STEPHENS

CONTRACT ID : 050705
 PCN : 2131504
 PROJECTS : BRO-169D(090)CO
 DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 8.67
 CALENDAR DAYS : 90
 RES. ENG.:
 LIQ. DAM.: \$ 500

SECTION NO. 0003	STAKING		
642 0098	STAKING	1.000	LSUM
SECTION NO. 0004	CONSTRUCTION		
641 1399	MOBILIZATION	1.000	LSUM

CALL ORDER : 435
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 050742
 PCN : 1842904
 PROJECTS : STP-172B(151) IG
 STPG-172B(267) IG
 STP-172B(152) IG
 STPG-172B(268) IG
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 63.95
 CALENDAR DAYS : 180
 RES. ENG.:
 LIQ. DAM.: \$ 1000

COUNTIES : TULSA

CONTRACT DESCRIPTION:
 INTERSECTION MODIFICATION AND TRAFFIC SIGNALS CITY STREET:
 121ST AT ELM STREET IN JENKS/ CITY STREET: MAIN ST AT
 NOGALES (ADAMS) IN JENKS. PROJECT LENGTH = 0.479 MILE
 FLEXIBLE ESALS = 2.9 MILLION ASPHALT GRADE = PG 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADWAY STP-172B(151) IG		
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	2,339.000	CY
202(C)	0184 UNCLASSIFIED BORROW	4,261.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	240.000	LF
223	2801 TEMPORARY SILT FENCE	2,670.000	LF
224	2803 TEMPORARY SEDIMENT FILTER	2.000	EA
226	2805 TEMPORARY SEDIMENT REMOVAL	95.000	CY
230(A)	2806 SOLID SLAB SODDING	7,935.000	SY
303	0192 AGGREGATE BASE	1,262.000	CY
325	5271 SEPARATOR FABRIC	7,945.000	SY
326(B)	4210 (SP)LIME	191.000	TON
326(F)	4250 (SP)LIME STABILIZED SUBGRADE	5,676.000	SY
403(A)	0217 TRAFFIC BOUND SURFACE COURSE TYPE A	50.000	TON
408	5774 PRIME COAT	852.000	GAL
411(S2)	5930 (SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	1,935.000	TON
411(S3)	5945 (SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	666.000	TON
411(S4)	5960 (SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	806.000	TON
414(A1)	5754 9" P.C. DOWEL JOINTED CONCRETE PAVEMENT	5,339.000	SY
417	4267 COLD MILLING BITUMINOUS PAVEMENT	3,156.000	SY
501(A)	0313 STRUCTURAL EXCAVATION UNCLASSIFIED	59.000	CY
509(B)	0321 CLASS A CONCRETE	10.450	CY
511(A)	0332 REINFORCING STEEL	3,950.000	LB
609(A)	0300 CONC.CURB(6" BARRIER-INTEGRAL)	1,868.000	LF
609(B)	0383 COMBINED CURB & GUTTER(6" BARRIER)	2,205.000	LF
610(B)	0399 6" CONCRETE DRIVEWAY (H.E.S.)	457.000	SY
610(G)	4142 BITUMINOUS DRIVEWAY	140.000	SY
611(A)	2657 MANHOLE (4' DIA.)	1.000	EA
611(A)	2658 MANHOLE (5' DIA.)	1.000	EA
611(B)	2681 ADD'L.DEPTH IN MANHOLE (5' DIA.)	0.710	VF
611(D)	4215 MANHOLE FRAME & COVER	11.000	EA
611(E)	5101 INLET CICI DES. 1 (A)	1.000	EA
611(E)	5112 INLET CICI DES. 2 (STD)	2.000	EA
611(E)	5113 INLET CICI DES. 2 (B)	4.000	EA

CALL ORDER : 435
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 050742
 PCN : 1842904
 PROJECTS : STP-172B(151) IG
 STPG-172B(267) IG
 STP-172B(152) IG
 STPG-172B(268) IG
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 63.95
 CALENDAR DAYS : 180
 RES. ENG.:
 LIQ. DAM.: \$ 1000

COUNTIES : TULSA

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROADWAY STP-172B(151) IG			
611(E) 5872	INLET W/LRG.JCT.BOX,CICI-JB-1,DES.2(B)	2.000	EA
611(E) 6002	INLET (SMD-TYPE 2)	1.000	EA
611(F) 5320	INLET CICI DES. 1 (ADD'L DEPTH)	2.470	VF
611(F) 5325	INLET CICI DES. 2 (ADD'L DEPTH)	22.820	VF
611(G) 4488	INLET FRM&GRT (SSIF-FRM,CIG-GRT-VG-F)	17.000	EA
611(J) 0487	JUNCTION BOXES	757.870	CF
611(K) 4488	CAST IRON CURB INLETS	32.000	EA
613(B) 0491	18" R.C.PIPE CLASS III	242.000	LF
613(B) 0492	24" R.C.PIPE CLASS III	358.000	LF
613(B) 0493	30" R.C.PIPE CLASS III	401.000	LF
613(B) 0494	36" R.C.PIPE CLASS III	99.000	LF
613(B) 0496	48" R.C.PIPE CLASS III	417.000	LF
613(B) 0498	60" R.C.PIPE CLASS III	123.000	LF
613(M) 5726	18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
613(M) 5730	24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
613(M) 5732	30" PREFAB. CULVERT END SEC., ROUND	2.000	EA
613(P) 1089	4" PERFORATED PIPE UNDERDRAIN ROUND	100.000	LF
613(Q) 1094	4" NON-PERF.PIPE UNDERDRAIN RND.	10.000	LF
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	1,376.000	SY
619(B) 4766	REMOVAL OF CONCRETE DRIVEWAY	147.000	SY
619(C) 0924	SAWING PAVEMENT	5,121.000	LF
629(E) 5048	REMOVE AND RESET MAILBOX	2.000	EA
SECTION NO. 0002 STAKING STP-172B(151) IG			
642 0098	STAKING	1.000	LSUM
SECTION NO. 0003 CONSTRUCTION STP-172B(151) IG			
640 1398	FIELD OFFICE	1.000	EA
641 1399	MOBILIZATION	1.000	LSUM
SECTION NO. 0004 NON-PARTICIPATING ITEMS STP-172B(151) IG			
612(G) 0647	VALVE BOXES ADJUST TO GRADE	1.000	EA
612(H) 0648	METER BOXES ADJUST TO GRADE	1.000	EA
616(A) 5123	10" DUCTILE IRON PIPE	888.000	LF
616(D) 0863	10" VALVES	2.000	EA
616(D) 7026	10" SOLID SLEEVE	3.000	EA
616(D) 7030	10" 90 DEGREE FITTING	2.000	EA

CALL ORDER : 435
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 050742
 PCN : 1842904
 PROJECTS : STP-172B(151) IG
 STPG-172B(267) IG
 STP-172B(152) IG
 STPG-172B(268) IG
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 63.95
 CALENDAR DAYS : 180
 RES. ENG.:
 LIQ. DAM.: \$ 1000

COUNTIES : TULSA

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0004	NON-PARTICIPATING ITEMS STP-172B(151) IG		
616(J) 0041	10" X 10" X 10" TEE	2.000	EA
SECTION NO. 0005	TRAFFIC STPG-172B(267) IG		
802(B) 8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	20.000	LF
802(B) 8344	3" PVC SCH.40 PLASTIC CONDUIT BORED	270.000	LF
802(B) 8346	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	20.000	LF
803 8065	PULL BOX(SIZE I)	4.000	EA
803 8066	PULL BOX(SIZE II)	1.000	EA
804(A) 2915	STRUCTURAL CONCRETE	11.500	CY
804(B) 2916	REINFORCING STEEL	1,767.000	LB
806(A) 8328	32'MH POLE 40'TS & 12'LMA(G.STL.)	1.000	EA
806(A) 8331	32'MH POLE 35'TS & 12'LMA(G.STL.)	2.000	EA
806(A) 8732	POLE & 40' TS MST.ARM(G.STL.)	1.000	EA
809(A) 8090	(PL)ROADWAY LUMINAIRE	3.000	EA
810(A) 3118	SERVICE POLE	1.000	EA
811 8040	1/C NO.6 ELECT.COND.	200.000	LF
811 8044	1/C NO.10 ELECT.COND.	1,160.000	LF
825 8550	VEH.ACT.SOL.ST.TRAF.SIG.CON.ASM	1.000	EA
828 8132	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
831 8231	1WAY3SEC.ADJ.SIG.HD.S-6	8.000	EA
831 8286	1WAY5SEC.ADJ.SIG.HD.S-19	4.000	EA
833 3030	BACKPLATE	12.000	EA
834(A) 8207	5/C TRAF.SIG.EL.CABLE	480.000	LF
834(A) 8208	7/C TRAF.SIG.EL.CABLE	325.000	LF
834(A) 8210	12/C TRAF.SIG.EL.CABLE	455.000	LF
834(A) 8212	18/C TRAF.SIG.EL.CABLE	120.000	LF
834(B) 8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	40.000	LF
840(B) 8593	(PL)E.P.S. OPTICAL DETECTOR	4.000	EA
840(C) 8594	(PL)E.P.S. OPTICAL DETECTOR CABLE	650.000	LF
840(D) 8595	(PL)E.P.S. 2 CHANNEL PHASE SELECTOR	2.000	EA
850(A) 8110	SHEET ALUMINUM SIGNS	75.250	SF
850(C) 8118	MAST ARM MOUNTED SIGNS(ALUM.)	76.500	SF
851(C) 8327	2 1/4" SQUARE TUBE POST	142.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC) (4" WIDE)	10,279.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC) (ARROWS)	14.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC) (WORDS)	5.000	EA
856(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT) (4" WIDE)	7,000.000	LF
856(G) 8881	(PL)CONSTRUCTION ZONE PAVEMENT MARKERS	200.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890 7700	(PL)TRAFFIC ITEMS	1.000	LSUM

CALL ORDER : 435
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 050742
 PCN : 1842904
 PROJECTS : STP-172B(151) IG
 STPG-172B(267) IG
 STP-172B(152) IG
 STPG-172B(268) IG
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 63.95
 CALENDAR DAYS : 180
 RES. ENG.:
 LIQ. DAM.: \$ 1000

COUNTIES : TULSA

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0005	TRAFFIC STPG-172B(267) IG		
890(A) 8724	(PL)REMOVAL OF EXISTING SIGNS	24.000	EA

SECTION NO. 0006	ROADWAY STP-172B(152) IG		
201 0102	CLEARING AND GRUBBING	1.000	LSUM
202(A) 0183	UNCLASSIFIED EXCAVATION	1,300.000	CY
202(C) 0184	UNCLASSIFIED BORROW	740.000	CY
205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222 2801	TEMPORARY BALE BARRIER	108.000	LF
223 2801	TEMPORARY SILT FENCE	1,420.000	LF
224 2803	TEMPORARY SEDIMENT FILTER	3.000	EA
226 2805	TEMPORARY SEDIMENT REMOVAL	157.000	CY
230(A) 2806	SOLID SLAB SODDING	5,178.000	SY
303 0192	AGGREGATE BASE	868.000	CY
325 5271	SEPARATOR FABRIC	5,171.000	SY
326(B) 4210	(SP)LIME	137.000	TON
326(F) 4250	(SP)LIME STABILIZED SUBGRADE	4,052.000	SY
403(A) 0217	TRAFFIC BOUND SURFACE COURSE TYPE A	80.000	TON
408 5774	PRIME COAT	608.000	GAL
411(S2) 5930	(SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	746.000	TON
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	556.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	821.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	161.000	SY
501(A) 0313	STRUCTURAL EXCAVATION UNCLASSIFIED	55.000	CY
509(B) 0321	CLASS A CONCRETE	51.000	CY
511(A) 0332	REINFORCING STEEL	6,664.000	LB
609(B) 0383	COMBINED CURB & GUTTER(6" BARRIER)	1,810.000	LF
610(B) 0399	6" CONCRETE DRIVEWAY (H.E.S.)	49.000	SY
610(G) 4142	BITUMINOUS DRIVEWAY	151.000	SY
611(A) 2658	MANHOLE (5' DIA.)	3.000	EA
611(B) 2681	ADD'L.DEPTH IN MANHOLE (5' DIA.)	0.470	VF
611(D) 4215	MANHOLE FRAME & COVER	5.000	EA
611(E) 5101	INLET CICI DES. 1 (A)	2.000	EA
611(E) 5109	INLET CICI DES. 1 (2B)	4.000	EA
611(E) 5852	INLET W/LRG.JCT.BOX,CICI-JB-1,DES.1(A)	1.000	EA
611(E) 5872	INLET W/LRG.JCT.BOX,CICI-JB-1,DES.2(B)	1.000	EA
611(E) 6000	INLET (SMD-TYPE 1)	1.000	EA
611(E) 6002	INLET (SMD-TYPE 2)	2.000	EA
611(G) 4488	INLET FRM&GRT (SSIF-FRM,CIG-GRT-VG-F)	10.000	EA
611(K) 4488	CAST IRON CURB INLETS	20.000	EA
613(B) 0491	18" R.C.PIPE CLASS III	380.000	LF

CALL ORDER : 435
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 050742
 PCN : 1842904
 PROJECTS : STP-172B(151) IG
 STPG-172B(267) IG
 STP-172B(152) IG
 STPG-172B(268) IG
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 63.95
 CALENDAR DAYS : 180
 RES. ENG.:
 LIQ. DAM.: \$ 1000

COUNTIES : TULSA

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0006 ROADWAY STP-172B(152) IG			
613(B) 0492	24" R.C.PIPE CLASS III	160.000	LF
613(B) 0494	36" R.C.PIPE CLASS III	613.000	LF
613(M) 5726	18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
613(M) 5734	36" PREFAB. CULVERT END SEC., ROUND	1.000	EA
613(P) 1089	4" PERFORATED PIPE UNDERDRAIN ROUND	100.000	LF
613(Q) 1094	4" NON-PERF.PIPE UNDERDRAIN RND.	10.000	LF
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	346.000	SY
619(C) 0924	SAWING PAVEMENT	3,114.000	LF
627(E) 4314	PRECAST CONC. MEDIAN BARRIER, PORT. TYPE	200.000	LF
627(G) 4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	200.000	LF
SECTION NO. 0007 STAKING STP-172B(152) IG			
642 0098	STAKING	1.000	LSUM
SECTION NO. 0008 CONSTRUCTION STP-172B(152) IG			
640 1398	FIELD OFFICE	1.000	EA
SECTION NO. 0009 NON-PARTICIPATING STP-172B(152) IG			
612(A) 0641	MANHOLES ADJUST TO GRADE	3.000	EA
612(G) 0647	VALVE BOXES ADJUST TO GRADE	3.000	EA
616(G) 1192	FIRE HYDRANTS	1.000	EA
SECTION NO. 0010 TRAFFIC STPG-152B(268) IG			
802(B) 8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	25.000	LF
802(B) 8346	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	300.000	LF
803 8065	PULL BOX(SIZE I)	3.000	EA
803 8066	PULL BOX(SIZE II)	1.000	EA
804(A) 2915	STRUCTURAL CONCRETE	11.600	CY
804(B) 2916	REINFORCING STEEL	1,309.800	LB
806(A) 8328	32'MH POLE 40'TS & 12'LMA(G.STL.)	2.000	EA
806(A) 8732	POLE & 40' TS MST.ARM(G.STL.)	1.000	EA
809(A) 8090	(PL)ROADWAY LUMINAIRE	2.000	EA
810(A) 3118	SERVICE POLE	1.000	EA
811 8040	1/C NO.6 ELECT.COND.	270.000	LF
811 8044	1/C NO.10 ELECT.COND.	350.000	LF
825 8550	VEH.ACT.SOL.ST.TRAF.SIG.CON.ASM	1.000	EA

CALL ORDER : 435
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 050742
 PCN : 1842904
 PROJECTS : STP-172B(151) IG
 STPG-172B(267) IG
 STP-172B(152) IG
 STPG-172B(268) IG
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 63.95
 CALENDAR DAYS : 180
 RES. ENG.:
 LIQ. DAM.: \$ 1000

COUNTIES : TULSA

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0010	TRAFFIC STPG-152B(268) IG		
828	8132 (PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
831	8231 1WAY3SEC.ADJ.SIG.HD.S-6	6.000	EA
831	8286 1WAY5SEC.ADJ.SIG.HD.S-19	1.000	EA
833	3030 BACKPLATE	7.000	EA
834(A)	8207 5/C TRAF.SIG.EL.CABLE	290.000	LF
834(A)	8208 7/C TRAF.SIG.EL.CABLE	120.000	LF
834(A)	8210 12/C TRAF.SIG.EL.CABLE	380.000	LF
840(B)	8593 (PL)E.P.S. OPTICAL DETECTOR	3.000	EA
840(C)	8594 (PL)E.P.S. OPTICAL DETECTOR CABLE	475.000	LF
840(D)	8595 (PL)E.P.S. 2 CHANNEL PHASE SELECTOR	2.000	EA
850(A)	8110 SHEET ALUMINUM SIGNS	18.000	SF
850(C)	8118 MAST ARM MOUNTED SIGNS(ALUM.)	43.500	SF
851(C)	8327 2 1/4" SQUARE TUBE POST	41.000	LF
855(A)	8812 TRAFFIC STRIPE(PLASTIC)(4" WIDE)	8,356.000	LF
855(B)	8818 TRAFFIC STRIPE(PLASTIC)(ARROWS)	5.000	EA
855(B)	8821 TRAFFIC STRIPE(PLASTIC)(WORDS)	3.000	EA
856(A)	8839 CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	5,000.000	LF
856(G)	8881 (PL)CONSTRUCTION ZONE PAVEMENT MARKERS	150.000	EA
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890	7700 (PL)TRAFFIC ITEMS	1.000	LSUM
890(A)	8724 (PL)REMOVAL OF EXISTING SIGNS	8.000	EA

CALL ORDER : 450
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : WOODWARD

CONTRACT ID : 050646
 PCN : 1745710
 PROJECTS : NHY-017N (053)
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 79.11
 CALENDAR DAYS : 255
 RES. ENG.: DISTRICT 6 (BUFFALO)
 LIQ. DAM.: \$ 2000

CONTRACT DESCRIPTION:

SURFACING US-270/183: BEGIN APPROX. .8 MILES SOUTH EAST OF
 SH-50, EXTEND NORTHWEST. PROJECT LENGTH = 4.536 MILES
 FLEXIBLE ESALS = 6.4 MILLION ASPHALT GRADE = PG 64-22 OK,
 PG 76-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADWAY		
202 (A) 0183	UNCLASSIFIED EXCAVATION	30,573.000	CY
202 (C) 0184	UNCLASSIFIED BORROW	59,297.000	CY
205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
210 0121	OBLITERATING ABANDONED ROAD	30.000	STA
222 2801	TEMPORARY BALE BARRIER	200.000	LF
223 2803	TEMPORARY SILT FENCE	9,265.000	LF
224 2803	TEMPORARY SEDIMENT FILTER	4.000	EA
225 2804	TEMPORARY SEDIMENT BASIN	16.000	EA
227 0100	TEMPORARY SILT DIKE	1,000.000	LF
229 4318	DITCH LINER PROTECTION	500.000	LF
230 (A) 2806	SOLID SLAB SODDING	222,479.000	SY
230 (F) 2812	WATERING	11,124.000	MGAL
233 (A) 2817	VEGETATIVE MULCHING	30.000	AC
244 7015	(SP)FLY ASH	7,359.000	TON
326 (E) 4240	(SP)CEMENTITIOUS STABILIZED SUBGRADE	169,892.000	SY
403 (E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	592.000	TON
407 0250	TACK COAT	27,862.000	GAL
408 5774	PRIME COAT	29,194.000	GAL
411 (S2) 5930	(SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	40,323.000	TON
411 (S3) 5935	(SP)ASPH.CONC.,TYPE S3(PG 76-28 OK)	20,725.000	TON
411 (S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	33,893.000	TON
411 (S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	18,377.000	TON
411 (S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	5,482.000	TON
413 (A) 4861	RUMBLE STRIP-METHOD AC-CON	95,880.000	LF
414 (C) 0309	APPROACH SLABS	180.000	SY
417 4659	(PL)FOG SEAL	560.000	GAL
417 5267	COLD MILLING PAVEMENT	17,437.000	SY
501 (A) 0313	STRUCTURAL EXCAVATION UNCLASSIFIED	58.000	CY
504 (E) 6245	CONCRETE RAIL (TR4)	80.000	LF
509 (B) 0321	CLASS A CONCRETE	122.000	CY
509 (C) 0322	CLASS A CONCRETE FOR SMALL STRUCTURES	71.000	CY
509 (D) 0325	CLASS C CONCRETE	194.000	CY
511 (A) 0332	REINFORCING STEEL	25,711.000	LB
515 (A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	38.000	SY
601 (A-1) 1353	TYPE I-A PLAIN RIPRAP	20.000	TON
611 (E) 6002	INLET (SMD-TYPE 2)	6.000	EA

CALL ORDER : 450
 LETTING DATE : January 19, 2006
 LETTING TIME : 10:30 A.M.
 COUNTIES : WOODWARD

CONTRACT ID : 050646
 PCN : 1745710
 PROJECTS : NHY-017N (053)
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 79.11
 CALENDAR DAYS : 255
 RES. ENG.: DISTRICT 6 (BUFFALO)
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	ROADWAY		
613(B) 0491	18" R.C.PIPE CLASS III	373.000	LF
613(B) 0492	24" R.C.PIPE CLASS III	134.000	LF
613(B) 0494	36" R.C.PIPE CLASS III	104.000	LF
613(B) 4495	22" X 13" R.C.PIPE ARCH CLASS A-III	40.000	LF
613(CC) 7186	TYPE A4 CULVERT END TREATMENT	3.000	EA
613(CC) 7189	TYPE D4 CULVERT END TREATMENT	2.000	EA
613(P) 1091	6" PERFORATED PIPE UNDERDRAIN ROUND	300.000	LF
613(Q) 1096	6" NON-PERF.PIPE UNDERDRAIN RND.	300.000	LF
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	17,854.000	SY
619(C) 0924	SAWING PAVEMENT	21,165.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	150.000	LF
623(E) 7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	4.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	4.000	EA
SECTION NO. 0002	TRAFFIC		
850(A) 8110	SHEET ALUMINUM SIGNS	745.400	SF
851(C) 8324	2" SQUARE TUBE POST	153.000	LF
851(C) 8327	2 1/4" SQUARE TUBE POST	1,251.000	LF
855(A) 8812	TRAFFIC STRIPE (PLASTIC) (4" WIDE)	138,360.000	LF
855(B) 8818	TRAFFIC STRIPE (PLASTIC) (ARROWS)	54.000	EA
856(A) 8839	CONSTRUCTION TRAFF.STR. (PAINT) (4" WIDE)	190,080.000	LF
856(G) 8890	(PL)CONST.ZONE PAV.MKRS (FLEX TAB) TYP.2-2	31,680.000	EA
880(C) 8850	PERMANENT BARRICADE UNIT	1.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890(A) 8722	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
890A/B 8756	(PL)REMOVE & RESET EXISTING SIGNS	1.000	EA
SECTION NO. 0003	STAKING		
642 0098	STAKING	1.000	LSUM
SECTION NO. 0004	CONSTRUCTION		
641 1552	MOBILIZATION	1.000	LSUM
643 0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM