



64'-8" Beam Length



**PLAN**




**ELEVATION**

**PRESSRESSED CONCRETE BEAM NOTES**


**COMPRESSIVE STRENGTH**  
The required compressive strength of the concrete is 6,000 P.S.I. at transfer of prestress and 8,000 P.S.I. at 28 days.

**STRAND TYPE**  
The required strand type is low-relaxation. Use strand having a nominal diameter of 0.6 with ultimate tensile strength of 270 K.S.I.

**LFD OPERATING RATING** - HS 36.1  
The Operating Rating shown is based on a nominal strength using only strands that are bonded for the full length of the beam. All partially bonded strands are neglected in strength computations.



**ELEVATION**




**TOP VIEW**

**END VIEW**

**ENCASED BEAM PLATE DETAILS**


**NOTE:**  
Encased Beam Plate located at expansion end only.




**DEAD LOAD DEFLECTION DIAGRAM**

**NOTE:**  
The Dead Load Deflection shown above at the tenth points are the initial deflections due to Deck Slab + Diaphragms + 5 P.S.F. Deck Form Allowance + Concrete Traffic Rail. It does not include the Beam weight or Future Wearing Surface.


Information shown on this sheet is applicable only to the standard bridge cross-section with 40' Clear Roadway, 8" Deck Slab and 4 Beams at 11'-4" spacing. Stay-in-Place Deck Forms are permitted if the conditions listed in the STAY-IN-PLACE FORM NOTES on LONGITUDINAL SECTION sheet are satisfied. Any modification will require a custom design with an appropriate Dead Load Deflection Diagram.



**END VIEW**  
(Type III P.C.B.)



**END SECTION**



**SECTION**

DEBOND SCHEDULE	
DEBOND PAIR	DEBOND LENGTH FROM END OF BEAM
B1	6'-0"

**BEAM SECTIONS**  
(24 - 0.6"Ø STRANDS)

APPROVED BY BRIDGE ENGINEER *Chad Head* DATE *8/16/03*

OKLAHOMA DEPT. OF TRANSPORTATION  
BRIDGE STANDARD (ENGLISH)  
TYPE III P.C. BEAM DETAILS  
65' SPAN  
CONVENTIONAL

1999 SPECIFICATIONS B40-C-PCB-III-65 OOE B-293E