

Spec Number	Special Provision	Use
<input type="checkbox"/> 102-004	A + B Bidding	At the discretion of the designer and/or field.
<input type="checkbox"/> 102-013	Bidding Procedures	On all projects.
<input type="checkbox"/> 103-001	Bonding Requirements	On all right-of-way clearance projects.
<input type="checkbox"/> 103-003	Subcontracts	On all federal funded projects.
<input type="checkbox"/> 103-004	Subcontracts for State Funded Construction Contracts	On all state funded projects.
<input type="checkbox"/> 104-002	Railroad Flagging	When the project has RR R-O-W, and flagging is paid under other items of work.
<input type="checkbox"/> 104-004	Utility Property and Services	When the project has Utilities that will not be cleared by the time work begins
<input type="checkbox"/> 104-006	Railroad Flagging (100% Reimbursement)	When the project has RR flagging is paid separately.
<input type="checkbox"/> 106-005	Buy America (Federal)	On all federal funded projects.
<input type="checkbox"/> 106-006	Buy America (State)	On all state funded projects.
<input type="checkbox"/> 107-008	Legal Relations and Responsibility to Public (Railroad Insurance)	Anytime RR R-O-W is involved (Rail Division should be consulted).
<input type="checkbox"/> 107-012	Federal Aviation Regulations	When construction is within 4 miles of an airport.
<input type="checkbox"/> 108-001	Progress and Prosecution for Right-of-Way Clearance Contracts	On all right-of-way clearance projects
<input type="checkbox"/> 108-005	Prosecution Progress (90 Days)	When contract time may be suspended for the fabrication of traffic items.
<input type="checkbox"/> 108-006	Prosecution Progress (120 Days)	When contract time may be suspended for the fabrication of traffic items.
<input type="checkbox"/> 108-023	Flexible Notice to Proceed	At the discretion of the designer and/or field. Used to delay the work order.
<input type="checkbox"/> 108-027	Delayed Notice to Proceed	To prevent construction from beginning before a specified date.
<input type="checkbox"/> 108-080	Liquidated Damages	On all projects.
<input type="checkbox"/> 108-081	Disincentive for Exposed Cold-Milled Pavement	When cold-milling asphalt driving surfaces.

Special Provisions marked "Sample" or "Project Specific" must receive approval from Office Engineer Division

Spec Number	Special Provision	Use
<input type="checkbox"/> 108-182	Subletting of Contract (70%)	When the Prime Contractor is unable to perform 50% or more of the contract work due to the nature of the construction activities.
<input type="checkbox"/> 108-ID	Incentive/Disincentive	
<input type="checkbox"/> 108-LR	Lane Rental	
<input type="checkbox"/> 108-MI	Internal Milestone	
<input type="checkbox"/> 108-PP	Prosecution and Progress	
<input type="checkbox"/> 109-003	Price Adjustment for Fuel	On projects with a duration around 180 calendar days, and moving at least 50,000 CY of combined excavation, borrow, and/or embankment.
<input type="checkbox"/> 109-014	Material on Hand	On all projects.
<input type="checkbox"/> 109-015	Prompt Payment for Subcontractors	On all projects.
<input type="checkbox"/> 110-1	General Provisions for Use of Electronic Data	When the Department is providing electronic design data to the Contractor for the purposes of bidding and/or construction using Automated Machine Guidance (AMG) technology.
<input type="checkbox"/> 202-002	Osage Nation Mineral Reservation Sandy Soil Mining Permit	When excavating borrow material within, or transporting borrow material out of Osage county.
<input type="checkbox"/> 233-002	Hydromulch	When specified to furnish and install hydromulch to help establish vegetation (Project Specific)
<input type="checkbox"/> 303-004	Cold In-Place Recycle	When Cold In-Place Recycling involves foaming. Not applicable when CSS-Special Liquified Emulsion is called for.
<input type="checkbox"/> 325-001	Moisture Barrier Membrane	On all projects using Moisture Barrier Membrane.
<input type="checkbox"/> 326-002	Woven Geosynthetic Reinforcement Fabric for Pavement	When woven geosynthetic reinforcement fabric for pavement is required.
<input type="checkbox"/> 407-002	Bonded Hot Mix Asphalt	When paying for Polymer Modified Cationic Rapid Set-1s (PMCRS-1s) instead of tackcoat.
<input type="checkbox"/> 410-001	Milled Hot Recycling of Bituminous Material (Partial Depth) 2"+ Surface Recycling	When paying for Hot-In Place Recycled Asphalt
<input type="checkbox"/> 411-015	Rich Intermediate Layer (RIL)	As directed by the Pavement Design Engineer, and/or as specified by the typical section depicted in the plans.
<input type="checkbox"/> 411-018	Intelligent Compaction of Asphalt	As requested by the Field Division on asphalt paving projects.

Special Provisions marked "Sample" or "Project Specific" must receive approval from Office Engineer Division

Spec Number	Special Provision	Use
<input type="checkbox"/> 411-025	Hot Mix Asphalt/Warm Mix Asphalt	On all Projects utilizing any Superpave pay item.
<input type="checkbox"/> 414-017	Longitudinal Finish	To specify transverse tining on PC paving.
<input type="checkbox"/> 414-018	Optimized Gradation for Portland Cement Concrete Pavement	On all PC paving projects. Use with Special Provision 701-14.
<input type="checkbox"/> 415-001	Bituminous (Fiber Fill) Crack Sealing	When specifying a bituminous sealant which contains fibers.
<input type="checkbox"/> 430-2QA	Pavement and Bridge Deck Smoothness	When establishing pay adjustment factors for quality of pavement or bridge deck smoothness (Zero Blanking Band).
<input type="checkbox"/> 435-003	Fiber Reinforced, Bonded Portland Cement Concrete Overlay	When placing a fiber reinforced, bonded PCC pavement overlay on an existing PCC pavement.
<input type="checkbox"/> 441-001	Electronic Ticketing for Bituminous Materials	On all projects utilizing Superpave.
<input type="checkbox"/> 502-002	Temporary Detour Bridge	When the project requires the construction of a temporary crossing/bridge.
<input type="checkbox"/> 504-006	Rail, Parapets, and Curbs	When the Contractor is allowed to place rail, parapets, and/or curbs using slip form methods.
<input type="checkbox"/> 504-007	Bridge Deck Finish on County Bridges	On all county bridge deck projects.
<input type="checkbox"/> 513-001	Anodes	When using anodes as part of the deck repair.
<input type="checkbox"/> 516-001	Pulse-Echo Testing of Drilled Shafts	When low strain impact integrity testing is desired.
<input type="checkbox"/> 524-003	Fiber Reinforced Polymer Material	When structural strengthening using fiber reinforced polymer composite wrap is desired.
<input type="checkbox"/> 525-001	Migratory Bird Nest Prevention for Bridge Structures and Culverts	When Plans specify that migratory Birds have been observed or assessment has not been performed on the structures
<input type="checkbox"/> 619-004	Plugging and Abandonment of Oil Wells	To specify the location and condition of each well.
<input type="checkbox"/> 631-001	Bollards	When Bollards are required on a project.
<input type="checkbox"/> 656-005	Artificial Lighting for American Burying Beetle (ABB) Compliance	On all projects with ABB in the plan notes.
<input type="checkbox"/> 701-014	Optimized Gradation for Portland Cement Concrete Pavement	On all PC paving projects. Use with Special Provision 414-18.projects.
<input type="checkbox"/> 708-021	Reclaimed Asphalt Pavement and Shingles	Upon Department approval of the use of recycled asphalt pavement and/or shingles on the project.

Special Provisions marked "Sample" or "Project Specific" must receive approval from Office Engineer Division

Spec Number	Special Provision	Use
<input type="checkbox"/> 708-024	Performance-Graded Asphalt Binder Using Multiple Stress Creep Recovery (MSCR) Test	When Rich Intermediate Layer is specified for the project; with Special Provision 411-15.
<input type="checkbox"/> 712-001	Woven Geosynthetic Reinforcement Fabric for Pavement	When woven geosynthetic reinforcement fabric for pavement is required.
<input type="checkbox"/> 809-001	Bridge Navigation Lighting	When paying for Bridge Navigation Lighting.
<input type="checkbox"/> 823-001	Temporary Traffic Signals	When using portable traffic signals as part of the traffic control plan.
<input type="checkbox"/> 880-010	Traffic Surveillance	On projects requiring OHP traffic surveillance during construction.
<input type="checkbox"/> 882-002	Portable Automated Real-Time Work Zone Information System (Smart Work Zone)	On projects utilizing Smart Work Zone.

Special Provisions marked "Sample" or "Project Specific" must receive approval from Office Engineer Division