

DATE : July 03, 2001 OKLAHOMA DEPARTMENT OF TRANSPORTATION
NOTICE TO CONTRACTORS -- July 26, 2001

LNTCNCA
LETTING

LNTCNCA-D

NOTICE TO CONTRACTORS: SEALED PROPOSALS SENT BY REGISTERED MAIL WILL BE RECEIVED THROUGH THE ODOT REPRODUCTION BRANCH UNTIL 30 MINUTES PRIOR TO THE SCHEDULED BID OPENING OR WILL BE RECEIVED AT THE OKLAHOMA DEPARTMENT OF TRANSPORTATION COMMISSION ROOM IN THE THE OKLAHOMA DEPARTMENT OF TRANSPORTATION BUILDING, 200 NORTHEAST 21ST STREET, OKLAHOMA CITY, OKLAHOMA 73105 FROM 30 MINUTES PRIOR TO THE SCHEDULED BID OPENING OF July 26, 2001 , TO BE PUBLICALLY OPENED AT 10:30 A.M. FOR THE WORK LISTED BELOW.

NO PROPOSAL FOR CONSTRUCTION OR MAINTENANCE WORK OF THE DEPARTMENT WILL BE ISSUED TO ANY CONTRACTOR AFTER 10:30 A.M. ON THE WORKING DAY PRECEDING OPENING OF BIDS FOR ANY CONTRACT.

EACH SEPARATE PROPOSAL SHALL BE ACCOMPANIED BY A CERTIFIED OR CASHIER'S CHECK OR BID BOND EQUAL TO 5% OF THE BID MADE PAYABLE TO THE STATE OF OKLAHOMA, DEPARTMENT OF TRANSPORTATION, AS A PROPOSAL GUARANTY. PROPOSAL CHECKS WILL BE HELD OR RETURNED BY THE DEPARTMENT AS PER SECTION 103.04 OF THE STATE STANDARD SPECIFICATIONS.

THIS WORK WILL BE DONE UNDER THE OKLAHOMA DEPARTMENT OF TRANSPORTATION COMMISSION'S APPLICABLE SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.

THE MINIMUM WAGE TO BE PAID LABORERS AND MECHANICS EMPLOYED ON THIS PROJECT WILL BE INCLUDED IN THE PROPOSAL.

PROPOSALS MUST BE PREPARED AS DIRECTED BY THE STATE STANDARD SPECIFICATIONS.

PLANS, FORMS OF PROPOSALS, CONTRACTS AND SPECIFICATIONS MAY BE EXAMINED AT THE DIVISION HEADQUARTERS IN THE DIVISION THE WORK IS TO BE PERFORMED OR AT THE OKLAHOMA DEPARTMENT OF TRANSPORTATION OFFICE ENGINEER'S DIVISION IN OKLAHOMA CITY, OKLAHOMA.

PLANS AND PROPOSAL FORMS MAY BE ORDERED FROM JACK STEWART, DIVISION ENGINEER, OKLAHOMA DEPARTMENT OF TRANSPORTATION BUILDING, 200 NORTHEAST 21ST STREET, OKLAHOMA CITY, OKLAHOMA 73105. COST OF BIDDING DOCUMENTS ARE \$25.00 + tax FOR EACH BIDDING PROPOSAL. STATE STANDARD SPECIFICATION 1988 EDITION (RED BOOK) AND 1991 SUPPLEMENT MAY BE PURCHASED FOR \$8.00 +tax, OR 1996 METRIC STD SPEC \$27.00 + TAX, OR 1999 METRIC AND ENGLISH TD SPEC \$55.00 + TAX.

(OKLAHOMA TAX IS 7.875%). MAKE CHECKS PAYABLE TO OKLAHOMA DEPARTMENT OF TRANSPORTATION
NO REFUNDS WILL BE MADE ON THE ABOVE COST. THE COST OF BIDDING DOCUMENT WILL BE BORNE BY PROSPECTIVE BIDDER.

UPON AWARD OF CONTRACT TO A SUCCESSFUL BIDDER, THE CONTRACT WILL BE COMPLETELY AND CORRECTLY EXECUTED BY THE CONTRACTOR AND RETURNED TO THE DEPARTMENT WITHIN TEN (10) WORKING DAYS FROM THE DATE OF AWARD. THE DEPARTMENT WILL HAVE FOURTEEN (14) WORKING DAYS FROM THE DATE OF AWARD TO COMPLETE ITS EXECUTION OF THE CONTRACT.

THE OKLAHOMA DEPARTMENT OF TRANSPORTATION HEREBY NOTIFIES ALL BIDDERS THAT IT WILL AFFIRMATIVELY INSURE THAT IN ANY CONTRACT ENTERED INTO PURSUANT TO THIS ADVERTISEMENT, DISADVANTAGED BUSINESS ENTERPRISES WILL BE AFFORDED FULL OPPORTUNITY TO SUBMIT BIDS IN RESPONSE TO THIS INVITATION AND WILL NOT BE DISCRIMINATED AGAINST ON THE GROUNDS OF RACE, COLOR, SEX, RELIGION, NATIONAL ORIGIN, OR DISABILITY IN CONSIDERATION FOR AN AWARD.

BIDDERS ARE HEREBY NOTIFIED THAT ALL BIDS ARE LIKELY TO BE REJECTED IF THE LOWEST RESPONSIVE BID RECEIVED EXCEEDS THE ENGINEER'S ESTIMATE BY MORE THAN SEVEN (7) PERCENT. IN THE EVENT ALL BIDS ARE REJECTED FOR THIS REASON, THIS PROJECT MAY BE DEFERRED FOR READVERTISING FOR BIDS UNTIL A MORE COMPETITIVE SITUATION EXISTS.

DESCRIPTION OF WORK AND LOCATION OF PROJECT:

LNTCIQA
CALL ORDER : 030
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: BLAINE

STATE PROJECT
CONTRACT ID : 010297
PCN : 1915704

PAGE 1

PROJECTS : CIP-106B(37)IP
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
RESURFACE(ASPHALT)
BEGIN AT THE JCT. OF SH-51A/SH-8 IN WATONGA AND EXTEND WEST
AND NORTH ON SH-51A
PROJ. LGTH.= 5.08 MILES
FLEX. ESALS= 0.5 MILLION
ASPH. GRADE= 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
411(B) 5280	(SP)ASPH.CONC.TYPE B(PATCH)(PG 64-22 OK)	1,000.000	TON
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	6,445.000	TON
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

LNTCIQA
CALL ORDER : 040
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: BRYAN
MCCURTAIN

FEDERAL PROJECT
CONTRACT ID : 010271
PCN : 1793504M
PROJECTS : BHFY-NBIP(157)/BRFY-NBIP(154)
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 2.70
RES. ENG.:
CAL. DAYS: 90 LIQ. DAM: \$ 500

PAGE 2

CONTRACT DESCRIPTION:
BRIDGE PAINTING
OVER SULPHUR CREEK, 4.2 MILES EAST OF BOKCHITO ON US-70 AND
OVER LITTLE RIVER OVERFLOW, 6.3 MILES SOUTH OF BROKEN BOW ON
US-70
PROJ. LGTH.= 0.00 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	X031-BRIDGE 'A' BHFY-NBIP(154)		
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
641 1399	MOBILIZATION	1.000	LSUM
876(C) 8482	(PL)TRUCK MOUNTED ATTENUATOR	20.000	SD
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	X031-BRIDGE 'B' BHFY-NBIP(154)		
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
SECTION NO. 0003	X031-BRIDGE 'C' BHFY-NBIP(157)		
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

LNTCIQA
CALL ORDER : 050
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: BRYAN
MCCURTAIN

FEDERAL PROJECT
CONTRACT ID : 010272
PCN : 1793505M
PROJECTS : BHFY-22N(44)/BRFY-22N(43)
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 2.70
RES. ENG.:
CAL. DAYS: 90 LIQ. DAM: \$ 500

PAGE 3

CONTRACT DESCRIPTION:
JOINT SEAL
OVER SULPHUR CREEK, 4.2 MILES EAST OF BOKCHITO ON US-70 AND
OVER LITTLE RIVER OVERFLOW, 6.3 MILES SOUTH OF BROKEN BOW
PROJ. LGTH.= 0.00 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	X031-BRIDGE 'A' BRFY-22N(43)		
504(H) 6390	RAPID CURE JOINT SEALANT	252.000	LF
504(I) 6389	ELASTOMERIC MORTAR	44.900	CF
641 1399	MOBILIZATION	1.000	LSUM
876(C) 8482	(PL)TRUCK MOUNTED ATTENUATOR	60.000	SD
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	X031-BIRDGE 'B' BRFY-22N(43)		
504(H) 6390	RAPID CURE JOINT SEALANT	364.000	LF
504(I) 6389	ELASTOMERIC MORTAR	37.600	CF
SECTION NO. 0003	X031-BRIDGE 'C' BHFY-22N(44)		
504(H) 6390	RAPID CURE JOINT SEALANT	124.000	LF
505(B) 6019	CLASS B BRIDGE DECK REPAIR	10.000	SY
505(C) 6020	CLASS C BRIDGE DECK REPAIR	10.000	SY
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

LNTCIQA
 CALL ORDER : 055
 LETTING DATE : July 26, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES: CANADIAN

FEDERAL PROJECT
 CONTRACT ID : 010299
 PCN : 1928904
 PROJECTS : STPY-109B(56)TR
 DBE/WBE GOALS: 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE: \$ 1.62
 RES. ENG.:
 CAL. DAYS:

PAGE 4

LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
 SIGNING
 AT CANADIAN VALLEY TECHNOLOGY CENTER(EVANS ROAD/SH-66)
 IN ELRENO
 PROJ. LGTH.= 0.00 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	Y002-SIGNING		
641 1552	MOBILIZATION	1.000	LSUM
802(B) 8332	1" PVC SCH.40 PLASTIC CONDUIT BORED	50.000	LF
802(B) 8334	1" PVC SCH.40 PLASTIC CONDUIT TRENCHED	675.000	LF
803 8065	PULL BOX(SIZE I)	5.000	EA
804(A) 2915	STRUCTURAL CONCRETE	0.800	CY
804(B) 2916	REINFORCING STEEL	54.000	LB
810(A) 3118	SERVICE POLE	2.000	EA
811 8044	1/C NO.10 ELECT.COND.	2,275.000	LF
827 8623	SOLID STATE FLASHER CONTROLLER(TYPE II)	2.000	EA
831 8301	1WAY1SEC.ADJ.SIG.HD.S-22	4.000	EA
850(A) 8110	SHEET ALUMINUM SIGNS	29.400	SF
851(B) 3220	4"@10.79 GALV.STL.PIPE POST	30.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

LNTCIQA
CALL ORDER : 060
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: CHOCTAW

STATE PROJECT
CONTRACT ID : 010292
PCN : 1849404

PAGE 5

PROJECTS : SAP-112D(32)
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: 45 LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
RESURFACE(ASPHALT)
LAKE ACCESS FOR HUGO LAKE: BEGIN APPROX. 1.0 MILE NORTH
OF US-70 ON NS-428.5, EXTEND NORTH.
PROJ. LGTH.= 3.02 MILE
FLEX ESALS = 0.6 MILLION
ASPH GRADE = 64-22 PG OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
303 0192	AGGREGATE BASE	395.000	CY
408 5774	PRIME COAT	2,949.000	GAL
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	3,104.000	TON
420(A) 4242	FABRIC REINFORCEMENT	31,173.000	SY
420(B) 4268	BITUMINOUS BINDER	5,830.000	GAL
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	2,027.000	SY
641 1552	MOBILIZATION	1.000	LSUM
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

LNTCIQA
 CALL ORDER : 070
 LETTING DATE : July 26, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES: CREEK

FEDERAL PROJECT
 CONTRACT ID : 010273
 PCN : 0926104M

PAGE 6

PROJECTS : MGSY-19B(265)/MGEY-119B(30)/BR
 DBE/WBE GOALS: 11.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE: \$ 108.95
 RES. ENG.:
 CAL. DAYS: 360 LIQ. DAM: \$ 1500

CONTRACT DESCRIPTION:
 GRADE, DRAIN, SURFACE AND BRIDGE(SUPERPAVE)
 BEGIN APPROX. 12 MILES WEST OF THE JCT OF I-44/SH-33 AND
 EXTEND
 EAST
 PROJ. LGTH.= 9.435 MILES
 FLEX. ESALS=13.9 MILLION
 ASPH. GRADE= 64-22 OK, 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY - MGSY-19B(265)		
201 M0102	CLEARING AND GRUBBING	1.000	LSUM
202(A) M0183	UNCLASSIFIED EXCAVATION	235,583.000	M3
202(C) M1302	UNCLASSIFIED BORROW	30,000.000	M3
205 M4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
210 M0121	OBLITERATING ABANDONED ROAD	3.191	STA
222 M2801	TEMPORARY BALE BARRIER	1,064.000	M
223 M2802	TEMPORARY SILT FENCE	4,080.000	M
224 M2803	TEMPORARY SEDIMENT FILTER	10.000	EA
226 M2805	TEMPORARY SEDIMENT REMOVAL	56.000	M3
229 M4318	DITCH LINER PROTECTION	387.000	M
230(A) M2806	SOLID SLAB SODDING	114,550.000	M2
230(D) M2810	BROADCAST SPRIGGING (METHOD A)	382,000.000	M2
230(F) M2812	WATERING	117,952.000	KL
232(A) M2813	SEEDING METHOD A	38.200	HA
233(A) M2817	VEGETATIVE MULCHING	38.200	HA
234(A) M2824	FERTILIZING (10-20-10)	19.760	T
234(A) M4406	FERTILIZING (0-46-0)	8.840	T
235(B) M0101	(PL)ROCK FILTER DAM, TYPE 2	28.000	M3
235(C) M0102	(PL)ROCK FILTER DAM, TYPE 3	554.000	M3
241 M2832	MOWING	52.000	HA
303 M0192	AGGREGATE BASE	10,997.000	M3
317(A) M4252	(SP)FLY ASH	5,818.000	T
317(B) M4254	SUBGRADE MODIFICATION	99,703.000	M2
317(C) M4253	LIME	497.000	T
317(D) M4254	SCARIFY, MIX BLADE OF SUBGRADE W/LIME TRT	25,845.000	M2
403(E) M0225	TRAFFIC BOUND SURFACE COURSE TYPE E	3,650.000	T
407 M0250	TACK COAT	95,582.000	L
408 M5774	PRIME COAT	143,552.000	L
420(A) M4242	FABRIC REINFORCEMENT	5,741.000	M2
501(A) M0313	STRUCTURAL EXCAVATION UNCLASSIFIED	127.000	M3
509(B) M0321	CLASS A CONCRETE	300.000	M3
509(D) M0325	CLASS C CONCRETE	809.000	M3
511(A) M1332	REINFORCING STEEL	52,999.000	KG

SECTION NO. 0001 I000-ROADWAY - MGSY-19B(265)

601A-1	M0536	TYPE I-A PLAIN RIPRAP	1,197.000	T
601B-2	M0544	TYPE II-A FILTER BLANKET	211.000	T
602(C)	M4155	FILTER FABRIC	500.000	M2
610(A)	M0605	150MM CONCRETE SIDEWALK	150.000	M2
611(E)	M5387	INLET CDI RCB DES. 1	10.000	EA
611(E)	M5388	INLET CDI RCB DES. 2	3.000	EA
611(E)	M5389	INLET CDI RCB DES. 3	3.000	EA
611(F)	M5536	INLET CDI RCB DES. 1,(ADD'L DEPTH)	7.760	M
611(F)	M5537	INLET CDI RCB DES. 2,(ADD'L DEPTH)	8.200	M
611(F)	M5538	INLET CDI RCB DES. 3,(ADD'L DEPTH)	3.860	M
613(B)	M0405	450MM R.C.PIPES CLASS III	792.500	M
613(B)	M0409	600MM R.C.PIPES CLASS III	270.940	M
613(B)	M0413	750MM R.C.PIPES CLASS III	211.710	M
613(B)	M0415	900MM R.C.PIPES CLASS III	43.800	M
613(B)	M0419	1200MM R.C.PIPES CLASS III	35.220	M
613(B)	M0421	1350MM R.C.PIPES CLASS III	44.230	M
613(CC)	M7196	TYPE A6 CULVERT END TREATMENT	70.000	EA
613(CC)	M7197	TYPE B6 CULVERT END TREATMENT	15.000	EA
613(CC)	M7198	TYPE C6 CULVERT END TREATMENT	10.000	EA
613(CC)	M7204	TYPE DD6 CULVERT END TREATMENT	2.000	EA
613(M)	M0897	450MM PREFAB. CULVERT END SEC., ROUND	4.000	EA
613(M)	M0898	600MM PREFAB. CULVERT END SEC., ROUND	3.000	EA
613(M)	M0899	750MM PREFAB. CULVERT END SEC., ROUND	4.000	EA
613(M)	M0981	1200MM PREFAB. CULVERT END SEC., ROUND	2.000	EA
613(M)	M0982	1350MM PREFAB. CULVERT END SEC., ROUND	2.000	EA
613(P)	M1091	150MM PERFORATED PIPE UNDERDRAIN ROUND	150.000	M
619(C)	M0924	SAWING PAVEMENT	10,836.000	M
624(A)	M4281	FENCE-STYLE WWF	99.000	M
624(C)	M4459	FENCE-STYLE SWF (5 BARBED WIRE)	9,272.000	M
624(D)	M4288	FENCE-STYLE CLF (1200MM HIGH, CLASS A)	171.000	M
629(A)	M4958	MAILBOX INSTALLATION-SINGLE	24.000	EA
629(B)	M4959	MAILBOX INSTALLATION-MULTIPLE	35.000	EA
629(C)	M4960	MAILBOX	59.000	EA
629(D)	M4961	REMOVAL OF MAILBOX INSTALLATION	59.000	EA
640	M1398	FIELD OFFICE	1.000	EA
641	M1399	MOBILIZATION	1.000	LSUM
643	M0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM

SECTION NO. 0002 I000-ROADWAY - MGEY-119B(30)

201	M0102	CLEARING AND GRUBBING	1.000	LSUM
202(A)	M0183	UNCLASSIFIED EXCAVATION	151,703.000	M3
202(C)	M0184	UNCLASSIFIED BORROW	108,755.000	M3
205	M4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	M2801	TEMPORARY BALE BARRIER	130.000	M
223	M2802	TEMPORARY SILT FENCE	4,058.000	M
225	M2804	TEMPORARY SEDIMENT BASIN	3.000	EA
226	M2805	TEMPORARY SEDIMENT REMOVAL	600.000	M3
229	M4318	DITCH LINER PROTECTION	1,017.000	M
230(A)	M2806	SOLID SLAB SODDING	2,930.000	M2
230(B)	M2807	MULCH SODDING	62,729.000	M2
230(F)	M2812	WATERING	11,819.000	KL
232(A)	M2813	SEEDING METHOD A	15.000	HA
232(B)	M2814	SEEDING METHOD B	15.000	HA
233(A)	M2817	VEGETATIVE MULCHING	6.080	HA

SECTION NO. 0002

I000-ROADWAY - MGEY-119B(30)

234(A)	M2824	FERTILIZING (10-20-10)	6.240	T
234(A)	M4406	FERTILIZING (0-46-0)	1.120	T
235(B)	M0101	(PL)ROCK FILTER DAM, TYPE 2	30.000	M3
241	M2832	MOWING	12.160	HA
303	M5912	AGGREGATE BASE	1,395.000	T
317(A)	M4252	(SP)FLY ASH	2,321.000	T
317(B)	M4254	SUBGRADE MODIFICATION	40,298.000	M2
317(C)	M4253	LIME	242.000	T
317(D)	M4254	SCARIFY, MIX BLADE OF SUBGRADE W/LIME TRT	40,298.000	M2
403(E)	M0225	TRAFFIC BOUND SURFACE COURSE TYPE E	278.000	T
407	M0250	TACK COAT	19,735.000	L
408	M5774	PRIME COAT	45,585.000	L
411(S2)	M5930	(SP)ASPH.CONC., TYPE S2(PG 64-22 OK)	2,222.000	T
411(S3)	M5940	(SP)ASPH.CONC., TYPE S3(PG 70-28 OK)	924.000	T
411(S3)	M5945	(SP)ASPH.CONC., TYPE S3(PG 64-22 OK)	743.000	T
411(S4)	M5955	(SP)ASPH.CONC., TYPE S4(PG 70-28 OK)	616.000	T
411(S4)	M5960	(SP)ASPH.CONC., TYPE S4(PG 64-22 OK)	3,656.000	T
414(A1)	M5755	250MM P.C. DOWEL JOINTED CONCRETE PAV	25,589.000	M2
501(A)	M0313	STRUCTURAL EXCAVATION UNCLASSIFIED	360.000	M3
509(B)	M0321	CLASS A CONCRETE	484.000	M3
509(D)	M0325	CLASS C CONCRETE	320.000	M3
511(A)	M1332	REINFORCING STEEL	62,570.000	KG
613(B)	M0405	450MM R.C.PIPE CLASS III	131.000	M
613(CC)	M7186	TYPE A4 CULVERT END TREATMENT	12.000	EA
613(CC)	M7191	TYPE AA4 CULVERT END TREATMENT	6.000	EA
613(CC)	M7196	TYPE A6 CULVERT END TREATMENT	2.000	EA
619(B)	M0291	REMOVAL OF HEADWALL	12.000	EA
619(B)	M4727	REMOVAL OF CONCRETE PAVEMENT	2,139.000	M2
619(B)	M4728	REMOVAL OF ASPHALT PAVEMENT	14,554.000	M2
619(C)	M0924	SAWING PAVEMENT	222.000	M
624(A)	M4281	FENCE-STYLE WWF	102.000	M
624(B)	M4462	GATES-STYLE WWF(1350MM HI X 3600MM LONG)		7.000 EA
624(C)	M4459	FENCE-STYLE SWF (5 BARBED WIRE)	1,538.000	M
629(A)	M4958	MAILBOX INSTALLATION-SINGLE	5.000	EA
629(B)	M4959	MAILBOX INSTALLATION-MULTIPLE	1.000	EA
629(C)	M4960	MAILBOX	7.000	EA
629(D)	M4961	REMOVAL OF MAILBOX INSTALLATION	6.000	EA
640	M1398	FIELD OFFICE	1.000	EA
641	M1399	MOBILIZATION	1.000	LSUM
643	M0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM

SECTION NO. 0003

I000-ROADWAY - BRFY-119B(31)

201	M0102	CLEARING AND GRUBBING	1.000	LSUM
202(A)	M0183	UNCLASSIFIED EXCAVATION	23,916.000	M3
202(C)	M0184	UNCLASSIFIED BORROW	8,247.000	M3
205	M4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
210	M0121	OBLITERATING ABANDONED ROAD	0.250	STA
230(A)	M2806	SOLID SLAB SODDING	6,000.000	M2
230(D)	M2810	BROADCAST SPRIGGING (METHOD A)	3,000.000	M2
230(F)	M2812	WATERING	4,000.000	KL
232(B)	M2814	SEEDING METHOD B	0.500	HA
234(A)	M2824	FERTILIZING (10-20-10)	2.000	T
234(A)	M4406	FERTILIZING (0-46-0)	1.000	T
241	M2832	MOWING	3.500	HA

SECTION NO. 0003

I000-ROADWAY - BRFY-119B(31)

303	M0192	AGGREGATE BASE	753.060	M3
317(A)	M4252	(SP)FLY ASH	336.150	T
317(B)	M4254	SUBGRADE MODIFICATION	5,761.000	M2
317(C)	M4253	LIME	27.680	T
317(D)	M4254	SCARIFY,MIX BLADE OF SUBGRADE W/LIME TRT	1,440.250	M2
403(E)	M0225	TRAFFIC BOUND SURFACE COURSE TYPE E	202.980	T
407	M0250	TACK COAT	5,115.720	L
408	M5774	PRIME COAT	11,493.630	L
411(S2)	M5930	(SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	2,593.200	T
411(S3)	M5940	(SP)ASPH.CONC.,TYPE S3(PG 70-28 OK)	617.000	T
411(S3)	M5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	365.360	T
411(S4)	M5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	404.680	T
411(S4)	M5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	665.070	T
509(D)	M0325	CLASS C CONCRETE	9.000	M3
609(D)	M0398	BITUMINOUS CURBING	406.000	M
613(B)	M0405	450MM R.C.PIPE CLASS III	27.030	M
613(B)	M0409	600MM R.C.PIPE CLASS III	24.850	M
613(D)	M4819	2400MM CORR. GALV. STEEL PIPE	54.800	M
613(M)	M0897	450MM PREFAB. CULVERT END SEC., ROUND	4.000	EA
613(M)	M0898	600MM PREFAB. CULVERT END SEC., ROUND	2.000	EA
619(C)	M0924	SAWING PAVEMENT	1,081.000	M
623(A)	M0932	BEAM GUARD RAIL-W-BEAM-SINGLE	154.410	M
623(F)	M4447	GUARD RAIL ANCHOR UNIT (TYPE B)	2.000	EA
623(F)	M4449	GUARD RAIL ANCHOR UNIT (TYPE D)	4.000	EA
623(H)	M8571	(SP)G.E.T. GUARD RAIL END SECTION	2.000	EA
624(C)	M4459	FENCE-STYLE SWF (5 BARBED WIRE)	800.000	M
629(A)	M4958	MAILBOX INSTALLATION-SINGLE	3.000	EA
629(C)	M4960	MAILBOX	3.000	EA
629(D)	M4961	REMOVAL OF MAILBOX INSTALLATION	3.000	EA

SECTION NO. 0004

X020-BRIDGE - BRFY-119B(31)

202(A)	M0183	UNCLASSIFIED EXCAVATION	20,100.000	M3
501(B)	M1307	SUBSTRUCTURE EXCAVATION COMMON	198.000	M3
501(G)	M6309	CLSM BACKFILL	110.000	M3
503(A)	M1312	PRESTRESSED CONCRETE BEAMS (TYPE III)	179.000	M
504(A)	M1304	APPROACH SLAB	254.000	M2
504(C)	M6250	SEALED EXPANSION JOINT	15.000	M
504(E)	M6239	CONCRETE RAIL (TR3)	132.000	M
506(A)	M1322	STRUCTURAL STEEL	2,160.000	KG
509(A)	M1326	CLASS AA CONCRETE	135.000	M3
509(B)	M1328	CLASS A CONCRETE	156.000	M3
511(A)	M1332	REINFORCING STEEL	5,966.000	KG
511(B)	M6010	EPOXY COATED REINFORCING STEEL	37,802.000	KG
514(A)	M6011	PILES, FURNISHED (HP 250X62)	64.000	M
514(A)	M6013	PILES, FURNISHED (HP 310X79)	271.000	M
514(B)	M6292	PILES, DRIVEN (HP 250X62)	64.000	M
514(B)	M6294	PILES, DRIVEN (HP 310X79)	271.000	M
514(F)	M6354	PILE LOAD TEST (DYNAMIC)	14.000	EA
515(A)	M6013	WATER REPELLENT (VISUALLY INSPECTED)	575.000	M2
516(A)	M6093	DRILLED SHAFTS 1050MM DIAMETER	67.000	M
601A-1	M1353	TYPE I-A PLAIN RIPRAP	2,200.000	T
601A-2	M1355	TYPE I-A FILTER BLANKET	600.000	T
613(P)	M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	29.000	M
613(Q)	M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	36.500	M

SECTION NO. 0004 X020-BRIDGE - BRFY-119B(31)

613(R)	M1100	PIPE UNDERDRAIN COVER MAT'L.	11.000	M3
613(S)	M1180	TRENCH EXCAVATION	37.000	M3
613(T)	M1181	STANDARD BEDDING MATERIAL	14.000	M3
619(D)	1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
640	M1398	FIELD OFFICE	1.000	EA
643	M0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM

SECTION NO. 0005 Y002-TRAFFIC SIGNING & STRIPING - MGSY-19B(265)

627(J)	M4318	MOVABLE CONCRETE MEDIAN BARRIER	3,592.000	M
850(A)	M8110	SHEET ALUMINUM SIGNS	21.390	M2
851(C)	M8327	57MM SQUARE TUBE POST	128.340	M
855(A)	M8812	TRAFFIC STRIPE(PLASTIC)(100MM WIDE)	31,704.500	M
855(B)	M8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	22.000	EA
855(B)	M8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	11.000	EA
856(A)	M8839	CONSTR.TRAFF.STR.(PAINT)(100MM WIDE)	53,560.000	M
856(C)	M8851	REM.PAVEMENT MARKING TAPE(100MM WIDE)	4,800.000	M
859(A)	M8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	58,360.000	M
880(B)	M8818	CONSTRUCTION SIGNS 0 TO 0.59 M2	4,800.000	SD
880(B)	M8821	CONSTRUCTION SIGNS 0.60 M2 TO 1.47 M2	20,000.000	SD
880(B)	M8824	CONSTRUCTION SIGNS 1.48 M2 TO 3.06 M2	4,650.000	SD
880(C)	M8842	BARRICEDES(TYPE III)	22,300.000	SD
880(D)	M8854	VERTICAL PANELS	476,400.000	SD
880(E)	M8860	WARNING LIGHTS(TYPE A)	29,750.000	SD
880(E)	M8872	WARNING LIGHTS(TYPE C)	607,200.000	SD
880(F)	M8878	DRUMS	169,200.000	SD
880(I)	M8902	FLAGGER	150.000	SD
890(A)	M8722	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM

SECTION NO. 0006 Y008-TRAFFIC - MGEY-119B(30)

627(E)	M4314	PRECAST CONC. MEDIAN BARRIER, PORT. TYPE	1,247.000	M
627(G)	M4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	505.000	M
850(A)	M8110	SHEET ALUMINUM SIGNS	9.660	M2
851(C)	M8327	57MM SQUARE TUBE POST	76.550	M
855(A)	M8812	TRAFFIC STRIPE(PLASTIC)(100MM WIDE)	11,168.000	M
855(B)	M8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	9.000	EA
855(B)	M8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	3.000	EA
856(A)	M8839	CONSTR.TRAFF.STR.(PAINT)(100MM WIDE)	3,348.000	M
856(C)	M8851	REM.PAVEMENT MARKING TAPE(100MM WIDE)	8,062.000	M
859(A)	M8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	265.000	M
871	M8705	(PL)CONST.ZONE QUADGUARD IMPACT ATTEN.	1.000	EA
880(B)	M8818	CONSTRUCTION SIGNS 0 TO 0.59 M2	3,960.000	SD
880(B)	M8821	CONSTRUCTION SIGNS 0.60 M2 TO 1.47 M2	11,228.000	SD
880(B)	M8824	CONSTRUCTION SIGNS 1.48 M2 TO 3.06 M2	1,855.000	SD
880(C)	M8842	BARRICEDES(TYPE III)	2,545.000	SD
880(C)	M8848	WING BARRICADES	1,317.000	SD
880(D)	M8854	VERTICAL PANELS	5,537.000	SD
880(E)	M8860	WARNING LIGHTS(TYPE A)	3,750.000	SD
880(F)	M8878	DRUMS	14,276.000	SD
890(A)	M8722	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM

SECTION NO. 0007 STAK-STAKING - MGEY-119B(30)MGSY-19B(265)/BRFY-119B(31)

642	M0098	STAKING	1.000	LSUM
-----	-------	---------	-------	------

LNTCIQA
 CALL ORDER : 080
 LETTING DATE : July 26, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES: ELLIS

FEDERAL PROJECT
 CONTRACT ID : 010274
 PCN : 1676304
 PROJECTS : NHY-19N(51)
 DBE/WBE GOALS: 10.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE: \$ 7.55
 RES. ENG.:
 CAL. DAYS: 150

PAGE 11

LIQ. DAM: \$ 1000

CONTRACT DESCRIPTION:
 WIDEN AND RESURFACE(SUPERPAVE)
 BEGIN AT THE TEXAS STATE LINE EXT. EAST TO THE AT&SF
 RAILROAD BRIDGE ON US-60
 PROJ. LGTH.= 1.480 KM.
 FLEX. ESALS= 2.2 MILLION
 ASPH. GRADE= 70-28 OK, 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
201	M0102	CLEARING AND GRUBBING	1.000
202(A)	M0183	UNCLASSIFIED EXCAVATION	26,903.000
202(C)	M0184	UNCLASSIFIED BORROW	100.000
205	M4229	TYPE A-SALVAGED TOPSOIL	1.000
222	M2801	TEMPORARY BALE BARRIER	150.000
223	M2802	TEMPORARY SILT FENCE	100.000
226	M2805	TEMPORARY SEDIMENT REMOVAL	20.000
229	M4318	DITCH LINER PROTECTION	1,908.000
230(A)	M2806	SOLID SLAB SODDING	3,340.000
230(F)	M2812	WATERING	6,830.000
232(B)	M2814	SEEDING METHOD B	11.480
233(A)	M2817	VEGETATIVE MULCHING	5.910
233(C)	M2819	ASPHALT MULCHING	78,036.000
234(A)	M2824	FERTILIZING (10-20-10)	3.489
234(A)	M4406	FERTILIZING (0-46-0)	1.250
241	M2832	MOWING	5.910
317(A)	M4252	(SP)FLY ASH	551.250
317(B)	M4254	SUBGRADE MODIFICATION	7,709.000
317(C)	M4253	LIME	15.320
317(D)	M4254	SCARIFY, MIX BLADE OF SUBGRADE W/LIME TRT	770.900
403(E)	M0225	TRAFFIC BOUND SURFACE COURSE TYPE E	172.360
407	M0250	TACK COAT	5,978.110
408	M5774	PRIME COAT	5,781.140
411(S3)	M5940	(SP)ASPH.CONC., TYPE S3(PG 70-28 OK)	3,549.000
411(S3)	M5945	(SP)ASPH.CONC., TYPE S3(PG 64-22 OK)	2,057.000
411(S4)	M5955	(SP)ASPH.CONC., TYPE S4(PG 70-28 OK)	2,140.250
413(A)	M4861	RUMBLE STRIP-METHOD AC-CON	2,960.000
417	M5267	COLD MILLING PAVEMENT	432.000
420(A)	M4242	FABRIC REINFORCEMENT	12,136.000
420(B)	M4268	BITUMINOUS BINDER	13,714.000
501(A)	M0313	STRUCTURAL EXCAVATION UNCLASSIFIED	32.000
501(G)	M6309	CLSM BACKFILL	6.700
509(B)	M0321	CLASS A CONCRETE	118.000
509(D)	M0325	CLASS C CONCRETE	600.000

SECTION NO. 0001

I000-ROADWAY

511(A)	M0332	REINFORCING STEEL	8,550.000	KG
601A-1	M0536	TYPE I-A PLAIN RIPRAP	506.000	T
601A-2	M0538	TYPE I-A FILTER BLANKET	159.000	T
610(G)	M4475	BITUMINOUS DRIVEWAY (150MM)	1,173.000	M2
613(B)	M4464	610MM X 960MM R.C.PIPE ELL. CLASS HE-III		17.100 M
613(CC)	M7186	TYPE A4 CULVERT END TREATMENT	2.000	EA
613(CC)	M7187	TYPE B4 CULVERT END TREATMENT	2.000	EA
613(CC)	M7188	TYPE C4 CULVERT END TREATMENT	2.000	EA
613(D)	M0689	450MM CORR. GALV. STEEL PIPE	28.000	M
613(D)	M0690	600MM CORR. GALV. STEEL PIPE	22.000	M
619(A)	M0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B)	M0291	REMOVAL OF HEADWALL	8.000	EA
619(C)	M0924	SAWING PAVEMENT	165.000	M
640	M1426	FIELD OFFICE	1.000	EA
641	M1552	MOBILIZATION	1.000	LSUM
643	M0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM

SECTION NO. 0002

Y002-TRAFFIC

855(A)	M8815	TRAF.STR.(PLAST.)(THIN-LINE)(100MM WIDE)	5,920.000	M
876(C)	M8482	(PL)TRUCK MOUNTED ATTENUATOR	75.000	SD
880(J)	M8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890A/B	M8756	(PL)REMOVE & RESET EXISTING SIGNS	10.000	EA

SECTION NO. 0003

STAK-STAKING

642	M0098	STAKING	1.000	LSUM
-----	-------	---------	-------	------

LNTCIQA
CALL ORDER : 120
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: HARPER

STATE PROJECT
CONTRACT ID : 010293
PCN : 1875704

PAGE 13

PROJECTS : SAP-130B(41)
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: 30 LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
RESURFACE(ASPHALT)
IND. ACCESS: APP. 3.5 MILES EAST OF BUFFALO
ON US-64, EXTEND EAST TO BUFFALO FEEDERS.
PROJ. LGTH.= 2.70 MILES
ASPH GRADE = 64-22 & 70-28 PG OK
FLEX ESALS = 2.7 MILLION

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY SAP-130B(41)		
411(A) 6500	(SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	1,600.000	TON
411(A) 6510	(SP)ASPHALT CONCRETE TYPE A(PG 70-28 OK)	1,600.000	TON
411(B) 6540	(SP)ASPHALT CONCRETE TYPE B(PG 70-28 OK)	1,700.000	TON
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

LNTCIQA
CALL ORDER : 130
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: TEXAS

STATE PROJECT
CONTRACT ID : 010294
PCN : 1887604
PROJECTS : SAP-170D(77)
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: 30 LIQ. DAM: \$ 500

PAGE 14

CONTRACT DESCRIPTION:
RESURFACE(ASPHALT)
IND ACCESS: 1.0 MI. SW OF HOOKER ON US-54
FOR COLLINGWOOD ELEVATOR
PROJ. LGTH.= .703 MILE
FLEX ESALS = 4.7 MILLION
ASPH GRADE = 64-22 PG OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY SAP-170D(77)		
411(A) 6500	(SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	2,050.000	TON
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	2,500.000	TON

LNTCIQA
CALL ORDER : 140
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: HARPER
TEXAS

STATE PROJECT
CONTRACT ID : 010295
PCN : 1875704C

PAGE 15

PROJECTS : SAP-130B(41)/SAP-170D(77)
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: 50 LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
RESURFACE(ASPHALT)
IND ACCESS: 3.5 MI. EAST OF BUFFALO ON US-64
EXT. E. AND BEGIN 1.0 MI. SW OF HOOKER ON US-54.
PROJ. LGTH.= 3.403 MILE
ASPH GRADE = 64-22 PG OK & 70-28 PG OK
FLEX ESALS = 4.7 MILLION

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY SAP-130B(41)			
411(A) 6500	(SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	1,600.000	TON
411(A) 6510	(SP)ASPHALT CONCRETE TYPE A(PG 70-28 OK)	1,600.000	TON
411(B) 6540	(SP)ASPHALT CONCRETE TYPE B(PG 70-28 OK)	1,700.000	TON
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002 I000-ROADWAY SAP-170D(77)			
411(A) 6500	(SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	2,050.000	TON
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	2,500.000	TON

LNTCIQA
 CALL ORDER : 170
 LETTING DATE : July 26, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES: HUGHES

FEDERAL PROJECT
 CONTRACT ID : 010278
 PCN : 1739704
 PROJECTS : STP-132C(23)
 DBE/WBE GOALS: 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE: \$ 9.17
 RES. ENG.:
 CAL. DAYS: 30 LIQ. DAM: \$ 500

PAGE 16

CONTRACT DESCRIPTION:
 RESURFACE(ASPHALT)
 COUNTY ROAD(EW-133) BEGINNING AT THE JCT. OF US-270/US-75
 AND EXTENDING EAST TO LAMAR
 PROJ. LGTH.= 7.105 MILES
 FLEX. ESALS= 0.8 MILLION
 ASPH. GRADE= 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
201	0102 CLEARING AND GRUBBING	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	500.000	LF
303	0192 AGGREGATE BASE	6,360.000	CY
311(D)	0154 PROCESS EXISTING BASE & SURFACE, METHOD D		21.000 STA
407	0250 TACK COAT	6,070.000	GAL
408	5774 PRIME COAT	3,895.000	GAL
411(A)	6500 (SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	7,535.000	TON
411(B)	6530 (SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	10,822.000	TON
619(B)	4728 REMOVAL OF ASPHALT PAVEMENT	7,449.000	SY
641	1552 MOBILIZATION	1.000	LSUM
850(A)	8110 SHEET ALUMINUM SIGNS	80.400	SF
851(D)	8597 FLANGE CHANNEL POSTS(4 LB/FT)	208.000	LF
853	9039 DELINEATORS(TYPE 2, CODE 3)	56.000	EA
853	9048 DELINEATORS(TYPE 1, CODE 3, FLEXIBLE)	24.000	EA
855(A)	8815 TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	130,000.000	LF
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

LNTCIQA
 CALL ORDER : 180
 LETTING DATE : July 26, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES: KAY

FEDERAL PROJECT
 CONTRACT ID : 010279
 PCN : 0042212
 PROJECTS : STPY-136B(001)
 DBE/WBE GOALS: 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE: \$ 17.80
 RES. ENG.:
 CAL. DAYS: 120

PAGE 17

LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
 GRADE, DRAIN AND SURFACE(SUPERPAVE)
 BEGIN 9.656 KM SOUTH OF THE JCT OF US-60/US-177
 IN PONCA CITY AND EXTEND NORTH ON US-177
 PROJ. LGTH.= 6.291 KM.
 FLEX. ESALS= 4.31 MILLION
 ASPH. GRADE= 64-22 OK, 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	I000-ROADWAY		
201	M0102	CLEARING AND GRUBBING	1.000
202(A)	M0183	UNCLASSIFIED EXCAVATION	8,012.000
202(C)	M0184	UNCLASSIFIED BORROW	2,639.000
205	M4229	TYPE A-SALVAGED TOPSOIL	1.000
222	M2801	TEMPORARY BALE BARRIER	100.000
223	M2802	TEMPORARY SILT FENCE	100.000
226	M2805	TEMPORARY SEDIMENT REMOVAL	25.000
230(A)	M2806	SOLID SLAB SODDING	15,000.000
230(B)	M2807	MULCH SODDING	40,740.000
230(F)	M2812	WATERING	10,033.000
233(A)	M2817	VEGETATIVE MULCHING	5.570
234(A)	M2824	FERTILIZING (10-20-10)	6.130
234(A)	M4407	FERTILIZING (13-13-13)	0.950
241	M2832	MOWING	5.570
303	M0192	AGGREGATE BASE	13,510.000
307(A)	M4233	LIME	2,297.000
307(B)	M4234	150MM LIME TREATED SUBGRADE	99,223.000
403(A)	M0217	TRAFFIC BOUND SURFACE COURSE TYPE A	494.000
407	M0250	TACK COAT	37,500.000
408	M5774	PRIME COAT	57,852.000
411(S3)	M5940	(SP)ASPH.CONC.,TYPE S3(PG 70-28 OK)	13,220.400
411(S3)	M5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	14,204.800
411(S4)	M5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	8,665.400
411(S4)	M5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	377.900
509(D)	M0325	CLASS C CONCRETE	50.000
613(CC)	M7196	TYPE A6 CULVERT END TREATMENT	3.000
613(CC)	M7197	TYPE B6 CULVERT END TREATMENT	3.000
613(D)	M5205	510MM X 380MM CORR. GALV. ST. PIPE ARCH	70.000
613(D)	M5214	680MM X 500MM CORR. GALV. ST. PIPE ARCH	50.500
613(M)	M4508	560MM X 345MM PREFAB.CULV.END SEC., ARCH	5.000
613(M)	M4516	700MM X 500MM PREFAB.CULV.END SEC., ARCH	3.000
619(B)	M4728	REMOVAL OF ASPHALT PAVEMENT	3,000.000
619(C)	M0924	SAWING PAVEMENT	120.000
629(A)	M4958	MAILBOX INSTALLATION-SINGLE	8.000

SECTION NO. 0001 I000-ROADWAY

629(C)	M4960	MAILBOX	8.000	EA
629(D)	M4961	REMOVAL OF MAILBOX INSTALLATION	8.000	EA
641	M1552	MOBILIZATION	1.000	LSUM
643	M0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM

SECTION NO. 0002 Y008-TRAFFIC

850(A)	M8110	SHEET ALUMINUM SIGNS	14.840	M2
851(C)	M8327	57MM SQUARE TUBE POST	161.900	M
855(A)	M8812	TRAFFIC STRIPE(PLASTIC)(100MM WIDE)	28,310.000	M
859(A)	M8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	14,000.000	M
880(J)	M8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION NO. 0003 STAK-STAKING

642	M0098	STAKING	1.000	LSUM
-----	-------	---------	-------	------

LNTCIQA
CALL ORDER : 190
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: LOGAN

STATE PROJECT
CONTRACT ID : 010296
PCN : 1887404

PAGE 19

PROJECTS : SAP-142D(62)
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
RESURFACE
INDUSTRIAL ACCRESS FOR CLARK METAL: APPROX. 2.0 MILE NORTH
OF JCT. SH-74C/SH-74 IN CRESCENT, EXTEND EAST.
PROJ. LGTH.= 1.65 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
303 5912	AGGREGATE BASE	3,500.000	TON
325 5271	SEPARATOR FABRIC	18,600.000	SY
402(A) 0204	BITUMINOUS BINDER	70.000	TON
402B-1 0206	NO.1 COVER AGGREGATE	400.000	TON
402B-2 0208	NO.2 COVER AGGREGATE	500.000	TON
408 5774	PRIME COAT	6,000.000	GAL

LNTCIQA
 CALL ORDER : 220
 LETTING DATE : July 26, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES: NOBLE

FEDERAL PROJECT
 CONTRACT ID : 010281
 PCN : 0812804
 PROJECTS : BRFY-52C(152)
 DBE/WBE GOALS: 9.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE: \$ 44.23
 RES. ENG.:
 CAL. DAYS: 300

PAGE 20

LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES
 BRIDGE OVER PETTIT CREEK AND LONG BRANCH CREEK,
 EAST OF RED ROCK ON SH-15
 PROJ. LGTH.= 1.565 KM
 FLEX. ESALS= 0.71 MILLION
 ASPH. GRADE= 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
201	M0102	CLEARING AND GRUBBING	1.000
202(A)	M0183	UNCLASSIFIED EXCAVATION	45,140.000
202(C)	M0184	UNCLASSIFIED BORROW	22,618.000
205	M4229	TYPE A-SALVAGED TOPSOIL	1.000
222	M2801	TEMPORARY BALE BARRIER	250.000
223	M2802	TEMPORARY SILT FENCE	650.000
226	M2805	TEMPORARY SEDIMENT REMOVAL	30.000
229	M4318	DITCH LINER PROTECTION	240.000
230(A)	M2806	SOLID SLAB SODDING	13,980.000
230(D)	M2810	BROADCAST SPRIGGING (METHOD A)	32,960.000
232(B)	M2814	SEEDING METHOD B	18.240
233(A)	M2817	VEGETATIVE MULCHING	20.820
234(A)	M2824	FERTILIZING (10-20-10)	7.470
234(A)	M4406	FERTILIZING (0-46-0)	1.960
241	M2832	MOWING	11.560
317(A)	M4252	(SP)FLY ASH	1,181.000
317(B)	M4254	SUBGRADE MODIFICATION	20,498.000
317(C)	M4253	LIME	40.000
317(D)	M4254	SCARIFY,MIX BLADE OF SUBGRADE W/LIME TRT	2,050.000
403(A)	M0217	TRAFFIC BOUND SURFACE COURSE TYPE A	529.000
407	M0250	TACK COAT	13,333.000
408	M5774	PRIME COAT	27,580.000
411(A)	M6500	(SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	6,706.000
411(B)	M6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	7,945.000
501(A)	M0313	STRUCTURAL EXCAVATION UNCLASSIFIED	33.000
509(B)	M0321	CLASS A CONCRETE	85.000
509(D)	M0325	CLASS C CONCRETE	46.000
511(A)	M0332	REINFORCING STEEL	11,081.000
610(B)	M0604	150MM CONCRETE DRIVEWAY	48.000
613(CC)	M7196	TYPE A6 CULVERT END TREATMENT	16.000
613(CC)	M7197	TYPE B6 CULVERT END TREATMENT	6.000
613(CC)	M7198	TYPE C6 CULVERT END TREATMENT	4.000
613(D)	M0689	450MM CORR. GALV. STEEL PIPE	269.000
613(D)	M0690	600MM CORR. GALV. STEEL PIPE	71.000

SECTION NO. 0001

I000-ROADWAY

613(D)	M0691	750MM CORR. GALV. STEEL PIPE	71.000	M
613(P)	M1091	150MM PERFORATED PIPE UNDERDRAIN ROUND	187.500	M
613(Q)	M1096	150MM NON-PERF.PIPES UNDERDRAIN RND.	62.500	M
613(R)	M1100	PIPE UNDERDRAIN COVER MAT'L.	38.000	M3
613(S)	M1180	TRENCH EXCAVATION	50.000	M3
613(T)	M1181	STANDARD BEDDING MATERIAL	13.000	M3
619(A)	M0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B)	M4727	REMOVAL OF CONCRETE PAVEMENT	313.000	M2
619(B)	M4728	REMOVAL OF ASPHALT PAVEMENT	25,757.000	M2
619(C)	M0924	SAWING PAVEMENT	29.000	M
623(A)	M0932	BEAM GUARD RAIL-W-BEAM-SINGLE	463.000	M
623(F)	M4447	GUARD RAIL ANCHOR UNIT (TYPE B)	4.000	EA
623(F)	M5686	GUARD RAIL ANCHOR UNIT (TYPE D-BF)	8.000	EA
623(H)	M8571	(SP)G.E.T. GUARD RAIL END SECTION	4.000	EA
624(C)	M4459	FENCE-STYLE SWF (5 BARBED WIRE)	3,256.000	M
624(D)	M4290	FENCE-STYLE CLF (1500MM HIGH, CLASS A)	260.000	M

SECTION NO. 0002

X081-BRIDGE 'A'

202(A)	M1301	UNCLASSIFIED EXCAVATION	1,770.000	M3
501(B)	M1307	SUBSTRUCTURE EXCAVATION COMMON	104.000	M3
501(F)	M6352	GRANULAR BACKFILL	79.000	M3
503(A)	M1311	PRESTRESSED CONCRETE BEAMS (TYPE II)	142.800	M
504(A)	M1304	APPROACH SLAB	152.000	M2
504(E)	M6239	CONCRETE RAIL (TR3)	98.400	M
506(A)	M1322	STRUCTURAL STEEL	1,863.400	KG
509(A)	M1326	CLASS AA CONCRETE	125.500	M3
509(B)	M1328	CLASS A CONCRETE	69.600	M3
509(D)	M1331	CLASS C CONCRETE	16.000	M3
511(A)	M1332	REINFORCING STEEL	17,337.600	KG
511(B)	M6010	EPOXY COATED REINFORCING STEEL	1,847.000	KG
514(A)	M6011	PILES, FURNISHED (HP 250X62)	115.000	M
514(B)	M6292	PILES, DRIVEN (HP 250X62)	115.000	M
514(F)	M6354	PILE LOAD TEST (DYNAMIC)	10.000	EA
515(A)	M6013	WATER REPELLENT (VISUALLY INSPECTED)	325.400	M2
516(A)	M6094	DRILLED SHAFTS 1200MM DIAMETER	18.680	M
601A-1	M1353	TYPE I-A PLAIN RIPRAP	1,360.000	T
601A-2	M1355	TYPE I-A FILTER BLANKET	275.000	T
609(D)	M0398	BITUMINOUS CURBING	346.700	M
613(P)	M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	25.420	M
613(Q)	M6207	150MM NON-PERF.PIPES UNDERDRAIN RND.	10.200	M
619(D)	M1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
640	M1398	FIELD OFFICE	1.000	EA
641	M1399	MOBILIZATION	1.000	LSUM
643	M0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM

SECTION NO. 0003

X028-BRIDGE 'B'

202(A)	M1301	UNCLASSIFIED EXCAVATION	840.000	M3
501(A)	M1306	STRUCTURAL EXCAVATION UNCLASSIFIED	120.000	M3
509(B)	M1328	CLASS A CONCRETE	213.000	M3
511(A)	M1332	REINFORCING STEEL	12,230.000	KG
619(B)	M2500	(PL)REMOVAL OF BRIDGE ITEMS	1.000	LSUM

SECTION NO. 0004

X081-BRIDGE 'C'

SECTION NO. 0004

X081-BRIDGE 'C'

202(A)	M1301	UNCLASSIFIED EXCAVATION	1,520.000	M3
501(B)	M1307	SUBSTRUCTURE EXCAVATION COMMON	315.600	M3
501(F)	M6352	GRANULAR BACKFILL	75.600	M3
503(A)	M1311	PRESTRESSED CONCRETE BEAMS (TYPE II)	142.800	M
504(A)	M1304	APPROACH SLAB	308.000	M2
504(C)	M6276	(PL)SEALED EXPANSION JOINTS	28.700	M
504(E)	M6239	CONCRETE RAIL (TR3)	122.400	M
506(A)	M1322	STRUCTURAL STEEL	2,415.000	KG
509(A)	M1326	CLASS AA CONCRETE	106.200	M3
509(B)	M1328	CLASS A CONCRETE	112.200	M3
509(D)	M1331	CLASS C CONCRETE	16.000	M3
511(A)	M1332	REINFORCING STEEL	5,802.100	KG
511(B)	M6010	EPOXY COATED REINFORCING STEEL	22,535.000	KG
514(A)	M6011	PILES, FURNISHED (HP 250X62)	219.200	M
514(B)	M6292	PILES, DRIVEN (HP 250X62)	219.200	M
514(F)	M6354	PILE LOAD TEST (DYNAMIC)	18.000	EA
515(A)	M6013	WATER REPELLENT (VISUALLY INSPECTED)	620.100	M2
516(A)	M6094	DRILLED SHAFTS 1200MM DIAMETER	37.200	M
601A-1	M1353	TYPE I-A PLAIN RIPRAP	1,250.000	T
601A-2	M1355	TYPE I-A FILTER BLANKET	245.000	T
609(D)	M0398	BITUMINOUS CURBING	286.500	M
613(P)	M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	54.400	M
613(Q)	M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	29.400	M
619(D)	M1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

SECTION NO. 0005

Y008-TRAFFIC CONTROL

850(A)	M8110	SHEET ALUMINUM SIGNS	0.580	M2
851(C)	M8327	57MM SQUARE TUBE POST	4.110	M
855(A)	M8815	TRAF.STR.(PLAST.)(THIN-LINE)(100MM WIDE)	7,420.000	M
855(B)	M8824	TRAFFIC STRIPE(PLASTIC)(SYMBOLS)	2.000	EA
890	M7702	(PL)TRAFFIC ITEMS(TRAFFIC CONTROL)	1.000	LSUM

SECTION NO. 0006

STAK-STAKING

642	M0098	STAKING	1.000	LSUM
-----	-------	---------	-------	------

LNTCIQA
 CALL ORDER : 320
 LETTING DATE : July 26, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES: PITTSBURG

FEDERAL PROJECT
 CONTRACT ID : 010287
 PCN : 1273704
 PROJECTS : BRF-61C(366)CO
 DBE/WBE GOALS: 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE: \$ 3.24
 RES. ENG.:
 CAL. DAYS: 120 LIQ. DAM: \$ 500

PAGE 23

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES
 TRIBUTARY OF COAL CREEK, 2.7 MILES SOUTH AND 0.4 MILE
 EAST OF INDIANOLA
 PROJ. LGTH.= 0.146 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000-ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	6181 EARTHWORK	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	500.000	LF
223	2801 TEMPORARY SILT FENCE	1,000.000	LF
230(A)	2806 SOLID SLAB SODDING	6,750.000	SY
233(A)	2817 VEGETATIVE MULCHING	2.200	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	455.500	TON
509(D)	1331 CLASS C CONCRETE	10.000	CY
SECTION NO. 0002 X081-BRIDGE 'A'			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	78.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	64.000	CY
503(A)	1312 PRESTRESSED CONCRETE BEAMS (TYPE III)	276.670	LF
504(E)	1380 CONCRETE RAIL (TR1)	197.000	LF
506(A)	1322 STRUCTURAL STEEL	1,620.000	LB
509(A)	1326 CLASS AA CONCRETE	54.700	CY
509(B)	1328 CLASS A CONCRETE	48.800	CY
511(A)	1332 REINFORCING STEEL	19,270.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	272.000	LF
514(A)	6011 PILES, FURNISHED (HP 12X53)	646.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	272.000	LF
514(B)	6294 PILES, DRIVEN (HP 12X53)	646.000	LF
514(G)	6310 METAL PILE SHOES	10.000	EA
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	340.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	70.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING			
642	0098 STAKING	1.000	LSUM

LNTCIQA
 CALL ORDER : 330
 LETTING DATE : July 26, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES: PITTSBURG

FEDERAL PROJECT
 CONTRACT ID : 010288
 PCN : 1816504
 PROJECTS : BR0-161D(54) CO
 DBE/WBE GOALS: 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE: \$ 4.32
 RES. ENG.:
 CAL. DAYS: 120

PAGE 24

LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES
 BRIDGE OVER UNNAMED CREEK, 1.0 MILE NORTH AND
 0.5 MILE EAST OF CROWDER
 PROJ. LGTH.= 0.131 MILE
 FLEX. ESALS= 0.1 MILLION
 ASPH. GRADE= 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	I000-ROADWAY		
201 0102	CLEARING AND GRUBBING	1.000	LSUM
202(G) 0185	EARTHWORK	1.000	LSUM
205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
227 0100	TEMPORARY SILT DIKE	2,300.000	LF
230(A) 2806	SOLID SLAB SODDING	3,251.000	SY
233(A) 2817	VEGETATIVE MULCHING	2.000	AC
303 0192	AGGREGATE BASE	557.000	CY
408 5774	PRIME COAT	815.000	GAL
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)		342.000 TON
509(D) 0325	CLASS C CONCRETE	71.400	CY
613(D) 4528	28" X 20" CORR. GALV. STEEL PIPE ARCH	94.000	LF
613(D) 5739	84" CORR. GALV. STEEL PIPE	152.000	LF
613(G) 4571	28" X 20" GALV. STEEL CULV. END SEC.ARCH		4.000 EA
850(A) 8110	SHEET ALUMINUM SIGNS	8.500	SF
851(D) 8597	FLANGE CHANNEL POSTS(4 LB/FT)	17.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	2,800.000	LF
SECTION NO. 0002	X081-BRIDGE 'A'		
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	57.000	CY
501(C) 1308	SUBSTRUCTURE EXCAVATION ROCK	7.100	CY
501(D) 6353	UNCLASSIFIED BACKFILL	61.000	CY
503(A) 1312	PRESTRESSED CONCRETE BEAMS (TYPE III)	296.670	LF
504(E) 1380	CONCRETE RAIL (TR1)	207.000	LF
506(A) 1322	STRUCTURAL STEEL	1,620.000	LB
509(A) 1326	CLASS AA CONCRETE	59.500	CY
509(B) 1328	CLASS A CONCRETE	43.800	CY
511(A) 1332	REINFORCING STEEL	19,630.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	25.000	LF
514(A) 6011	PILES, FURNISHED (HP 12X53)	85.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	25.000	LF
514(B) 6294	PILES, DRIVEN (HP 12X53)	85.000	LF
601(A-1)1353	TYPE I-A PLAIN RIPRAP	370.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	105.000	TON

SECTION NO. 0002	X081-BRIDGE 'A'		
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	60.000	LF
613(Q) 6207	6" NON-PERF.PIPES UNDERDRAIN RND.	36.000	LF
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F) 6034	GUARD RAIL ANCHOR UNIT (TYPE III)	4.000	EA
641 1399	MOBILIZATION	1.000	LSUM
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	STAK-STAKING		
642 0098	STAKING	1.000	LSUM

LNTCIQA
 CALL ORDER : 340
 LETTING DATE : July 26, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES: PITTSBURG

FEDERAL PROJECT
 CONTRACT ID : 010289
 PCN : 1273704C

PAGE 26

PROJECTS : BRF-61C(366)C0/BRO-161D(54)C0
 DBE/WBE GOALS: 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE: \$ 7.56
 RES. ENG.:
 CAL. DAYS: 240 LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
 BRIDGES AND APPROACHES
 TRIBUTARY OF COAL CREEK, 2.7 MILES SOUTH AND 0.4 MILE EAST
 OF
 INDIANOLA AND BRIDGE OVER UNNAMED CREEK, 1.0 MILES NORTH
 AND 0.5 MILE EAST OF CROWDER
 PROJ. LGTH.= 0.277 MILE
 FLEX. ESALS= 0.1 MILLION
 ASPH. GRADE= 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000-ROADWAY BRF-61C(366)C0			
201 0102	CLEARING AND GRUBBING	1.000	LSUM
202(G) 6181	EARTHWORK	1.000	LSUM
222 2801	TEMPORARY BALE BARRIER	500.000	LF
223 2801	TEMPORARY SILT FENCE	1,000.000	LF
230(A) 2806	SOLID SLAB SODDING	6,750.000	SY
233(A) 2817	VEGETATIVE MULCHING	2.200	AC
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	455.500	TON
509(D) 1331	CLASS C CONCRETE	10.000	CY
SECTION NO. 0002 I000-ROADWAY BRO-161D(54)C0			
201 0102	CLEARING AND GRUBBING	1.000	LSUM
202(G) 0185	EARTHWORK	1.000	LSUM
205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
227 0100	TEMPORARY SILT DIKE	2,300.000	LF
230(A) 2806	SOLID SLAB SODDING	3,251.000	SY
233(A) 2817	VEGETATIVE MULCHING	2.000	AC
303 0192	AGGREGATE BASE	557.000	CY
408 5774	PRIME COAT	815.000	GAL
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	342.000	TON
509(D) 0325	CLASS C CONCRETE	71.400	CY
613(D) 4528	28" X 20" CORR. GALV. STEEL PIPE ARCH	94.000	LF
613(D) 5739	84" CORR. GALV. STEEL PIPE	152.000	LF
613(G) 4571	28" X 20" GALV. STEEL CULV. END SEC.ARCH	4.000	EA
850(A) 8110	SHEET ALUMINUM SIGNS	8.500	SF
851(D) 8597	FLANGE CHANNEL POSTS(4 LB/FT)	17.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	2,800.000	LF
SECTION NO. 0003 X081-BRIDGE 'A' BRF-61C(366)C0			
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	78.000	CY
501(D) 6353	UNCLASSIFIED BACKFILL	64.000	CY

SECTION NO. 0003 X081-BRIDGE 'A' BRF-61C(366)C0

503(A)	1312	PRESTRESSED CONCRETE BEAMS (TYPE III)	276.670	LF
504(E)	1380	CONCRETE RAIL (TR1)	197.000	LF
506(A)	1322	STRUCTURAL STEEL	1,620.000	LB
509(A)	1326	CLASS AA CONCRETE	54.700	CY
509(B)	1328	CLASS A CONCRETE	48.800	CY
511(A)	1332	REINFORCING STEEL	19,270.000	LB
514(A)	6010	PILES, FURNISHED (HP 10X42)	272.000	LF
514(A)	6011	PILES, FURNISHED (HP 12X53)	646.000	LF
514(B)	6292	PILES, DRIVEN (HP 10X42)	272.000	LF
514(B)	6294	PILES, DRIVEN (HP 12X53)	646.000	LF
514(G)	6310	METAL PILE SHOES	10.000	EA
601(A-1)	1353	TYPE I-A PLAIN RIPRAP	340.000	TON
601(A-2)	1355	TYPE I-A FILTER BLANKET	70.000	TON
619(D)	1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641	1399	MOBILIZATION	1.000	LSUM
880(J)	8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION NO. 0004 X081-BRIDGE 'A' BR0-161D(54)C0

501(B)	1307	SUBSTRUCTURE EXCAVATION COMMON	57.000	CY
501(C)	1308	SUBSTRUCTURE EXCAVATION ROCK	7.100	CY
501(D)	6353	UNCLASSIFIED BACKFILL	61.000	CY
503(A)	1312	PRESTRESSED CONCRETE BEAMS (TYPE III)	296.670	LF
504(E)	1380	CONCRETE RAIL (TR1)	207.000	LF
506(A)	1322	STRUCTURAL STEEL	1,620.000	LB
509(A)	1326	CLASS AA CONCRETE	59.500	CY
509(B)	1328	CLASS A CONCRETE	43.800	CY
511(A)	1332	REINFORCING STEEL	19,630.000	LB
514(A)	6010	PILES, FURNISHED (HP 10X42)	25.000	LF
514(A)	6011	PILES, FURNISHED (HP 12X53)	85.000	LF
514(B)	6292	PILES, DRIVEN (HP 10X42)	25.000	LF
514(B)	6294	PILES, DRIVEN (HP 12X53)	85.000	LF
601(A-1)	1353	TYPE I-A PLAIN RIPRAP	370.000	TON
601(A-2)	1355	TYPE I-A FILTER BLANKET	105.000	TON
613(P)	6204	6" PERFORATED PIPE UNDERDRAIN ROUND	60.000	LF
613(Q)	6207	6" NON-PERF. PIPE UNDERDRAIN RND.	36.000	LF
619(D)	1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	6034	GUARD RAIL ANCHOR UNIT (TYPE III)	4.000	EA
641	1399	MOBILIZATION	1.000	LSUM
880(J)	8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION NO. 0005 STAK-STAKING BRF-61C(366)C0

642	0098	STAKING	1.000	LSUM
-----	------	---------	-------	------

SECTION NO. 0006 STAK-STAKING BR0-161D(54)C0

642	0098	STAKING	1.000	LSUM
-----	------	---------	-------	------

LNTCIQA
CALL ORDER : 366
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: WOODS

FEDERAL PROJECT
CONTRACT ID : 010338
PCN : 1257009
PROJECTS : STPY-176B(49) RW
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: 30 LIQ. DAM: \$ 500

PAGE 28

CONTRACT DESCRIPTION:
RIGHT-OF-WAY CLEARANCE
BEGIN 1.6 MILES EAST OF ALVA EXTEND EAST TO THE ALFALFA
COUNTY LINE ON US-64
PROJ. LGTH.= 9.809 KM.

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROWA-RIGHT- OF- WAY CLEARANCE		
643 0094	(PL)RIGHT-OF-WAY CLEARANCE	1.000	LSUM
643 0100	(PL)NESHAP PREDEM. INSP. & NOTIFICATION		1.000 EA

LNTCIQA
CALL ORDER : 440
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: BEAVER

STATE PROJECT
CONTRACT ID : 010311
PCN : 1914304
PROJECTS : MC-104B(21)PT.1
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: 30 LIQ. DAM: \$ 500

PAGE 29

CONTRACT DESCRIPTION:
RESURFACE(ASPHALT)
BEGIN 22.0 MILES WEST OF THE BEAVER/HARPER COUNTY
LINE AND EXTEND EAST ON US-64
PROJ. LGTH.= 5.0 MILES
FLEX. ESALS= 1.5 MILLION
ASPH. GRADE= 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
411(A) 6500	(SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	2,650.000	TON
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	6,900.000	TON
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

LNTCIQA
CALL ORDER : 450
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: BEAVER

STATE PROJECT
CONTRACT ID : 010312
PCN : 1914305

PAGE 30

PROJECTS : MC-104B(21)PT.2
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: 30 LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
RESURFACE(ASPHALT)
BEGIN 17.0 MILES WEST OF THE BEAVER/HARPER COUNTY
LINE AND EXTEND EAST ON US-64
PROJ. LGTH. 5.0 MILES
FLEX. ESALS= 1.5 MILLION
ASPH. GRADE= 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	9,250.000	TON
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

LNTCIQA
CALL ORDER : 460
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: BEAVER

STATE PROJECT
CONTRACT ID : 010313
PCN : 1914306

PAGE 31

PROJECTS : MC-104B(21)PT.3
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
RESURFACE(ASPHALT)
BEGIN 12.0 MILES WEST OF THE BEAVER/HARPER COUNTY LINE
AND EXTEND EAST ON US064
PROJ. LGTH.= 5.0 MILES
FLEX. ESALS= 1.5 MILLION
ASPH. GRADE= 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	9,250.000	TON
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

LNTCIQA
CALL ORDER : 461
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: BEAVER

STATE PROJECT
CONTRACT ID : 010339
PCN : 1929504
PROJECTS : MC-104B(22)
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

PAGE 32

CONTRACT DESCRIPTION:
RESURFACE(ASPHALT)
BEGIN 28.6 MILES WEST OF HARPER/BEAVER COUNTY LINE, EXTEND
EAST ON US-64
PROJ. LGTH.= 6.6 MILES
FLEX. ESALS= 1.5 MILLION
ASPH. GRADE= 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
411(A) 6500	(SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	3,600.000	TON
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	9,300.000	TON
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

LNTCIQA
CALL ORDER : 470
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: HARPER

STATE PROJECT
CONTRACT ID : 010314
PCN : 1914204
PROJECTS : MC-130B(048)
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

PAGE 33

CONTRACT DESCRIPTION:
RESURFACE(ASPHALT)
BEGIN 3.85 MILES WEST OF JCT. US-64/SH-34 AND EXTEND EAST
ON US-64
PROJ. LGTH.= 6.0 MILES
FLEX. ESALS= 1.2 MILLION
ASPH. GRADE= 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
411(A) 6500	(SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	9,000.000	TON
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	12,250.000	TON
641 1552	MOBILIZATION	1.000	LSUM
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

LNTCIQA
 CALL ORDER : 480
 LETTING DATE : July 26, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES: BEAVER
 HARPER

STATE PROJECT
 CONTRACT ID : 010315
 PCN : 1914304C

PAGE 34

PROJECTS : MC-104B(21) PT.1-3/MC-130B(48)
 DBE/WBE GOALS: 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE: \$ 0.00
 RES. ENG.:
 CAL. DAYS: LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
 RESURFACE(ASPHALT)
 BEGIN 28.6 MILES WEST OF THE BEAVER/HARPER COUNTY LINE
 EXTEND EAST, THEN FROM 3.85 MILES WEST OF THE JCT. OF
 US-64/SH-34 EXTEND EAST ON US-64
 PROJ. LGTH.= 27.6 MILES
 FLEX. ESALS= 1.5 MILLION
 ASPH. GRADE= 64-22 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY MC-104B(21) PT.1		
411(A) 6500	(SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	2,650.000	TON
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	6,900.000	TON
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	I000-ROADWAY MC-104B(21) PT.2		
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	9,250.000	TON
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	I000-ROADWAY MC-104B(21) PT.3		
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	9,250.000	TON
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0004	I000-ROADWAY MC-130B(48)		
411(A) 6500	(SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	9,000.000	TON
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	12,250.000	TON
641 1552	MOBILIZATION	1.000	LSUM
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0005	I000-ROADWAY MC-104B(22)		
411(A) 6500	(SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	3,600.000	TON
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	9,300.000	TON
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

LNTCIQA
 CALL ORDER : 490
 LETTING DATE : July 26, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES: CHEROKEE
 MUSKOGEE

STATE PROJECT
 CONTRACT ID : 010316
 PCN : 1912104M
 PROJECTS : MC-111B(44)/MC-151B(82)
 DBE/WBE GOALS: 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE: \$ 0.00
 RES. ENG.:
 CAL. DAYS: 45 LIQ. DAM: \$ 500

PAGE 35

CONTRACT DESCRIPTION:
 MICRO-SURFACING
 BEGIN AT JCT. OF SH-51/US-62, EXT. SE ON US-62
 BEGIN 0.88 MILE E. OF JCT. SH-165/US-62, EXT E. ON US-62.
 PROJ. LGTH.= 7.30 MILE
 FLEX ESALS = 4.70 MILLION

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 F000-ROADWAY MC-111B(44)			
410(A) 4323	EMULSIFIED ASPHALT	43,760.000	GAL
410(C) 4760	TYPE II AGGREGATE	1,600.000	TON
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	61,620.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	30.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	15.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002 F000-ROADWAY MC-151B(82)			
410(A) 4323	EMULSIFIED ASPHALT	84,900.000	GAL
410(C) 4760	TYPE II AGGREGATE	3,525.000	TON
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	134,060.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	24.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	12.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

LNTCIQA
CALL ORDER : 500
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: LEFLORE

STATE PROJECT
CONTRACT ID : 010317
PCN : 1913104

PAGE 36

PROJECTS : MC-140A(76)PT.1
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
ARMOR COAT
BEGIN 0.5 MILE WEST OF JCT US-271/US-59 WEST OF SPIRO AND
EXTEND WEST AND NORTH ON US-59
PROJ. LGTH.= 4.97 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ARMOR COAT		
402 5205	(PL)ARMOR COAT	82,110.000	SY

LNTCIQA
CALL ORDER : 510
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: LEFLORE

STATE PROJECT
CONTRACT ID : 010318
PCN : 1913105
PROJECTS : MC-140A(76)PT. 2
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

PAGE 37

CONTRACT DESCRIPTION:
ARMOR COAT
BEGIN AT JCT OF SH-9/US-59 WEST OF SPIRO AND EXTEND
NORTH ON US-59
PROJ. LGTH.= 6.34 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	F000-ARMOR COAT		
402 5205	(PL)ARMOR COAT	125,690.000	SY

LNTCIQA
CALL ORDER : 520
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: LEFLORE

STATE PROJECT
CONTRACT ID : 010319
PCN : 1913106
PROJECTS : MC-140A(76)PT. 3
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

PAGE 38

CONTRACT DESCRIPTION:
ARMOR COAT
BEGIN AT HASKELL COUNTY LINE AND EXTEND EAST TO THE JCT
OF SH-9/US-59 ON SH-9
PROJ. LGTH.= 3.05 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	F000-ARMOR COAT		
402 5205	(PL)ARMOR COAT	42,945.000	SY

LNTCIQA
CALL ORDER : 530
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: LEFLORE

STATE PROJECT
CONTRACT ID : 010320
PCN : 1913104C

PAGE 39

PROJECTS : MC-140A(76)PT. 1, 2 & 3
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
ARMOR COAT
BEGIN AT THE HASKELL COUNTY LINE EXTEND EAST ON SH-9 AND
NORTH FROM SH-9 ON US-59
PROJ. LGTH.= 14.36 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	F000-ARMOR COAT MC-140A(76)PT. 1		
402 5205	(PL)ARMOR COAT	82,110.000	SY
SECTION NO. 0002	F000-ARMOR COAT MC-140A(76)PT. 2		
402 5205	(PL)ARMOR COAT	125,690.000	SY
SECTION NO. 0003	F000-ARMOR COAT MC-140A(76)PT. 3		
402 5205	(PL)ARMOR COAT	42,945.000	SY

LNTCIQA
CALL ORDER : 538
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: LOGAN

STATE PROJECT
CONTRACT ID : 010341
PCN : 1929704
PROJECTS : MC-142C(66)
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS:

PAGE 40

LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
RESURFACE(ASPHALT)
BEGIN AT THE OKLAHOMA/LOGAN COUNTY LINE, EXTEND
NORTH ON US-74
PROJ. LGTH.= 5.821 MILES
FLEX. ESALS= 3.2 MILLION
ASPH. GRADE= 70-28 OK

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
411(B) 6540	(SP)ASPHALT CONCRETE TYPE B(PG 70-28 OK)	10,500.000	TON
411(D) 6600	(SP)ASPHALT CONC.TYPE D(PG 70-28 OK)	3,600.000	TON
417 5267	COLD MILLING PAVEMENT	1,500.000	SY
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

LNTCIQA
CALL ORDER : 563
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: NOBLE

STATE PROJECT
CONTRACT ID : 010342
PCN : 1929804
PROJECTS : MC-152A(40)
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS:

PAGE 41

LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
RESURFACE(MICRO-SURFACE)
BEGIN AT FIR STREET AND EXTEND EAST TO CEDAR STREET
ON US-64 IN PERRY
PROJ. LGTH.= 3.413 MILES
FLEX. ESALS= N/A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY			
407 0250	TACK COAT	2,800.000	GAL
410(A) 4324	EMULSIFIED ASPHALT	250.000	TON
410(C) 4760	TYPE II AGGREGATE	2,600.000	TON
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	73,000.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	27.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	6.000	EA
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	100.000	LF
859(B) 8007	PAVEMENT MARKING REMOVAL(ARROWS)	24.000	EA
859(B) 8008	PAVEMENT MARKING REMOVAL(WORDS)	4.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

LNTCIQA
CALL ORDER : 570
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: PITTSBURG

STATE PROJECT
CONTRACT ID : 010324
PCN : 1912704
PROJECTS : MC-161C(83)
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

PAGE 42

CONTRACT DESCRIPTION:
ARMOR COAT
BEGIN AT THE EAST INDIANOLA CITY LIMITS AND EXTEND
EAST ON SH-113
PROJ. LGTH.= 6.38 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
402 5205	(PL)ARMOR COAT	97,320.000	SY

LNTCIQA
CALL ORDER : 580
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: PITTSBURG

STATE PROJECT
CONTRACT ID : 010325
PCN : 1912804
PROJECTS : MC-161B(84)
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

PAGE 43

CONTRACT DESCRIPTION:
ARMOR COAT
BEGIN AT THE MCINTOSH/PITTSBURG COUNTY LINE AND EXTEND EAST
ON SH-9
PROJ. LGTH.- 6.62 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
402 5205	(PL)ARMOR COAT	139,815.000	SY

LNTCIQA
CALL ORDER : 590
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: PITTSBURG

STATE PROJECT
CONTRACT ID : 010326
PCN : 1912904
PROJECTS : MC-161B(85)
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS:

PAGE 44

LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:

ARMOR COAT
BEGIN AT THE JCT OF US-69/SH-9A AND EXTEND EAST ON SH-9A
PROJ. LGTH.= 4.11 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
402 5205	(PL)ARMOR COAT	91,626.000	SY

LNTCIQA
CALL ORDER : 600
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: PITTSBURG

STATE PROJECT
CONTRACT ID : 010327
PCN : 1912704C

PAGE 45

PROJECTS : MC-161C(83)MC-161B(84)(85)
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:

ARMOR COAT
BEG AT E. INDIANOLA CITY LIMITS EXT E. ON SH-113/MCINTOSH/
PITTSBURG C/L EXT E. ON SH-9/US-69/SH-9A EXT E ON SH-9A
PROJ. LGTH.= 17.11 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY MC-161C(83)		
402 5205	(PL)ARMOR COAT	97,320.000	SY
SECTION NO. 0002	I000-ROADWAY MC-161C(84)		
402 5205	(PL)ARMOR COAT	139,815.000	SY
SECTION NO. 0003	I000-ROADWAY MC-161C(85)		
402 5205	(PL)ARMOR COAT	91,626.000	SY

LNTCIQA
CALL ORDER : 610
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: PUSHMATAHA

STATE PROJECT
CONTRACT ID : 010328
PCN : 1913204
PROJECTS : MC-164A(39)PT. 1
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

PAGE 46

CONTRACT DESCRIPTION:
ARMOR COAT
BEGIN 0.5 MILE EAST OF JCT. US-271/SH-3 IN ANTLERS AND
EXTEND
EAST ON SH-3
PROJ. LGTH.= 5.0 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ARMOR COAT		
402 5205	(PL)ARMOR COAT	93,870.000	SY

LNTCIQA
CALL ORDER : 620
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: PUSHMATAHA

STATE PROJECT
CONTRACT ID : 010329
PCN : 1913205
PROJECTS : MC-164A(39)PT. 2
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

PAGE 47

CONTRACT DESCRIPTION:
ARMOR COAT
BEGIN 0.5 MILE NORTH OF JCT SH-3/SH-2 WEST OF ANTLERS AND
EXTEND
NORTH ON SH-2
PROJ. LGTH.= 8.00 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
402 5205	(PL)ARMOR COAT	150,190.000	SY

LNTCIQA
CALL ORDER : 630
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: PUSHMATAHA

STATE PROJECT
CONTRACT ID : 010330
PCN : 1913206
PROJECTS : MC-164A(39)PT. 3
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

PAGE 48

CONTRACT DESCRIPTION:
ARMOR COAT
BEGIN AT THE CHOCTAW COUNTY LINE AND EXTEND NORTH
ON US-271
PROJ. LGTH.= 4.65 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ARMOR COAT		
402 5205	(PL)ARMOR COAT	92,755.000	SY

LNTCIQA
CALL ORDER : 640
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: CHOCTAW

STATE PROJECT
CONTRACT ID : 010331
PCN : 1913207
PROJECTS : MC-164A(39)PT. 4
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

PAGE 49

CONTRACT DESCRIPTION:
ARMOR COAT
BEGIN 0.3 MILE NORTH OF JCT US-70/US-271 EAST OF SOPER AND
EXTEND NORTH ON US-271
PROJ. LGTH.= 7.7 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
402 5205	(PL)ARMOR COAT	144,555.000	SY

LNTCIQA
CALL ORDER : 650
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: CHOCTAW

STATE PROJECT
CONTRACT ID : 010332
PCN : 1913208
PROJECTS : MC-164A(39)PT. 5
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

PAGE 50

CONTRACT DESCRIPTION:
ARMOR COAT
BEGIN 3.24 MILES WEST OF JCT. US-271/US-70 AND EXTEND
EAST ON US-70
PROJ. LGTH.= 2.89 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
402 5205	(PL)ARMOR COAT	54,255.000	SY

LNTCIQA
CALL ORDER : 660
LETTING DATE : July 26, 2001
LETTING TIME : 10:30 A.M.
COUNTIES: PUSHMATAHA
 CHOCTAW

STATE PROJECT
CONTRACT ID : 010333
PCN : 1913204C

PAGE 51

PROJECTS : MC-164A(39)PT. 1,2,3,4 & 5
DBE/WBE GOALS: 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE: \$ 0.00
RES. ENG.:
CAL. DAYS: LIQ. DAM: \$ 500

CONTRACT DESCRIPTION:
ARMOR COAT
BEGIN AT ANTLERS EXT. SOUTHEASTS ON SH-3/NORTH ON SH-2/SOUTH
ON US-271
AND NORTH AND WEST FROM THE JCT. US-271/US-70 IN CHOCTAW
COUNTY
PROJ. LGTH.= 28.24 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	F000-ROADWAY MC-164A(39) PT. 1		
402 5205	(PL)ARMOR COAT	93,870.000	SY
SECTION NO. 0002	F000-ROADWAY MC-164A(39) PT. 2		
402 5205	(PL)ARMOR COAT	150,190.000	SY
SECTION NO. 0003	F000-ROADWAY MC-164A(39) PT. 3		
402 5205	(PL)ARMOR COAT	92,755.000	SY
SECTION NO. 0004	F000-ROADWAY MC-164A(39) PT. 4		
402 5205	(PL)ARMOR COAT	144,555.000	SY
SECTION NO. 0005	F000-ROADWAY MC-164A(39) PT. 5		
402 5205	(PL)ARMOR COAT	54,255.000	SY

LNTCIQA
 CALL ORDER : 680
 LETTING DATE : July 26, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES: STEPHENS

STATE PROJECT
 CONTRACT ID : 010337
 PCN : 1883404
 PROJECTS : CMC-169A(50)
 DBE/WBE GOALS: 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE: \$ 0.00
 RES. ENG.:
 CAL. DAYS: 100 LIQ. DAM: \$ 500

PAGE 52

CONTRACT DESCRIPTION:
 RESURFACE(PC CONCRETE PAVING)
 BEGIN AT JCT US-81A/US-81 AND EXTEND EAST TO 10TH STREET ON
 US-81A IN DUNCAN
 PROJ. LGTH.= 0.45 MILES

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	US-81A (MAIN STREET)		
202(A) 0183	UNCLASSIFIED EXCAVATION	1,560.000	CY
414 5169	(PL)CRACK SEALING P.C.PAVEMENT	14,000.000	LF
414(B) 5070	7" H.E.S. CONCRETE (PATCHING)	1,960.000	SY
414(B) 5913	H.E.S. CONCRETE (FULL DEPTH PATCHING)	1,540.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	10,300.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	2.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	1.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	US-81		
202(A) 0183	UNCLASSIFIED EXCAVATION	150.000	CY
411(B) 4928	(PL)ASPHALT CONCRETE TYPE B(PATCHING)	40.000	TON
414(B) 5071	8" H.E.S. CONCRETE (PATCHING)	325.000	SY
506(A) 1322	STRUCTURAL STEEL	50.000	LB
509(C) 0322	CLASS A CONCRETE FOR SMALL STRUCTURES	2.000	CY
611(G) 4488	INLET FRM&GRT (SSIF-FRM,CIG-GRT-VG-F)	3.000	EA
611(K) 4488	CAST IRON CURB INLETS	6.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	500.000	LF