

DATE : August 29, 2001 OKLAHOMA DEPARTMENT OF TRANSPORTATION
NOTICE TO CONTRACTORS -- September 20, 2001

LNTCNCA
LETTING

LNTCNCA-D

SEALED PROPOSALS SENT BY REGISTERED MAIL WILL BE RECEIVED THROUGH THE ODOT REPRODUCTION BRANCH UNTIL 30 MINUTES PRIOR TO THE SCHEDULED BID OPENING. FROM 30 MINUTES PRIOR TO THE BID OPENING UNTIL THE TIME OF THE BID OPENING, BID PROPOSALS MUST BE TURNED IN DIRECTLY TO THE ODOT COMMISSION ROOM LOCATED ON THE EAST SIDE OF THE LOBBY. THE SCHEDULED BID OPENING OF 10:30 A.M. September 20, 2001, FOR THE WORK LISTED BELOW.

NO PROPOSAL FOR CONSTRUCTION OR MAINTENANCE WORK OF THE DEPARTMENT WILL BE ISSUED TO ANY CONTRACTOR AFTER 10:30 A.M. ON THE WORKING DAY PRECEDING OPENING OF BIDS FOR ANY CONTRACT.

EACH SEPARATE PROPOSAL SHALL BE ACCOMPANIED BY A CERTIFIED OR CASHIER'S CHECK OR BID BOND EQUAL TO 5% OF THE BID MADE PAYABLE TO THE STATE OF OKLAHOMA, DEPARTMENT OF TRANSPORTATION, AS A PROPOSAL GUARANTY. PROPOSAL CHECKS WILL BE HELD OR RETURNED BY THE DEPARTMENT AS PER SECTION 103.04 OF THE STATE STANDARD SPECIFICATIONS.

THIS WORK WILL BE DONE UNDER THE OKLAHOMA DEPARTMENT OF TRANSPORTATION COMMISSION'S APPLICABLE SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.

THE MINIMUM WAGE TO BE PAID LABORERS AND MECHANICS EMPLOYED ON THIS PROJECT WILL BE INCLUDED IN THE PROPOSAL.

PROPOSALS MUST BE PREPARED AS DIRECTED BY THE STATE STANDARD SPECIFICATIONS.

PLANS, FORMS OF PROPOSALS, CONTRACTS AND SPECIFICATIONS MAY BE EXAMINED AT THE DIVISION HEADQUARTERS IN THE DIVISION THE WORK IS TO BE PERFORMED OR AT THE OKLAHOMA DEPARTMENT OF TRANSPORTATION OFFICE ENGINEER'S DIVISION IN OKLAHOMA CITY, OKLAHOMA.

PLANS AND PROPOSAL FORMS MAY BE ORDERED FROM JACK STEWART, DIVISION ENGINEER, OKLAHOMA DEPARTMENT OF TRANSPORTATION BUILDING, 200 N.E. 21ST STREET, OKLAHOMA CITY, OKLAHOMA 73105. COST OF BIDDING DOCUMENTS ARE \$25.00 + tax FOR EACH BIDDING PROPOSAL. STATE STANDARD SPECIFICATION 1988 EDITION (RED BOOK) AND 1991 SUPPLEMENT MAY BE PURCHASED FOR \$8.00 + tax, OR 1996 METRIC STANDARD SPECIFICATION \$27.00 + TAX, OR 1999 METRIC AND ENGLISH STANDARD SPECIFICATION \$55.00 + TAX. (OKLAHOMA TAX IS 7.875%). MAKE CHECKS PAYABLE TO OKLAHOMA DEPARTMENT OF TRANSPORTATION.

NO REFUNDS WILL BE MADE FOR BIDDING DOCUMENTS OR SPECIFICATION BOOKS PURCHASED BY PROSPECTIVE BIDDERS.

UPON AWARD OF CONTRACT TO A SUCCESSFUL BIDDER, THE CONTRACT WILL BE COMPLETELY AND CORRECTLY EXECUTED BY THE CONTRACTOR AND RETURNED TO THE DEPARTMENT WITHIN TEN (10) WORKING DAYS FROM THE DATE OF AWARD. THE DEPARTMENT WILL HAVE FOURTEEN (14) WORKING DAYS FROM THE DATE OF AWARD TO COMPLETE ITS EXECUTION OF THE CONTRACT.

THE OKLAHOMA DEPARTMENT OF TRANSPORTATION HEREBY NOTIFIES ALL BIDDERS THAT IT WILL AFFIRMATIVELY INSURE THAT IN ANY CONTRACT ENTERED INTO PURSUANT TO THIS ADVERTISEMENT, DISADVANTAGED BUSINESS ENTERPRISES WILL BE AFFORDED FULL OPPORTUNITY TO SUBMIT BIDS IN RESPONSE TO THIS INVITATION AND WILL NOT BE DISCRIMINATED AGAINST ON THE GROUNDS OF RACE, COLOR, SEX, RELIGION, NATIONAL ORIGIN, OR DISABILITY IN CONSIDERATION FOR AN AWARD.

BIDDERS ARE HEREBY NOTIFIED THAT ALL BIDS ARE LIKELY TO BE REJECTED IF THE LOWEST RESPONSIVE BID RECEIVED EXCEEDS THE ENGINEER'S ESTIMATE BY MORE THAN SEVEN (7) PERCENT. IN THE EVENT ALL BIDS ARE REJECTED FOR THIS REASON, THIS PROJECT MAY BE DEFERRED FOR READVERTISING FOR BIDS UNTIL A MORE COMPETITIVE SITUATION EXISTS.

DESCRIPTION OF WORK AND LOCATION OF PROJECT:

CALL ORDER : 010
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES : ADAIR

CONTRACT ID : 010389
 PCN : 0947304
 PROJECTS : BRFY-001B(154)
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 35.60
 CALENDAR DAYS : 210
 RES. ENG.:
 LIQ. DAM.: \$ 800

CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES US-62 AT PEACH EATER CREEK, APPROX. 9.
 865 KM EAST OF THE CHEROKEE C/L, JUST WEST OF CHRISTIE.
 PROJ. LGTH.= 1.0792 ASPH GRADE = 64-22 PG OK FLEX ESALS = 1.
 6 MILLION

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000 - ROADWAY		
201 M0102	CLEARING AND GRUBBING	1.000	LSUM
202(A) M0183	UNCLASSIFIED EXCAVATION	25,527.000	M3
202(C) M0184	UNCLASSIFIED BORROW	51,400.000	M3
205 M4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222 M2801	TEMPORARY BALE BARRIER	200.000	M
223 M2802	TEMPORARY SILT FENCE	400.000	M
226 M2805	TEMPORARY SEDIMENT REMOVAL	500.000	M3
227 M0100	TEMPORARY SILT DIKE	200.000	M
229 M4318	DITCH LINER PROTECTION	812.000	M
230(A) M2806	SOLID SLAB SODDING	4,590.000	M2
230(B) M2807	MULCH SODDING	26,710.000	M2
232(B) M2814	SEEDING METHOD B	8.560	HA
233(A) M2817	VEGETATIVE MULCHING	20.250	HA
234(A) M2824	FERTILIZING (10-20-10)	4.350	T
241 M2832	MOWING	9.750	HA
303 M0192	AGGREGATE BASE	2,042.000	M3
403(E) M0225	TRAFFIC BOUND SURFACE COURSE TYPE E	565.000	T
407 M0250	TACK COAT	5,031.000	L
408 M5774	PRIME COAT	25,217.000	L
411(A) M6500	(SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	4,196.000	T
411(B) M6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	2,253.000	T
509(D) M0325	CLASS C CONCRETE	204.000	M3
613(B) M0405	450MM R.C.PIPE CLASS III	17.000	M
613(B) M0409	600MM R.C.PIPE CLASS III	22.000	M
613(B) M0417	1050MM R.C.PIPE CLASS III	24.000	M
613(D) M0689	450MM CORR. GALV. STEEL PIPE	25.000	M
613(D) M0690	600MM CORR. GALV. STEEL PIPE	5.000	M
613(F) M0741	600MM MILL PRECOATED COR.GALV.STL.PIPE	26.000	M
613(F) M0742	750MM MILL PRECOATED COR.GALV.STL.PIPE	56.000	M
613(M) M0898	600MM PREFAB. CULVERT END SEC., ROUND	4.000	EA
613(M) M0899	750MM PREFAB. CULVERT END SEC., ROUND	6.000	EA
613(M) M0980	1050MM PREFAB. CULVERT END SEC., ROUND	2.000	EA
613(MM)M7501	TYPE B4 SLOPED CONCRETE END SECTION	1.000	EA
613(MM)M7520	TYPE A6 SLOPED CONCRETE END SECTION	2.000	EA
613(MM)M7521	TYPE B6 SLOPED CONCRETE END SECTION	2.000	EA
613(P) M1091	150MM PERFORATED PIPE UNDERDRAIN ROUND	83.000	M

CALL ORDER : 010
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES : ADAIR

CONTRACT ID : 010389
 PCN : 0947304
 PROJECTS : BRFY-001B(154)
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 35.60
 CALENDAR DAYS : 210
 RES. ENG.:
 LIQ. DAM.: \$ 800

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000 - ROADWAY		
613(Q) M1096	150MM NON-PERF.PIPE UNDERDRAIN RND.	28.000	M
613(R) M1100	PIPE UNDERDRAIN COVER MAT'L.	21.000	M3
613(S) M1180	TRENCH EXCAVATION	91.000	M3
613(T) M1181	STANDARD BEDDING MATERIAL	26.000	M3
619(A) M0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) M4728	REMOVAL OF ASPHALT PAVEMENT	11,620.000	M2
619(B) M4780	REMOVAL OF GUARD RAIL	153.000	M
619(C) M0924	SAWING PAVEMENT	236.000	M
623(A) M0932	BEAM GUARD RAIL-W-BEAM-SINGLE	100.000	M
623(F) M5686	GUARD RAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
624(C) M4459	FENCE-STYLE SWF (5 BARBED WIRE)	1,767.000	M
629(A) M4958	MAILBOX INSTALLATION-SINGLE	5.000	EA
629(C) M4960	MAILBOX	5.000	EA
629(D) M4961	REMOVAL OF MAILBOX INSTALLATION	5.000	EA
643 M0100	(PL)NESHAP PREDEM. INSP. & NOTIFICATION	3.000	EA
SECTION NO. 0002	Y008-TRAFFIC CONTROL		
880(J) M8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003	Y002-SIGNING & STRIPING		
850(A) M8110	SHEET ALUMINUM SIGNS	0.480	M2
851(C) M8327	57MM SQUARE TUBE POST	4.110	M
855(A) M8812	TRAFFIC STRIPE(PLASTIC)(100MM WIDE)	4,902.000	M
SECTION NO. 0004	STAK-STAKING		
642 M0098	STAKING	1.000	LSUM
SECTION NO. 0005	X081-BRIDGE-PCB SPANS		
202(A) M1301	UNCLASSIFIED EXCAVATION	290.000	M3
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	620.000	M3
501(C) M1308	SUBSTRUCTURE EXCAVATION ROCK	29.400	M3
501(G) M6309	CLSM BACKFILL	109.400	M3
503(A) M1312	PRESTRESSED CONCRETE BEAMS (TYPE III)	190.800	M
504(A) M1304	APPROACH SLAB	253.200	M2
504(C) M6250	SEALED EXPANSION JOINT	25.620	M
504(E) M6239	CONCRETE RAIL (TR3)	137.200	M
506(A) M1322	STRUCTURAL STEEL	2,460.000	KG
509(A) M1326	CLASS AA CONCRETE	141.200	M3
509(B) M1328	CLASS A CONCRETE	182.100	M3

CALL ORDER : 010
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES : ADAIR

CONTRACT ID : 010389
 PCN : 0947304
 PROJECTS : BRFY-001B(154)
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 35.60
 CALENDAR DAYS : 210
 RES. ENG.:
 LIQ. DAM.: \$ 800

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0005	X081-BRIDGE-PCB SPANS		
509(D) M1331	CLASS C CONCRETE	1.500	M3
511(A) M1332	REINFORCING STEEL	18,995.000	KG
511(B) M6010	EPOXY COATED REINFORCING STEEL	20,135.000	KG
515(A) M6013	WATER REPELLENT (VISUALLY INSPECTED)	666.000	M2
516(A) M6089	DRILLED SHAFTS 450MM DIAMETER	22.400	M
601B-1 M1359	TYPE II-A SP. PLAIN RIPRAP	2,480.000	T
601B-2 M1361	TYPE II-A FILTER BLANKET	400.000	T
609(D) M0398	BITUMINOUS CURBING	55.000	M
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	25.600	M
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	26.000	M
619(D) M1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(H) M8571	(SP)G.E.T. GUARD RAIL END SECTION	4.000	EA
640 M1398	FIELD OFFICE	1.000	EA
641 1399	MOBILIZATION	1.000	LSUM
643 M0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
SECTION NO. 0006	X071-BRIDGE - STEEL SPANS		
202(A) M1301	UNCLASSIFIED EXCAVATION	290.000	M3
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	620.000	M3
501(C) M1308	SUBSTRUCTURE EXCAVATION ROCK	29.400	M3
501(G) M6309	CLSM BACKFILL	91.200	M3
504(A) M1304	APPROACH SLAB	253.200	M2
504(C) M6250	SEALED EXPANSION JOINT	25.620	M
504(E) M6239	CONCRETE RAIL (TR3)	137.200	M
506(A) M1322	STRUCTURAL STEEL	42,965.000	KG
509(A) M1326	CLASS AA CONCRETE	125.600	M3
509(B) M1328	CLASS A CONCRETE	178.800	M3
509(D) M1331	CLASS C CONCRETE	1.500	M3
511(A) M1332	REINFORCING STEEL	17,715.000	KG
511(B) M6010	EPOXY COATED REINFORCING STEEL	19,875.000	KG
515(A) M6013	WATER REPELLENT (VISUALLY INSPECTED)	487.000	M2
516(A) M6089	DRILLED SHAFTS 450MM DIAMETER	22.400	M
601B-1 M1359	TYPE II-A SP. PLAIN RIPRAP	2,480.000	T
601B-2 M1361	TYPE II-A FILTER BLANKET	400.000	T
609(D) M0398	BITUMINOUS CURBING	55.000	M
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	25.600	M
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	26.000	M
619(D) M1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(H) M8571	(SP)G.E.T. GUARD RAIL END SECTION	4.000	EA
640 M1398	FIELD OFFICE	1.000	EA
641 M1399	MOBILIZATION	1.000	LSUM
643 M0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM

CALL ORDER : 020
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES : ATOKA

CONTRACT ID : 010390
 PCN : 1735604
 PROJECTS : BR0-103D(20) CO
 DBE GOALS : 10.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 3.24
 CALENDAR DAYS : 110
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
 BRIDGE AND APPROACHES COUNTY BRIDGE OVER FIVE MILE CREEK,
 APPROX. 0.322 KM NORTH AND 5.633 KM EAST OF WARDVILLE. PROJ.
 LGTH.= 0.299 KM

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000-ROADWAY			
201 M0102	CLEARING AND GRUBBING	1.000	LSUM
202(G) M0185	EARTHWORK	1.000	LSUM
205 M4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222 M2801	TEMPORARY BALE BARRIER	550.000	M
223 M2802	TEMPORARY SILT FENCE	600.000	M
230(A) M2806	SOLID SLAB SODDING	2,426.000	M2
233(A) M2817	VEGETATIVE MULCHING	0.490	HA
403(E) M0225	TRAFFIC BOUND SURFACE COURSE TYPE E	467.000	T
509(D) M0325	CLASS C CONCRETE	10.000	M3
613(D) M5214	680MM X 500MM CORR. GALV. ST. PIPE ARCH	27.400	M
613(G) M7036	680MM X 500MM GALV.STL.CULV.END SEC.ARCH	4.000	EA
SECTION NO. 0002 X081-BRIDGE "A"			
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	102.000	M3
501(D) M6353	UNCLASSIFIED BACKFILL	48.000	M3
503(A) M1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	103.000	M
504(E) M1380	CONCRETE RAIL (TR1)	72.700	M
506(A) M1322	STRUCTURAL STEEL	670.000	KG
509(A) M1326	CLASS AA CONCRETE	47.700	M3
509(B) M1328	CLASS A CONCRETE	45.000	M3
511(A) M1332	REINFORCING STEEL	10,098.000	KG
514(A) M6011	PILES, FURNISHED (HP 250X62)	218.600	M
514(B) M6292	PILES, DRIVEN (HP 250X62)	218.600	M
601A-1 M1353	TYPE I-A PLAIN RIPRAP	590.000	T
601A-2 M1355	TYPE I-A FILTER BLANKET	130.000	T
619(D) M1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(A) M0932	BEAM GUARD RAIL-W-BEAM-SINGLE	8.740	M
623(F) M5686	GUARD RAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
623(F) M6029	GUARD RAIL ANCHOR UNIT (TYPE A)	4.000	EA
641 M1399	MOBILIZATION	1.000	LSUM
880(J) M8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING			
642 M0098	STAKING	1.000	LSUM

CALL ORDER : 030
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES : BECKHAM

CONTRACT ID : 010391
 PCN : 1662804
 PROJECTS : BR0-105D(18)C0
 DBE GOALS : 8.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 3.24
 CALENDAR DAYS : 110
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES COUNTY BRIDGE OVER TURKEY CREEK,
 APPROX. 6.0 MILE EAST AND 1.0 MI NORTH OF ERICK. PROJ.
 LGTH= 0.175 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000-ROADWAY			
202(G) 0185	EARTHWORK	1.000	LSUM
222 2801	TEMPORARY BALE BARRIER	300.000	LF
223 2801	TEMPORARY SILT FENCE	500.000	LF
230(A) 2806	SOLID SLAB SODDING	6,400.000	SY
233(A) 2817	VEGETATIVE MULCHING	1.320	AC
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	416.000	TON
509(D) 0325	CLASS C CONCRETE	20.000	CY
613(CC) 7187	TYPE B4 CULVERT END TREATMENT	2.000	EA
613(D) 0690	24" CORR. GALV. STEEL PIPE	46.000	LF
SECTION NO. 0002 X081-BRIDGE			
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	96.000	CY
501(D) 6353	UNCLASSIFIED BACKFILL	114.000	CY
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	396.170	LF
504(E) 1380	CONCRETE RAIL (TR1)	273.160	LF
506(A) 1322	STRUCTURAL STEEL	2,020.000	LB
509(A) 1326	CLASS AA CONCRETE	80.200	CY
509(B) 1328	CLASS A CONCRETE	63.800	CY
511(A) 1332	REINFORCING STEEL	26,818.000	LB
514 6260	(PL)PILOT HOLES	91.000	LF
514(A) 6011	PILES, FURNISHED (HP 12X53)	475.000	LF
514(B) 6294	PILES, DRIVEN (HP 12X53)	475.000	LF
601(A-1)1353	TYPE I-A PLAIN RIPRAP	500.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	140.000	TON
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F) 6034	GUARD RAIL ANCHOR UNIT (TYPE III)	4.000	EA
641 1399	MOBILIZATION	1.000	LSUM
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING			
642 0098	STAKING	1.000	LSUM

CALL ORDER : 050
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES : BRYAN

CONTRACT ID : 010392
 PCN : 1799404
 PROJECTS : BR0-107D(32) CO
 DBE GOALS : 7.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 3.78
 CALENDAR DAYS : 80
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES COUNTY BRIDGE OVER NEWBERRY CREEK, 1.
 4 MILE NORTH AND 7.5 MILE WEST OF DURANT. PROJ. LGTH.= 0.
 170 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000-ROADWAY			
201 0102	CLEARING AND GRUBBING	1.000	LSUM
202(G) 0185	EARTHWORK	1.000	LSUM
205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
227 0100	TEMPORARY SILT DIKE	2,129.000	LF
230(A) 2806	SOLID SLAB SODDING	2,206.000	SY
233(A) 2817	VEGETATIVE MULCHING	1.100	AC
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	493.000	TON
509(D) 0325	CLASS C CONCRETE	62.000	CY
613(D) 4528	28" X 20" CORR. GALV. STEEL PIPE ARCH	66.000	LF
613(G) 4571	28" X 20" GALV. STEEL CULV. END SEC.ARCH	4.000	EA
SECTION NO. 0002 X031-BRIDGE "A"			
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	96.000	CY
501(D) 6353	UNCLASSIFIED BACKFILL	128.000	CY
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	416.170	LF
504(E) 1380	CONCRETE RAIL (TR1)	283.200	LF
506(A) 1322	STRUCTURAL STEEL	2,020.000	LB
509(A) 1326	CLASS AA CONCRETE	84.100	CY
509(B) 1328	CLASS A CONCRETE	66.000	CY
511(A) 1332	REINFORCING STEEL	26,960.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	104.000	LF
514(A) 6011	PILES, FURNISHED (HP 12X53)	315.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	104.000	LF
514(B) 6294	PILES, DRIVEN (HP 12X53)	315.000	LF
601(A-1)1353	TYPE I-A PLAIN RIPRAP	510.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	140.000	TON
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641 1399	MOBILIZATION	1.000	LSUM
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING			
642 0098	STAKING	1.000	LSUM

CALL ORDER : 051
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES : BRYAN

CONTRACT ID : 010412
 PCN : 1799504
 PROJECTS : BR0-107D(033)CO
 DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 4.32
 CALENDAR DAYS : 80
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES COUNTY BRIDGE OVER ROCK CREEK, 0.6
 MILE SOUTH AND 5.5 MILE WEST OF DURANT. PROJ. LGTH.=0.141
 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000-ROADWAY			
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(G)	0185 EARTHWORK	1.000	LSUM
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
227	0100 TEMPORARY SILT DIKE	1,692.000	LF
230(A)	2806 SOLID SLAB SODDING	1,617.000	SY
233(A)	2817 VEGETATIVE MULCHING	0.800	AC
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	473.000	TON
509(D)	0325 CLASS C CONCRETE	49.000	CY
613(D)	4528 28" X 20" CORR. GALV. STEEL PIPE ARCH	160.000	LF
613(G)	4571 28" X 20" GALV. STEEL CULV. END SEC.ARCH	6.000	EA
850(A)	8110 SHEET ALUMINUM SIGNS	35.360	SF
851(D)	8597 FLANGE CHANNEL POSTS(4 LB/FT)	79.000	LF
SECTION NO. 0002 X031-BRIDGE "A"			
501(B)	1307 SUBSTRUCTURE EXCAVATION COMMON	78.000	CY
501(D)	6353 UNCLASSIFIED BACKFILL	64.000	CY
503(A)	1312 PRESTRESSED CONCRETE BEAMS (TYPE III)	296.670	LF
504(E)	1380 CONCRETE RAIL (TR1)	207.000	LF
506(A)	1322 STRUCTURAL STEEL	1,620.000	LB
509(A)	1326 CLASS AA CONCRETE	58.300	CY
509(B)	1328 CLASS A CONCRETE	48.800	CY
511(A)	1332 REINFORCING STEEL	20,090.000	LB
514(A)	6010 PILES, FURNISHED (HP 10X42)	82.000	LF
514(A)	6011 PILES, FURNISHED (HP 12X53)	185.000	LF
514(B)	6292 PILES, DRIVEN (HP 10X42)	82.000	LF
514(B)	6294 PILES, DRIVEN (HP 12X53)	185.000	LF
601(A-1)	1353 TYPE I-A PLAIN RIPRAP	775.000	TON
601(A-2)	1355 TYPE I-A FILTER BLANKET	205.000	TON
619(D)	1397 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F)	5686 GUARD RAIL ANCHOR UNIT (TYPE D-BF)	1.000	EA
623(F)	6030 GUARD RAIL ANCHOR UNIT (TYPE B)	1.000	EA
623(F)	6033 GUARD RAIL ANCHOR UNIT (TYPE II)	2.000	EA
623(F)	6034 GUARD RAIL ANCHOR UNIT (TYPE III)	1.000	EA
641	1399 MOBILIZATION	1.000	LSUM
880(J)	8905 CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0003 STAK-STAKING			

CALL ORDER : 051
LETTING DATE : September 20, 2001
LETTING TIME : 10:30 A.M.
COUNTIES : BRYAN

CONTRACT ID : 010412
PCN : 1799504
PROJECTS : BR0-107D(033)C0
DBE GOALS : 6.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : 4.32
CALENDAR DAYS : 80
RES. ENG.:
LIQ. DAM.: \$ 500

642 0098 STAKING

1.000 LSUM

CALL ORDER : 052
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES : BRYAN

CONTRACT ID : 010413
 PCN : 1799404C
 PROJECTS : BR0-107D(32)C0/BR0-107D(33)C0
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 8.10
 CALENDAR DAYS : 150
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE AND APPROACHES CO. BR. OVER NEWBERRY CREEK, 1.4 MI N
 & 7.5 MI W OF DURANT & CO. BR. OVER ROCK CREEK, 0.6 MI S. &
 5.5 MI. W OF DURANT. PROJ. LGTH.= 0.311 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 E000-ROADWAY BR0-107D(32)C0			
201 0102	CLEARING AND GRUBBING	1.000	LSUM
202(G) 0185	EARTHWORK	1.000	LSUM
205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
227 0100	TEMPORARY SILT DIKE	2,129.000	LF
230(A) 2806	SOLID SLAB SODDING	2,206.000	SY
233(A) 2817	VEGETATIVE MULCHING	1.100	AC
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	493.000	TON
509(D) 0325	CLASS C CONCRETE	62.000	CY
613(D) 4528	28" X 20" CORR. GALV. STEEL PIPE ARCH	66.000	LF
613(G) 4571	28" X 20" GALV. STEEL CULV. END SEC.ARCH	4.000	EA
SECTION NO. 0002 E000-ROADWAY BR0-107D(33)C0			
201 0102	CLEARING AND GRUBBING	1.000	LSUM
202(G) 0185	EARTHWORK	1.000	LSUM
205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
227 0100	TEMPORARY SILT DIKE	1,692.000	LF
230(A) 2806	SOLID SLAB SODDING	1,617.000	SY
233(A) 2817	VEGETATIVE MULCHING	0.800	AC
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	473.000	TON
509(D) 0325	CLASS C CONCRETE	49.000	CY
613(D) 4528	28" X 20" CORR. GALV. STEEL PIPE ARCH	160.000	LF
613(G) 4571	28" X 20" GALV. STEEL CULV. END SEC.ARCH	6.000	EA
850(A) 8110	SHEET ALUMINUM SIGNS	35.360	SF
851(D) 8597	FLANGE CHANNEL POSTS(4 LB/FT)	79.000	LF
SECTION NO. 0003 X031-BRIDGE "A" BR0-107D(32)C0			
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	96.000	CY
501(D) 6353	UNCLASSIFIED BACKFILL	128.000	CY
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	416.170	LF
504(E) 1380	CONCRETE RAIL (TR1)	283.200	LF
506(A) 1322	STRUCTURAL STEEL	2,020.000	LB
509(A) 1326	CLASS AA CONCRETE	84.100	CY
509(B) 1328	CLASS A CONCRETE	66.000	CY
511(A) 1332	REINFORCING STEEL	26,960.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	104.000	LF

CALL ORDER : 052
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES : BRYAN

CONTRACT ID : 010413
 PCN : 1799404C
 PROJECTS : BR0-107D(32)C0/BR0-107D(33)C0
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 8.10
 CALENDAR DAYS : 150
 RES. ENG.:
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	X031-BRIDGE "A" BR0-107D(32)C0		
514(A) 6011	PILES, FURNISHED (HP 12X53)	315.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	104.000	LF
514(B) 6294	PILES, DRIVEN (HP 12X53)	315.000	LF
601(A-1)1353	TYPE I-A PLAIN RIPRAP	510.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	140.000	TON
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
641 1399	MOBILIZATION	1.000	LSUM
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0004	X031-BRIDGE "A" BR0-107D(33)C0		
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	78.000	CY
501(D) 6353	UNCLASSIFIED BACKFILL	64.000	CY
503(A) 1312	PRESTRESSED CONCRETE BEAMS (TYPE III)	296.670	LF
504(E) 1380	CONCRETE RAIL (TR1)	207.000	LF
506(A) 1322	STRUCTURAL STEEL	1,620.000	LB
509(A) 1326	CLASS AA CONCRETE	58.300	CY
509(B) 1328	CLASS A CONCRETE	48.800	CY
511(A) 1332	REINFORCING STEEL	20,090.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	82.000	LF
514(A) 6011	PILES, FURNISHED (HP 12X53)	185.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	82.000	LF
514(B) 6294	PILES, DRIVEN (HP 12X53)	185.000	LF
601(A-1)1353	TYPE I-A PLAIN RIPRAP	775.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	205.000	TON
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F) 5686	GUARD RAIL ANCHOR UNIT (TYPE D-BF)	1.000	EA
623(F) 6030	GUARD RAIL ANCHOR UNIT (TYPE B)	1.000	EA
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	2.000	EA
623(F) 6034	GUARD RAIL ANCHOR UNIT (TYPE III)	1.000	EA
641 1399	MOBILIZATION	1.000	LSUM
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0005	STAK-STAKING BR0-107D(32)C0		
642 0098	STAKING	1.000	LSUM
SECTION NO. 0006	STAK-STAKING BR0-107D(33)C0		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 063
LETTING DATE : September 20, 2001
LETTING TIME : 10:30 A.M.

CONTRACT ID : 010292
PCN : 1849404
PROJECTS : SAP-112D(32)
CALENDAR DAYS : 45
RES. ENG.:
LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

RESURFACE(ASPHALT) LAKE ACCESS FOR HUGO LAKE: BEGIN APPROX.
1.0 MILE NORTH OF US-70 ON NS-428.5, EXTEND NORTH. PROJ.
LGTH.= 3.02 MILE FLEX ESALS = 0.6 MILLION ASPH GRADE =
64-22 PG OK

ITEM NO.		DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001		I000-ROADWAY		
303	0192	AGGREGATE BASE	395.000	CY
408	5774	PRIME COAT	2,949.000	GAL
411(B)	6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	3,920.000	TON
619(B)	4728	REMOVAL OF ASPHALT PAVEMENT	2,027.000	SY
641	1552	MOBILIZATION	1.000	LSUM
880(J)	8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

CALL ORDER : 090
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 010411
 PCN : 1695814
 PROJECTS : CIP-126D(41)IP
 CALENDAR DAYS : 210
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

GRADE, DRAIN & SURFACE(ASPHALT) MUSTANG ROAD BEGINNING AT
 THE JCT. OF ROCK CREEK, EXTEND NORTH TO SH-37. PROJ. LGTH.=
 0.993 ASPH GRADE = 64-22 & 70-28 PG OK FLEX ESALS = 3.5
 MILLION

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	I000-ROADWAY		
201	0102 CLEARING AND GRUBBING	1.000	LSUM
202(A)	0183 UNCLASSIFIED EXCAVATION	44,576.000	CY
202(C)	0184 UNCLASSIFIED BORROW	2,722.000	CY
205	4229 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222	2801 TEMPORARY BALE BARRIER	350.000	LF
223	2801 TEMPORARY SILT FENCE	2,500.000	LF
224	2803 TEMPORARY SEDIMENT FILTER	30.000	EA
225	2804 TEMPORARY SEDIMENT BASIN	2.000	EA
227	0100 TEMPORARY SILT DIKE	2,000.000	LF
229	4318 DITCH LINER PROTECTION	675.000	LF
230(A)	2806 SOLID SLAB SODDING	22,389.000	SY
230(B)	2807 MULCH SODDING	18,945.000	SY
230(F)	2812 WATERING	3,289.000	MGAL
233(A)	2817 VEGETATIVE MULCHING	11.900	AC
241	2832 MOWING	16.000	AC
317(A)	4252 (SP)FLY ASH	2,545.000	TON
317(B)	4254 SUBGRADE MODIFICATION	39,283.000	SY
403(E)	0225 TRAFFIC BOUND SURFACE COURSE TYPE E	201.000	TON
407	0250 TACK COAT	4,134.000	GAL
408	5774 PRIME COAT	6,431.000	GAL
411(A)	6500 (SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	2,181.000	TON
411(A)	6510 (SP)ASPHALT CONCRETE TYPE A(PG 70-28 OK)	9,251.000	TON
411(B)	6530 (SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	1,076.000	TON
411(B)	6540 (SP)ASPHALT CONCRETE TYPE B(PG 70-28 OK)	3,712.000	TON
501(A)	0313 STRUCTURAL EXCAVATION UNCLASSIFIED	153.000	CY
509(B)	0321 CLASS A CONCRETE	341.000	CY
509(D)	0325 CLASS C CONCRETE	188.000	CY
511(A)	0332 REINFORCING STEEL	47,754.000	LB
601(A-1)	0536 TYPE I-A PLAIN RIPRAP	119.000	TON
601(A-2)	0538 TYPE I-A FILTER BLANKET	48.000	TON
609(B)	1526 2'-8" COMB.CRB.& GUT.(8" BARRIER)	8,075.000	LF
610(B)	0399 6" CONCRETE DRIVEWAY (H.E.S.)	297.000	SY
611(A)	2657 MANHOLE (4' DIA.)	5.000	EA
611(D)	4215 MANHOLE FRAME & COVER	5.000	EA
611(E)	5112 INLET CICI DES. 2 (STD)	30.000	EA
611(F)	5325 INLET CICI DES. 2 (ADD'L DEPTH)	21.000	VF
611(G)	1391 INLET FRAME AND GRATE	60.000	EA
611(K)	4488 CAST IRON CURB INLETS	60.000	EA
613(B)	0403 15" R.C.P.IPE CLASS III	974.000	LF

CALL ORDER : 090
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.

CONTRACT ID : 010411
 PCN : 1695814
 PROJECTS : CIP-126D(41)IP
 CALENDAR DAYS : 210
 RES. ENG.:
 LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	I000-ROADWAY		
613(B) 0491	18" R.C.PIPE CLASS III	1,919.000	LF
613(B) 0492	24" R.C.PIPE CLASS III	991.000	LF
613(D) 0689	18" CORR. GALV. STEEL PIPE	40.000	LF
613(D) 0690	24" CORR. GALV. STEEL PIPE	98.000	LF
613(M) 5726	18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
613(M) 5730	24" PREFAB. CULVERT END SEC., ROUND	6.000	EA
613(P) 1091	6" PERFORATED PIPE UNDERDRAIN ROUND	300.000	LF
613(Q) 1096	6" NON-PERF.PIPE UNDERDRAIN RND.	300.000	LF
613(Q) 1099	12" NON-PERF.PIPE UNDERDRAIN RND.	48.000	LF
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 4726	REMOVAL OF CURB AND GUTTER	200.000	LF
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	15,955.000	SY
619(B) 5918	REMOVAL OF EXISTING PIPE	680.000	LF
624(A) 4281	FENCE-STYLE WWF	618.000	LF
624(B) 4462	GATES-STYLE WWF (4.5'HIGH X 12'LONG)	2.000	EA
624(B) 4466	GATES-STYLE WWF (4.5'HIGH X 16'LONG)	2.000	EA
624(C) 4459	FENCE-STYLE SWF (5 BARBED WIRE)	2,840.000	LF
624(D) 4288	FENCE-STYLE CLF (4'HIGH, CLASS A)	214.000	LF
624(E) 5845	GATES-STYLE CLF (4'HIGH X 10'LONG)	2.000	EA
624(E) 5847	GATES-STYLE CLF (4'HIGH X 12'LONG)	2.000	EA
629(A) 4958	MAILBOX INSTALLATION-SINGLE	10.000	EA
629(B) 4959	MAILBOX INSTALLATION-MULTIPLE	3.000	EA
629(C) 4960	MAILBOX	19.000	EA
640 1398	FIELD OFFICE	1.000	EA
641 1399	MOBILIZATION	1.000	LSUM
643 0100	(PL)NESHAP PREDEM. INSP. & NOTIFICATION	1.000	EA
SECTION NO. 0002	Y008-TRAFFIC ITEMS		
627(E) 4314	PRECAST CONC. MEDIAN BARRIER, PORT. TYPE	260.000	LF
802(B) 8338	1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCH	310.000	LF
803 8065	PULL BOX(SIZE I)	1.000	EA
803 8067	PULL BOX(SIZE III)	1.000	EA
828(B) 8138	LOOP DETECTOR WIRE	650.000	LF
834(B) 8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	300.000	LF
850(A) 8110	SHEET ALUMINUM SIGNS	181.000	SF
851(C) 8327	2 1/4" SQUARE TUBE POST	311.000	LF
855(A) 3320	TRAFFIC STRIPE(THERMOPLASTIC)(4" WIDE)	21,010.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	30.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	1.000	EA
856(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	20,840.000	LF
856(C) 8851	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	900.000	LF
856(G) 8881	(PL)CONSTRUCTION ZONE PAVEMENT MARKERS	500.000	EA
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAFF.STRP)	1,000.000	LF
870(A) 8011	SAND FILLED IMPACT ATTEN.MODULE	30.000	EA
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	11,000.000	SD

CALL ORDER : 090
LETTING DATE : September 20, 2001
LETTING TIME : 10:30 A.M.

CONTRACT ID : 010411
PCN : 1695814
PROJECTS : CIP-126D(41)IP
CALENDAR DAYS : 210
RES. ENG.:
LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	Y008-TRAFFIC ITEMS		
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,750.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,500.000	SD
880(C) 8842	BARRICADES(TYPE III)	3,000.000	SD
880(C) 8845	BARRICADES(TYPE III)	3.000	EA
880(C) 8848	WING BARRICADES	1,000.000	SD
880(D) 8854	VERTICAL PANELS	19,000.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	11,500.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	46,000.000	SD
880(F) 8878	DRUMS	39,500.000	SD
890A/B 8742	(PL)REMOVE & RESET TRAF.SIG.EQUIPMENT	1.000	LSUM
SECTION NO. 0003	STAK-STAKING		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 130
LETTING DATE : September 20, 2001
LETTING TIME : 10:30 A.M.
COUNTIES : KIOWA

CONTRACT ID : 010398
PCN : 1606338
PROJECTS : NHY-009N(72)RW
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : 0.00
CALENDAR DAYS : 30
RES. ENG.:
LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
RIGHT-OF-WAY CLEARANCE US-183 FROM EW-141 NORTH TO EW-137
PROJ. LGTH.= 6.1 KM

ITEM NO.		DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001		ROWA-RIGHT-OF-WAY CLEARANCE		
643	M0094	(PL)RIGHT-OF-WAY CLEARANCE	1.000	LSUM
643	M0100	(PL)NESHAP PREDEM. INSP. & NOTIFICATION	4.000	EA

CALL ORDER : 140
LETTING DATE : September 20, 2001
LETTING TIME : 10:30 A.M.
COUNTIES : KIOWA

CONTRACT ID : 010399
PCN : 1606339
PROJECTS : NHY-009N(73)RW
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : 0.00
CALENDAR DAYS : 30
RES. ENG.:
LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:
RIGHT-OF-WAY CLEARANCE FROM SH-9/US-183 JCT. NORTH ALONG
US-183 PROJ. LGTH.= 3.516 MILES

ITEM NO.		DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001		ROWA-RIGHT-OF-WAY CLEARANCE		
643	0094	(PL)RIGHT-OF-WAY CLEARANCE	1.000	LSUM
643	0100	(PL)NESHAP PREDEM. INSP. & NOTIFICATION	1.000	EA

CALL ORDER : 150
LETTING DATE : September 20, 2001
LETTING TIME : 10:30 A.M.
COUNTIES : KIOWA WASHITA

CONTRACT ID : 010400
PCN : 1606340
PROJECTS : NHY-009N(74)RW
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : 0.00
CALENDAR DAYS : 30
RES. ENG.:
LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

RIGHT-OF-WAY CLEARANCE FROM APPROX. 6.0 MILE SOUTH OF ROCKY,
EXTEND NORTH ALONG US-183 PROJ. LGTH.=5.495 MILES

ITEM NO.		DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001		ROWA-RIGHT-OF-WAY CLEARANCE		
643	0094	(PL)RIGHT-OF-WAY CLEARANCE	1.000	LSUM
643	0100	(PL)NESHAP PREDEM. INSP. & NOTIFICATION	1.000	EA

CALL ORDER : 160
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES : LEFLORE

CONTRACT ID : 010401
 PCN : 1169408
 PROJECTS : STPY-140A(01)
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 56.10
 CALENDAR DAYS : 350
 RES. ENG.:
 LIQ. DAM.: \$ 2000

CONTRACT DESCRIPTION:

GRADE, DRAIN, BRIDGES & SURFACE(SUPERPAVE) SOUTH EDGE OF
 POTEAU ON US-59/US-271 SOUTH INTERCHANGE OF THE POTEAU
 BYPASS. PROJ. LGTH.= 1.770 KM ASPH GRADE = 64-22 PG OK FLEX
 ESALS = 0.00

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	J000-ROADWAY		
201 M0102	CLEARING AND GRUBBING	1.000	LSUM
202(A) M0183	UNCLASSIFIED EXCAVATION	96,332.000	M3
202(C) M0184	UNCLASSIFIED BORROW	358,113.000	M3
205 M4230	TYPE A-SALVAGED TOPSOIL	19,647.000	M3
221 M2800	TEMPORARY SLOPE DRAINS	100.000	M
222 M2801	TEMPORARY BALE BARRIER	800.000	M
223 M2802	TEMPORARY SILT FENCE	800.000	M
224 M2803	TEMPORARY SEDIMENT FILTER	20.000	EA
227 M0100	TEMPORARY SILT DIKE	1,600.000	M
229 M4318	DITCH LINER PROTECTION	3,413.000	M
230(A) M2806	SOLID SLAB SODDING	139,406.000	M2
230(F) M2812	WATERING	25,093.000	KL
233(A) M2817	VEGETATIVE MULCHING	13.740	HA
234(A) M2824	FERTILIZING (10-20-10)	1.520	T
317(A) M4252	(SP)FLY ASH	6,757.000	T
317(B) M4254	SUBGRADE MODIFICATION	116,279.000	M2
317(C) M4253	LIME	3,572.000	T
317(D) M4254	SCARIFY,MIX BLADE OF SUBGRADE W/LIME TRT	29,070.000	M2
403(E) M0225	TRAFFIC BOUND SURFACE COURSE TYPE E	100.000	T
407 M0250	TACK COAT	6,550.000	L
408 M5774	PRIME COAT	93,235.000	L
411(S3)M5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	21,780.000	T
411(S4)M5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	1,540.000	T
414(A) M0262	250MM P.C. CONCRETE PAVEMENT	23,474.000	M2
414(A1)M5755	250MM P.C. DOWEL JOINTED CONCRETE PAV	67,240.000	M2
501(A) M0313	STRUCTURAL EXCAVATION UNCLASSIFIED	221.000	M3
509(B) M1328	CLASS A CONCRETE	659.000	M3
509(D) M0325	CLASS C CONCRETE	1,361.000	M3
511(A) M0332	REINFORCING STEEL	71,241.000	KG
610(B) M0399	150MM CONCRETE DRIVEWAY (H.E.S.)	453.000	M2
610(C) M0609	150MM CONCRETE DIVIDING STRIP	5,727.000	M2
610(G) M4475	BITUMINOUS DRIVEWAY (150MM)	2,389.000	M2
611(E) M6002	INLET (SMD-TYPE 2)	5.000	EA
611(E) M6004	INLET (SMD-TYPE 2A)	1.000	EA
613(B) M0405	450MM R.C.PIPE CLASS III	42.000	M
613(B) M0409	600MM R.C.PIPE CLASS III	137.000	M

CALL ORDER : 160
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES : LEFLORE

CONTRACT ID : 010401
 PCN : 1169408
 PROJECTS : STPY-140A(01)
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 56.10
 CALENDAR DAYS : 350
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	J000-ROADWAY		
613(B) M0413	750MM R.C.PIPES CLASS III	15.000	M
613(B) M0415	900MM R.C.PIPES CLASS III	45.000	M
613(B) M0419	1200MM R.C.PIPES CLASS III	196.000	M
613(B) M0421	1350MM R.C.PIPES CLASS III	87.000	M
613(B) M0512	1350MM R.C.PIPES CLASS IV	77.000	M
613(CC)M7186	TYPE A4 CULVERT END TREATMENT	22.000	EA
613(CC)M7187	TYPE B4 CULVERT END TREATMENT	8.000	EA
613(CC)M7189	TYPE D4 CULVERT END TREATMENT	2.000	EA
613(CC)M7194	TYPE DD4 CULVERT END TREATMENT	2.000	EA
613(D) M0689	450MM CORR. GALV. STEEL PIPE	145.000	M
613(D) M0690	600MM CORR. GALV. STEEL PIPE	25.000	M
613(D) M5226	1030MM X 740MM CORR. GALV. ST. PIPE ARCH	27.000	M
613(M) M0897	450MM PREFAB. CULVERT END SEC., ROUND	4.000	EA
613(M) M0898	600MM PREFAB. CULVERT END SEC., ROUND	4.000	EA
613(M) M0899	750MM PREFAB. CULVERT END SEC., ROUND	1.000	EA
613(M) M0900	900MM PREFAB. CULVERT END SEC., ROUND	2.000	EA
613(M) M0981	1200MM PREFAB. CULVERT END SEC., ROUND	1.000	EA
613(M) M0982	1350MM PREFAB. CULVERT END SEC., ROUND	4.000	EA
613(P) M1091	150MM PERFORATED PIPE UNDERDRAIN ROUND	100.000	M
613(Q) M1096	150MM NON-PERF. PIPE UNDERDRAIN RND.	300.000	M
613(R) M1100	PIPE UNDERDRAIN COVER MAT'L.	54.000	M3
613(S) M1180	TRENCH EXCAVATION	5,361.000	M3
613(T) M1181	STANDARD BEDDING MATERIAL	661.000	M3
619(A) M0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) M0291	REMOVAL OF HEADWALL	3.000	EA
619(B) M4726	REMOVAL OF CURB AND GUTTER	625.000	M
619(B) M4727	REMOVAL OF CONCRETE PAVEMENT	461.000	M2
619(B) M4728	REMOVAL OF ASPHALT PAVEMENT	39,288.000	M2
619(C) M0924	SAWING PAVEMENT	73.000	M
623(A) M0932	BEAM GUARD RAIL-W-BEAM-SINGLE	210.000	M
623(F) M4447	GUARD RAIL ANCHOR UNIT (TYPE B)	6.000	EA
623(F) M4453	GUARD RAIL ANCHOR UNIT (TYPE GE)	4.000	EA
623(F) M5686	GUARD RAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
623(H) M8571	(SP)G.E.T. GUARD RAIL END SECTION	6.000	EA
624(A) M4281	FENCE-STYLE WWF	1,576.000	M
624(D) M4288	FENCE-STYLE CLF (1200MM HIGH, CLASS A)	60.000	M
640 M1426	FIELD OFFICE	1.000	EA
641 M1552	MOBILIZATION	1.000	LSUM
643 M0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM
SECTION NO. 0002	X281-BRIDGE H		
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	280.000	M3

CALL ORDER : 160
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES : LEFLORE

CONTRACT ID : 010401
 PCN : 1169408
 PROJECTS : STPY-140A(01)
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 56.10
 CALENDAR DAYS : 350
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	X281-BRIDGE H		
501(G) M6309	CLSM BACKFILL	250.000	M3
503(A) M1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	621.600	M
504(A) M1304	APPROACH SLAB	420.000	M2
504(C) M6250	SEALED EXPANSION JOINT	20.900	M
504(F) M1381	CONCRETE PARAPET	263.200	M
506(A) M1322	STRUCTURAL STEEL	3,290.000	KG
509(A) M1326	CLASS AA CONCRETE	412.500	M3
509(B) M1328	CLASS A CONCRETE	469.800	M3
510(C) M6135	SLOPE WALL (125MM)	740.000	M2
511(A) M1332	REINFORCING STEEL	7,830.000	KG
511(B) M6010	EPOXY COATED REINFORCING STEEL	68,710.000	KG
514(A) M6011	PILES, FURNISHED (HP 250X62)	48.800	M
514(A) M6013	PILES, FURNISHED (HP 310X79)	283.600	M
514(B) M6292	PILES, DRIVEN (HP 250X62)	48.800	M
514(B) M6294	PILES, DRIVEN (HP 310X79)	283.600	M
514(F) M6354	PILE LOAD TEST (DYNAMIC)	26.000	EA
515(A) M6013	WATER REPELLENT (VISUALLY INSPECTED)	1,333.000	M2
516(A) M6098	DRILLED SHAFTS 1800MM DIAMETER	100.800	M
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	42.000	M
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	18.000	M
641 M1399	MOBILIZATION	1.000	LSUM
SECTION NO. 0003	X281-BRIDGE I		
501(B) M1307	SUBSTRUCTURE EXCAVATION COMMON	280.000	M3
501(G) M6309	CLSM BACKFILL	250.000	M3
503(A) M1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	621.600	M
504(A) M1304	APPROACH SLAB	420.000	M2
504(C) M6250	SEALED EXPANSION JOINT	20.900	M
504(F) M1381	CONCRETE PARAPET	263.200	M
506(A) M1322	STRUCTURAL STEEL	3,290.000	KG
509(A) M1326	CLASS AA CONCRETE	412.500	M3
509(B) M1328	CLASS A CONCRETE	469.800	M3
510(C) M6135	SLOPE WALL (125MM)	740.000	M2
511(A) M1332	REINFORCING STEEL	7,830.000	KG
511(B) M6010	EPOXY COATED REINFORCING STEEL	68,710.000	KG
514(A) M6011	PILES, FURNISHED (HP 250X62)	48.800	M
514(A) M6013	PILES, FURNISHED (HP 310X79)	283.600	M
514(B) M6292	PILES, DRIVEN (HP 250X62)	48.800	M
514(B) M6294	PILES, DRIVEN (HP 310X79)	283.600	M
514(F) M6354	PILE LOAD TEST (DYNAMIC)	26.000	EA
515(A) M6013	WATER REPELLENT (VISUALLY INSPECTED)	1,333.000	M2
516(A) M6098	DRILLED SHAFTS 1800MM DIAMETER	100.800	M

CALL ORDER : 160
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES : LEFLORE

CONTRACT ID : 010401
 PCN : 1169408
 PROJECTS : STPY-140A(01)
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 56.10
 CALENDAR DAYS : 350
 RES. ENG.:
 LIQ. DAM.: \$ 2000

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	X281-BRIDGE I		
613(P) M6204	150MM PERFORATED PIPE UNDERDRAIN ROUND	42.000	M
613(Q) M6207	150MM NON-PERF.PIPE UNDERDRAIN RND.	18.000	M
SECTION NO. 0004	Y008-TRAFFIC CONTROL		
856(A) M8839	CONSTR.TRAFF.STR.(PAINT)(100MM WIDE)	7,000.000	M
856(C) M8851	REM.PAVEMENT MARKING TAPE(100MM WIDE)	10,500.000	M
859(A) M8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	500.000	M
876(C) M8482	(PL)TRUCK MOUNTED ATTENUATOR	360.000	SD
880(A) M8812	ARROW DISPLAY(TYPE C)	360.000	SD
880(B) M8818	CONSTRUCTION SIGNS 0 TO 0.59 M2	11,000.000	SD
880(B) M8821	CONSTRUCTION SIGNS 0.60 M2 TO 1.47 M2	7,500.000	SD
880(B) M8824	CONSTRUCTION SIGNS 1.48 M2 TO 3.06 M2	900.000	SD
880(C) M8842	BARRICEDES(TYPE III)	1,800.000	SD
880(C) M8848	WING BARRICADES	1,080.000	SD
880(D) M8854	VERTICAL PANELS	1,800.000	SD
880(E) M8860	WARNING LIGHTS(TYPE A)	11,700.000	SD
880(E) M8872	WARNING LIGHTS(TYPE C)	2,160.000	SD
880(F) M8878	DRUMS	25,200.000	SD
880(G) M8884	TUBE CHANNELIZERS	18,000.000	SD
SECTION NO. 0005	Y008-SIGNING & STRIPING		
804(A) M2915	STRUCTURAL CONCRETE	13.900	M3
804(B) M2916	REINFORCING STEEL	1,393.600	KG
850(A) M8110	SHEET ALUMINUM SIGNS	101.010	M2
850(B) M8112	EXTRUDED ALUMINUM PANEL SIGNS	68.380	M2
851(A) M3206	100MM@19.3 GALV.STL.WD.FLANGE BM.POST	18.400	M
851(A) M3207	150MM@22.3 GALV.STL.WD.FLANGE BM.POST	27.200	M
851(A) M3208	150MM@29.8 GALV.STL.WD.FLANGE BM.POST	35.000	M
851(A) M3209	150MM@37.2 GALV.STL.WD.FLANGE BM.POST	33.700	M
851(B) M3218	75MM@11.28 GALV.STL.PIPE POST	42.300	M
851(B) M3219	89MM@13.56 GALV.STL.PIPE POST	122.000	M
851(C) M8321	44MM SQUARE TUBE POST	144.000	M
851(C) M8324	50MM SQUARE TUBE POST	47.000	M
851(C) M8327	57MM SQUARE TUBE POST	335.000	M
855(A) M8812	TRAFFIC STRIPE(PLASTIC)(100MM WIDE)	25,260.000	M
855(B) M8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	25.000	EA
855(B) M8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	13.000	EA
SECTION NO. 0006	STAK-STAKING		
642 M0098	STAKING	1.000	LSUM

CALL ORDER : 170
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES : LOGAN

CONTRACT ID : 010402
 PCN : 1868504
 PROJECTS : STPY-142A(57)TR
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 6.47
 CALENDAR DAYS : 60
 RES. ENG.:
 LIQ. DAM.: \$ 800

CONTRACT DESCRIPTION:

TRAFFIC SIGNAL INTERSECTION OF US-77/(DIVISION STREET) AND
 INDUSTRIAL ROAD IN THE CITY OF GUTHRIE. PROJ. LGTH.= 0.00
 MILE

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	Y031-TRAFFIC SIGNAL		
230(A) 2806	SOLID SLAB SODDING	400.000	SY
407 0250	TACK COAT	241.000	GAL
411(B) 4264	ASPHALT CONCRETE TYPE B	621.000	TON
414(A) 0260	8" P.C. CONCRETE PAVEMENT	846.000	SY
417 5267	COLD MILLING PAVEMENT	222.000	SY
509(D) 0325	CLASS C CONCRETE	0.750	CY
609(B) 1525	2'-8" COMB.CRB.& GUT.(6" BARRIER)	1,240.000	LF
610(A) 0602	4" CONCRETE SIDEWALK	27.000	SY
610(B) 0604	6" CONCRETE DRIVEWAY	189.000	SY
611(E) 5122	INLET CICI DES. 3 (D)	3.000	EA
611(F) 5330	INLET CICI DES. 3 (ADD'L DEPTH)	1.000	VF
611(K) 4488	CAST IRON CURB INLETS	12.000	EA
613(B) 0491	18" R.C.Pipe CLASS III	99.000	LF
613(B) 0492	24" R.C.Pipe CLASS III	17.000	LF
613(B) 4495	22" X 13" R.C.Pipe ARCH CLASS A-III	108.000	LF
619(B) 4726	REMOVAL OF CURB AND GUTTER	1,142.000	LF
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	147.000	SY
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	217.000	SY
619(B) 4741	REMOVAL OF DRAINAGE INLETS	3.000	EA
619(B) 4766	REMOVAL OF CONCRETE DRIVEWAY	254.000	SY
619(B) 4815	REMOVAL OF 18" RCP CL. III	273.000	LF
619(B) 4816	REMOVAL OF 24" RCP CL. III	48.000	LF
619(C) 0924	SAWING PAVEMENT	503.000	LF
641 1552	MOBILIZATION	1.000	LSUM
802(B) 8336	1 1/2" PVC SCH.40 PLASTIC CONDUIT BORED	80.000	LF
802(B) 8338	1 1/2" PVC SCH.40 PLASTIC CONDUIT TRENCH	550.000	LF
802(B) 8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	60.000	LF
802(B) 8344	3" PVC SCH.40 PLASTIC CONDUIT BORED	230.000	LF
802(B) 8346	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	40.000	LF
803 8065	PULL BOX(SIZE I)	2.000	EA
803 8066	PULL BOX(SIZE II)	4.000	EA
803 8067	PULL BOX(SIZE III)	2.000	EA
804(A) 2915	STRUCTURAL CONCRETE	11.260	CY
804(B) 2916	REINFORCING STEEL	1,753.000	LB
806(A) 8284	32'MHP 25'T.S.& 6'LMA(G.STL.)	2.000	EA
806(A) 8305	32'MH POLE 50'TS & 6'LMA(G.STL.)	2.000	EA
809(A) 8090	(PL)ROADWAY LUMINAIRE	4.000	EA

CALL ORDER : 170
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES : LOGAN

CONTRACT ID : 010402
 PCN : 1868504
 PROJECTS : STPY-142A(57)TR
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 6.47
 CALENDAR DAYS : 60
 RES. ENG.:
 LIQ. DAM.: \$ 800

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	Y031-TRAFFIC SIGNAL		
811 8040	1/C NO.6 ELECT.COND.	75.000	LF
811 8044	1/C NO.10 ELECT.COND.	1,130.000	LF
825 8550	VEH.ACT.SOL.ST.TRAF.SIG.CON.ASM	1.000	EA
828(A) 8135	SOL.STE.DIGITAL IND.VEH.LP.DET.	8.000	EA
828(B) 8138	LOOP DETECTOR WIRE	3,362.000	LF
831 8231	1WAY3SEC.ADJ.SIG.HD.S-6	8.000	EA
831 8252	1WAY3SEC.ADJ.SIG.HD.S-9	2.000	EA
833 3030	BACKPLATE	10.000	EA
834(A) 8207	5/C TRAF.SIG.EL.CABLE	1,275.000	LF
834(A) 8209	9/C TRAF.SIG.EL.CABLE	300.000	LF
834(A) 8210	12/C TRAF.SIG.EL.CABLE	275.000	LF
834(B) 8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	1,760.000	LF
850(A) 8110	SHEET ALUMINUM SIGNS	67.080	SF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	5,778.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	2.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	2.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
SECTION NO. 0002	STAK-STAKING		
642 0098	STAKING	1.000	LSUM

CALL ORDER : 195
LETTING DATE : September 20, 2001
LETTING TIME : 10:30 A.M.
COUNTIES : NOBLE

CONTRACT ID : 010414
PCN : 1733506
PROJECTS : IMY-35-4(189)199 IR
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : 2.70
CALENDAR DAYS : 30
RES. ENG.:
LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

BRIDGE REPAIR I-35 OVER RED ROCK CREEK, 21.8 MILE NORTH OF
PAYNE COUNTY LINE. PROJ. LGTH.= 0.00 MILES ASPH GRADE =
70-28 PG OK FKEX ESAKS = 17.5 MILLION

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	X071 BRIDGE 'A' & 'B'		
411(B) 6540	(SP)ASPHALT CONCRETE TYPE B(PG 70-28 OK)	150.000	TON
417 5267	COLD MILLING PAVEMENT	175.000	SY
504(H) 6390	RAPID CURE JOINT SEALANT	245.300	LF
504(I) 6389	ELASTOMERIC MORTAR	5.000	CF
505(D) 6087	LATEX MODIFIED BRIDGE DECK OVERLAY	2,887.500	SY
509 6386	(PL)SILICONE CONSTRUCTION JOINT	945.000	LF
641 1399	MOBILIZATION	1.000	LSUM
SECTION NO. 0002	Y002-TRAFFIC		
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	1,700.000	LF
857(A) 8947	PAVE.MARKERS CLASS C TYPE 2-C	8.000	EA
876(C) 8482	(PL)TRUCK MOUNTED ATTENUATOR	30.000	SD
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(K) 8908	SURVEILLANCE TRAFFIC CONTROL	30.000	SD
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	30.000	SD

CALL ORDER : 200
 LETTING DATE : September 20, 2001
 LETTING TIME : 10:30 A.M.
 COUNTIES : OKFUSKEE

CONTRACT ID : 010404
 PCN : 1810704M
 PROJECTS : STP-154C(27)C0/STP-154C(36)C0
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : 4.32
 CALENDAR DAYS : 30
 RES. ENG.:
 LIQ. DAM.: \$ 500

CONTRACT DESCRIPTION:

RESURFACE(ASPHALT) CO.RD: BEG 4.0 MI. W. & 1.0 MI. N. OF
 PHAROAH, EXT. EAST PROJ. LGTH.=2.04 PROJ. GRADE = 64-22 PG
 OK FLEX ESALS = 2.0 MILLION

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 I000-ROADWAY STP-154C(27)C0			
202(G) 0185	EARTHWORK	1.000	LSUM
303 0192	AGGREGATE BASE	40.000	CY
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	630.000	TON
407 0250	TACK COAT	1,410.000	GAL
408 5774	PRIME COAT	190.000	GAL
411(A) 6500	(SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	2,445.000	TON
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	1,215.000	TON
411(D) 6590	(SP)ASPHALT CONC.TYPE D(PG 64-22 OK)	576.000	TON
417 5267	COLD MILLING PAVEMENT	6,610.000	SY
420(A) 4242	FABRIC REINFORCEMENT	13,666.000	SY
420(B) 4268	BITUMINOUS BINDER	3,420.000	GAL
509(D) 0325	CLASS C CONCRETE	10.000	CY
601(A) 0297	TYPE I PLAIN RIPRAP	25.000	TON
613(D) 0689	18" CORR. GALV. STEEL PIPE	26.000	LF
613(M) 5726	18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
613(P) 1089	4" PERFORATED PIPE UNDERDRAIN ROUND	500.000	LF
613(Q) 1094	4" NON-PERF.PIPE UNDERDRAIN RND.	500.000	LF
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	120.000	SY
629(E) 5048	REMOVE AND RESET MAILBOX	1.000	EA
641 1552	MOBILIZATION	1.000	LSUM
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	20,270.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
931.57 5706	(PL) PRECOATED FABRIC MEMBRANE(STRIP)	1,980.000	LF
SECTION NO. 0002 I000-ROADWAY STP-154C(36)C0			
202(G) 0185	EARTHWORK	1.000	LSUM
303 0192	AGGREGATE BASE	40.000	CY
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	566.000	TON
407 0250	TACK COAT	1,335.000	GAL
408 5774	PRIME COAT	80.000	GAL
411(A) 6500	(SP)ASPHALT CONCRETE TYPE A(PG 64-22 OK)	2,352.000	TON
411(B) 6530	(SP)ASPHALT CONCRETE TYPE B(PG 64-22 OK)	1,145.000	TON
411(D) 6590	(SP)ASPHALT CONC.TYPE D(PG 64-22 OK)	575.000	TON
417 5267	COLD MILLING PAVEMENT	6,590.000	SY
420(A) 4242	FABRIC REINFORCEMENT	13,630.000	SY
420(B) 4268	BITUMINOUS BINDER	3,410.000	GAL

CALL ORDER : 200
LETTING DATE : September 20, 2001
LETTING TIME : 10:30 A.M.
COUNTIES : OKFUSKEE

CONTRACT ID : 010404
PCN : 1810704M
PROJECTS : STP-154C(27)C0/STP-154C(36)C0
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : 4.32
CALENDAR DAYS : 30
RES. ENG.:
LIQ. DAM.: \$ 500

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002	I000-ROADWAY STP-154C(36)C0		
509(D) 0325	CLASS C CONCRETE	10.000	CY
601(A) 0297	TYPE I PLAIN RIPRAP	50.000	TON
613(P) 1089	4" PERFORATED PIPE UNDERDRAIN ROUND	500.000	LF
613(Q) 1094	4" NON-PERF.PIPES UNDERDRAIN RND.	500.000	LF
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	120.000	SY
629(E) 5048	REMOVE AND RESET MAILBOX	1.000	EA
641 1552	MOBILIZATION	1.000	LSUM
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	20,220.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
931.57 5706	(PL) PRECOATED FABRIC MEMBRANE(STRIP)	1,980.000	LF