

NOTICE TO ALL CONTRACTORS

CONTRACTORS WILL NEED TO **DOWNLOAD, AND INSTALL, THE NEWEST VERSION OF EXPEDITE BID (5.9a)** AND USE THIS VERSION WHEN SUBMITTING THEIR BIDS. THIS UPDATE MAY BE ACCESSED THROUGH THE ODOT WEB SITE AT:

www.okladot.state.ok.us/contracts/index.htm



REMINDER

ODOT NOW REQUIRES ON LINE BIDDING. TO GET SIGNED UP TO BID OVER THE INTERNET CONTACT BID EXPRESS AT (352)381-4888, OR

<http://www.BIDX.com>



Unless otherwise noted in the proposal, all bids must be submitted over the internet using Bid Express. If a bidder is unable to submit an electronic bid due to conditions out of their control, such as, a disabled network server, power outage, or other unforeseen emergency, the bidder must request and get approval to submit a paper bid. This written approval should include the justification for the request and be taken to the Office engineer for signature prior to the bid opening. Once signed, include the approval form with the submitted bid.

Until further notice all projects which include a pay item for Contractors Quality Control (Item 643) will require the bidder to bid a minimum amount for that item.

This minimum will be specified at the end of the Special Provision 648-1QA(a)99, Payment for Contractor's Quality Control. You may increase this amount as necessary to cover the estimated Quality Control expenses.

Failure to include at least this amount will be considered grounds for rejection of Contractor's bid as nonresponsive.

Reminder

The low bidder must submit to the Office Engineer Division written confirmation from the DBE that it is participating in the contract as provided in the prime contractor's commitment. This may be submitted with the bid or not later than the Department's close of business on the Wednesday following the bid opening. Otherwise the bid shall be considered nonresponsive and shall be rejected by the Department.

Please ensure that the DBE commitment provided in the proposal matches the written confirmation.

Only DBE firms listed for the Letting month on the following web site are eligible for DBE credit:
<http://www.okladot.state.ok.us/regserv/dbeinfo/DCF2005.htm>

Reminder

*Please be sure that bid bonds are properly executed through the Bid Express system or stapled to the **back** of the proposal with written bid.*

For written bids, do not disassemble the bidding proposal in any way.

Note

Only written, Email, Fax and in-person orders will be accepted.

The Order Form included in this Notice may be used to order plans and proposals for this letting.

Please check off the proposal(s) in which you are interested and fax to:

405-522-0972 attention Order Desk

Or email your requests to:

mhenry@odot.org

CERTIFIED PAYROLL – FEDERAL RULE CHANGE

The U.S. Department of Labor, Wage and Hour Division, has revised regulations, pursuant to the Davis-Bacon and Related Acts and the Copeland Anti-Kickback Act to better protect the personal privacy of laborers and mechanics employed on covered construction projects.

The final rule, 29 CFR Parts 3 and 5, has an effective date of January 18, 2009. The revisions shall be applicable to federally assisted construction contracts entered into pursuant to invitations for bids issued or negotiations concluded on or after January 18, 2009.

The rule change states, in part, “ The payrolls submitted shall set out accurately and completely all of the information required to be maintained under 29 CFR Part 5.5 (a)(3)(i), except that full social security numbers and home addresses shall not be included on weekly transmittals. Instead, the payrolls shall only need to include an individual identifying number for each employee.”

The rule suggests that the last four digits of the employee’s social security number be used as the employee’s identification number. There is no prescribed method required by U.S. DOL.

The prime contractor is responsible for the submission of copies of payrolls by all subcontractors. Contractors and subcontractors shall maintain the full social security number and current address of each covered worker, and shall provide them upon request of the federal and/or state agency responsible for the contract for purposes of an investigation or audit of compliance with prevailing wage requirements. It is not a violation of the rule for a prime contractor to require a subcontractor provide addresses and social security numbers to the prime contractor for its own records, without weekly submission of such information to the sponsor government agency.

If the contractors utilize an electronic payroll system, a change from social security number to a personal identification number may require programming changes. If it is more convenient for the contractors, FHWA agrees that they may go ahead and make the necessary changes on all existing contracts, rather than only on those entered into after the effective date.

The provisions of the contracts will be revised to reflect this rule change as soon as practical. Should you have questions, you may contact the Regulatory Services Office at (405) 521-6046.

Notice

Internet bidding is required for most projects on the January 20, 2011 10:30 A.M. Letting. Instructions for using Bid Express, Expedite and the electronic bidding system (EBS) are available from the Office Engineer's office. When paper bids are allowed the printed bid sheets created from the EBS system must be placed in front of the bid item pages in the bidding proposal and will be turned in with the bid documents along with the proper disk. They should be placed and attached there without detaching the original proposal. (The paper copy of the bid items is the official bid document.) Plans and proposals should be ready for sale on December 30, 2010.

If ordering plans only please call the Print Services Branch at 521-2586.

A Pre-Bid Conference will be held at 10:00 a.m. on January 07, 2011. concerning this January 20 Bid Opening at the Oklahoma Department of Transportation (ODOT) Commission Room. Please review plans and proposals and send your comments and questions to the Office Engineer Division (attn: Masoud Pajoh) as early as possible at Fax: (405) 522-0972 or phone: (405) 521-2625. Please include JP, County, Letting date and Call Order (if known) in all your correspondence with Office Engineer. This will help both ODOT and Contractor.

Please write the call order number of the jobs you are bidding on any bidders disk submitted. Be sure to save your work and any revisions you receive to your original disk and submit that disk with your bid.

Important:

Effective with January 2011 Bid Opening, all bids for projects requiring pre-qualification will be submitted via Bid Express. Exceptions to this new policy will be discussed with the Office Engineer on a case-by-case basis, and noted on the Short and Long Form Notices

Effective with the June 2009 Letting, any firm bidding a project as a joint venture must complete the "Request for Joint Venture" form which is posted on the ODOT website.

Long Form and Short Form Notices, Order Forms, Bid Tabs and Awards, can be accessed on ODOT's Website

<http://www.okladot.state.ok.us/contracts/index.htm>

Questions and concerns regarding projects on any Letting should be faxed to:

Office Engineer Division at 405-522-0972

or emailed to:

mpajoh@odot.org with copy to bschmitt@odot.org

Please include words ***"Pre-bid question(s) and the Call Order and the Letting date of the project in question"*** in the subject line.

Plans for the project on this letting can be found at:
<http://www.okladot.state.ok.us/contracts/a2009/plans.htm>

OKLAHOMA DEPARTMENT OF TRANSPORTATION

Unless otherwise noted in the proposal, all bids must be submitted over the internet via Bid Express. When written bids are allowed, sealed proposals sent by registered mail will be received through the ODOT Office Engineer Division until 30 minutes prior to the scheduled bid opening. From 30 minutes prior to the bid opening until the time of the bid opening, bid proposals must be turned in directly to the ODOT Commission Room located on the east side of the lobby.

The scheduled bid opening is 10:30 A.M., January 20, 2011 , for the work listed below. No proposal for construction or maintenance work of the Department will be issued to any contractor after 10:30 A.M. on the working day preceding opening of bids for any contract.

Each bid shall be accompanied by a Certified or Cashier's Check or Bid Bond equal to 5% of the bid made payable to the State of Oklahoma, Department of Transportation, as a proposal guaranty. Proposal checks will be held or returned by the Department as per section 103.04 of the State Standard Specifications.

The minimum wage to be paid laborers and mechanics employed on this project shall be included in the proposal.

Bids must be prepared as directed by the State Standard Specifications.

Plans, proposals, and specifications may be examined in the plan room or in the Office Engineer Division at the Oklahoma Department of Transportation central office in Oklahoma City, Oklahoma.

This work will be done under the Oklahoma Department of Transportation applicable specifications for highway construction as depicted on the lower left corner of the plan's title sheet.

Plans and proposal forms may be ordered from the Office Engineer Division, Oklahoma Department of Transportation building, 200 N.E. 21st street, Oklahoma City, Oklahoma 73105. Cost of bidding documents is \$50.00 + tax for each bidding proposal. State Standard Specifications may be purchased for \$55.00 + tax. (Oklahoma tax is 8.375%). Make checks payable to Oklahoma Department of Transportation.

No Refunds will be made for Bidding Documents or Specification Books purchased.

Upon award of contract to a successful bidder, the contract will be completely and correctly executed by the contractor and returned to the Department within ten (10) working days from the date of award. The Department will have fourteen (14) working days from the date of award to complete its execution of the contract.

The Oklahoma Department of Transportation hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement, disadvantaged business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, sex, religion, national origin, or disability in consideration for an award.

Description of work and location of Project:

OKLAHOMA DEPARTMENT OF TRANSPORTATION**STATE PROJECT**

CONTRACT ID: 110032

CALL ORDER: 010
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: ADAIR

PROJECT(S) : PCN
SSR-101A(073)SR 2449104
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
60 CALENDAR DAYS
RES. ENG.: DIVISION 1 (MUSKOGEE)

CONTRACT DESCRIPTION
RESURFACE (ASPHALT)
US-59: FROM 0.25 MILES NORTH OF THE SH-51 WEST JUNCTION,
EXTEND, NORTH.
PROJECT LENGTH = 5.88 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	2500.000	TON
407 0250	TACK COAT	6660.000	GAL
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	12054.000	TON
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	117500.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**STATE PROJECT**

CONTRACT ID: 110033

CALL ORDER: 020
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: ADAIR

PROJECT(S) : PCN
SSR-101A(074)SR 2449105
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
60 CALENDAR DAYS
RES. ENG.: DIVISION 1 (MUSKOGEE)

CONTRACT DESCRIPTION
RESURFACE (ASPHALT)
US-59: FROM 6.38 MILES NORTH OF THE SH-51 WEST JUNCTION,
EXTEND NORTH.
PROJECT LENGTH = 7.62 MILES

SECTION 0001 - ROADWAY

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	3100.000	TON
407 0250	TACK COAT	8400.000	GAL
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	15230.000	TON
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	160934.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**STATE PROJECT**

CONTRACT ID: 110162

CALL ORDER: 021
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: ADAIR

<u>PROJECT(S) :</u>	<u>PCN</u>
SSR-101A(073)SR	2449104
SSR-101A(074)SR	2449105

DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
90 CALENDAR DAYS
RES. ENG.: DIVISION 1 (MUSKOGEE)

CONTRACT DESCRIPTION

RESURFACE (ASPHALT)
US-59: FROM 0.25 MILES NORTH OF THE SH-51 WEST JUNCTION,
EXTEND NORTH.
PROJECT LENGTH = 13.50 MILES

SECTION 0001 - ROADWAY - SSR-101A(073)SR

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	2500.000	TON
407 0250	TACK COAT	6660.000	GAL
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	12054.000	TON
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	117500.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0002 - ROADWAY - SSR-101A(074)SR

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	3100.000	TON
407 0250	TACK COAT	8400.000	GAL
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	15230.000	TON
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	160934.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 110034

CALL ORDER: 040
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: ATOKA

PROJECT(S) : PCN
NHY-013N(139)3P 2744904
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
120 CALENDAR DAYS
RES. ENG.: DIVISION 2 (ANTLERS)

CONTRACT DESCRIPTION
RESURFACE (CONCRETE)
US-69: FROM THE PITTSBURG COUNTY LINE, EXTEND SOUTH.
PROJECT LENGTH = 8.00 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	18500.000	TON
411(D) 5965	SUPERPAVE, TYPE S5(PG 76-28 OK)	250.000	TON
411(D) 5975	SUPERPAVE, TYPE S5(PG 64-22 OK)	10000.000	TON
412 5267	COLD MILLING PAVEMENT	2200.000	SY
413(C) 4868	RUMBLE STRIP-METHOD PCC-CON	83600.000	LF
414(A) 0210	P.C.CONCRETE PAVEMENT(PLACEMENT)	173800.000	SY
414(D) 0220	BONDED CONCRETE OVERLAY	9200.000	SY
414(E) 0225	FULL DEPTH P.C.C. PATCH(PLACEMENT ONLY)	1500.000	SY
414(G) 5275	P.C. CONCRETE FOR PAVEMENT	31700.000	CY
415 6300	CONCRETE JOINT SEALING	798.000	LF
856(A) 8530	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	83600.000	LF
856(A) 8535	TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	22560.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110002

CALL ORDER: 050
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: BLAINE

PROJECT(S) : PCN
 BRO-106D(089)CI 2497304
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$9.75
 120 CALENDAR DAYS
 RES. ENG.: DIVISION 5 (CLINTON)

CONTRACT DESCRIPTION
 BRIDGE AND APPROACHES
 COUNTY ROAD (EW-67): OVER MINNEHAHA CREEK, 1.2 MILES WEST OF
 THE SH-58 JUNCTION.
 PROJECT LENGTH = 0.226 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
201 0102	CLEARING AND GRUBBING	1.000	LSUM
202(G) 0185	EARTHWORK	1.000	LSUM
205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
222 2801	TEMPORARY BALE BARRIER	100.000	LF
223 2801	TEMPORARY SILT FENCE	4880.000	LF
230(A) 2806	SOLID SLAB SODDING	5200.000	SY
233(A) 2817	VEGETATIVE MULCHING	1.100	AC
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	674.000	TON
509(D) 0325	CLASS C CONCRETE	10.000	CY
613(CC) 7192	TYPE BB4 CULVERT END TREATMENT	2.000	EA
613(D) 0690	24" CORR. GALV. STEEL PIPE	48.000	LF

SECTION 0002 - BRIDGE 'A'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	88.000	CY
501(D) 6353	UNCLASSIFIED BACKFILL	90.000	CY
503(A) 1312	PRESTRESSED CONCRETE BEAMS (TYPE III)	296.200	LF
504(E) 1380	CONCRETE RAIL (TR1)	215.200	LF
506(A) 1322	STRUCTURAL STEEL	1800.000	LB
509(A) 1326	CLASS AA CONCRETE	58.500	CY
509(B) 1328	CLASS A CONCRETE	58.400	CY
511(A) 1332	REINFORCING STEEL	21317.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	148.000	LF
514(A) 6011	PILES, FURNISHED (HP 12X53)	331.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	148.000	LF
514(B) 6294	PILES, DRIVEN (HP 12X53)	331.000	LF
601(A-1)1353	TYPE I-A PLAIN RIPRAP	980.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	350.000	TON
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT****CONTRACT ID: 110002****SECTION 0002 - BRIDGE 'A'**

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0003 - STAKING

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
642 0098	STAKING	1.000	LSUM

SECTION 0004 - CONSTRUCTION

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
220 2800	(SP)SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
641 1399	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 090151

CALL ORDER: 060
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: BRYAN

PROJECT(S) : PCN
 NHY-013N(147)3P 2629506
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 120 CALENDAR DAYS
 RES. ENG.: DIVISION 2 (ANTLERS)

CONTRACT DESCRIPTION
 RESURFACE (CONCRETE)
 US-69: FROM 1.07 MILES NORTHEAST OF THE SH-78 JUNCTION,
 EXTEND NORTH.
 PROJECT LENGTH = 8.00 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	18600.000	TON
411(D) 5965	SUPERPAVE, TYPE S5(PG 76-28 OK)	250.000	TON
411(D) 5975	SUPERPAVE, TYPE S5(PG 64-22 OK)	10600.000	TON
412 5267	COLD MILLING PAVEMENT	8000.000	SY
413(C) 4868	RUMBLE STRIP-METHOD PCC-CON	84600.000	LF
414(A) 0210	P.C.CONCRETE PAVEMENT(PLACEMENT)	186000.000	SY
414(D) 0220	BONDED CONCRETE OVERLAY	5100.000	SY
414(E) 0225	FULL DEPTH P.C.C. PATCH(PLACEMENT ONLY)	1500.000	SY
414(G) 5275	P.C. CONCRETE FOR PAVEMENT	32750.000	CY
415 6300	CONCRETE JOINT SEALING	670.000	LF
504(A) 1304	APPROACH SLAB	296.000	SY
612(C) 0645	INLET ADJUST TO GRADE	3.000	EA

SECTION 0002 - TRAFFIC

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
856(A) 8530	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	86400.000	LF
856(A) 8535	TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	23040.000	LF
856(A) 8540	TRAFFIC STRIPE(MULTI-POLY.)(8" WIDE)	6000.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110039

CALL ORDER: 070
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: CANADIAN

PROJECT(S) : PCN
 STPY-109C(176)3P 2824104
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 60 CALENDAR DAYS
 RES. ENG.: DIVISION 4 (PERRY)

CONTRACT DESCRIPTION
 RESURFACE (ASPHALT)
 US-270: FROM 3RD STREET IN CALUMET, EXTEND SOUTH.
 PROJECT LENGTH = 4.99 MILES

SECTION 0001 - ROADWAY - STPY-109C(176)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 4781	UNCLASSIFIED BORROW (TOPSOIL)	1500.000	CY
407(C) 0300	POLYMER MODIFIED CATIONIC RAPID SET - 1	25500.000	GAL
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	9300.000	TON
411(E) 5990	SUPERPAVE, TYPE S6(PG 64-22 OK)	400.000	TON
412 5267	COLD MILLING PAVEMENT	2800.000	SY
413(B) 4862	RUMBLE STRIP-METHOD HMA-CYC GROUP	8.000	EAGP
619(B) 4780	REMOVAL OF GUARDRAIL	600.000	LF
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	50.000	LF
623(G) 8571	GUARDRAIL END TREATMENT (GET)	8.000	EA

SECTION 0002 - BRIDGE - STPY-109C(176)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
504(G) 6390	RAPID CURE JOINT SEALANT	56.000	LF
504(H) 6389	ELASTOMERIC MORTAR	4.100	CF
513(B) 6019	CLASS B BRIDGE DECK REPAIR	20.000	SY
513(C) 6020	CLASS C BRIDGE DECK REPAIR	1.000	SY

SECTION 0003 - TRAFFIC - STPY-109C(176)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
623(H) 0940	GUARDRAIL BLOCKOUT REPLACEMENT	450.000	LF
853 9069	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	62.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	88000.000	LF
855(A) 8825	TRAFFIC STRIPE(PLASTIC)(24" WIDE)	100.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110041

CALL ORDER: 080
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: BLAINE
 CANADIAN

PROJECT(S) : PCN
 STPY-109C(177)3P 2825104
 DBE GOALS : 3.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 60 CALENDAR DAYS
 RES. ENG.: DIVISION 4 (PERRY)

CONTRACT DESCRIPTION
 RESURFACE (ASPHALT)
 US-270: FROM THE US-281 JUNCTION, EXTEND EAST.
 PROJECT LENGTH = 5.72 MILES

SECTION 0001 - ROADWAY - STPY-109C(177)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 4781	UNCLASSIFIED BORROW (TOPSOIL)	1000.000	CY
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	8000.000	TON
412 5267	COLD MILLING PAVEMENT	600.000	SY
619(B) 4780	REMOVAL OF GUARDRAIL	300.000	LF
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	75.000	LF
623(C) 5202	BEAM GUARDRAIL THRIE-BEAM SINGLE	62.500	LF
623(D) 5203	BEAM GUARDRAIL THRIE-BEAM DOUBLE	50.000	LF
623(E) 7113	BEAM GUARDRAIL TRANSITION SECTION	4.000	EA
623(G) 8571	GUARDRAIL END TREATMENT (GET)	4.000	EA

SECTION 0002 - TRAFFIC - STPY-109C(177)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
853 9069	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	20.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	98000.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110042

CALL ORDER: 090
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: CANADIAN

PROJECT(S) : PCN
 STPY-109C(178)3P 2825204
 DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 60 CALENDAR DAYS
 RES. ENG.: DIVISION 4 (PERRY)

CONTRACT DESCRIPTION
 RESURFACE (ASPHALT)
 US-270: FROM 5.72 MILES EAST OF THE US-281 JUNCTION, EXTEND
 EAST.
 PROJECT LENGTH = 5.85 MILES

SECTION 0001 - ROADWAY - STPY-109C(178)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 4781	UNCLASSIFIED BORROW (TOPSOIL)	1000.000	CY
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	8900.000	TON
412 5267	COLD MILLING PAVEMENT	9500.000	SY
619(B) 4780	REMOVAL OF GUARDRAIL	1850.000	LF
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	200.000	LF
623(C) 5202	BEAM GUARDRAIL THRIE-BEAM SINGLE	250.000	LF
623(D) 5203	BEAM GUARDRAIL THRIE-BEAM DOUBLE	100.000	LF
623(E) 7113	BEAM GUARDRAIL TRANSITION SECTION	8.000	EA
623(G) 8571	GUARDRAIL END TREATMENT (GET)	8.000	EA

SECTION 0002 - TRAFFIC - STPY-109C(178)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
853 9069	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	46.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	100000.000	LF
855(A) 8825	TRAFFIC STRIPE(PLASTIC)(24" WIDE)	60.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110165

CALL ORDER: 091 LETTING DATE: January 20, 2011 LETTING TIME: 10:30 A.M. COUNTIES: BLAINE CANADIAN	PROJECT(S) : <u>PCN</u> STPY-109C(176)3P 2824104 STPY-109C(177)3P 2825104 STPY-109C(178)3P 2825204 DBE GOALS : 3.00 GUARANTY : 5% OF BID TOTAL PLAN PRICE : \$0.00 150 CALENDAR DAYS RES. ENG.: DIVISION 4 (PERRY)
--	---

CONTRACT DESCRIPTION

RESURFACE (ASPHALT)

US-270: FROM THE US-281 JUNCTION, EXTEND EAST THEN SOUTH AT
3RD STREET IN THE TOWN OF CALUMET.

PROJECT LENGTH = 16.56 MILES

SECTION 0001 - ROADWAY - STPY-109C(176)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 4781	UNCLASSIFIED BORROW (TOPSOIL)	1500.000	CY
407(C) 0300	POLYMER MODIFIED CATIONIC RAPID SET - 1	25500.000	GAL
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	9300.000	TON
411(E) 5990	SUPERPAVE, TYPE S6(PG 64-22 OK)	400.000	TON
412 5267	COLD MILLING PAVEMENT	2800.000	SY
413(B) 4862	RUMBLE STRIP-METHOD HMA-CYC GROUP	8.000	EAGP
619(B) 4780	REMOVAL OF GUARDRAIL	600.000	LF
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	50.000	LF
623(G) 8571	GUARDRAIL END TREATMENT (GET)	8.000	EA

SECTION 0002 - BRIDGE - STPY-109C(176)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
504(G) 6390	RAPID CURE JOINT SEALANT	56.000	LF
504(H) 6389	ELASTOMERIC MORTAR	4.100	CF
513(B) 6019	CLASS B BRIDGE DECK REPAIR	20.000	SY
513(C) 6020	CLASS C BRIDGE DECK REPAIR	1.000	SY

SECTION 0003 - TRAFFIC - STPY-109C(176)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
623(H) 0940	GUARDRAIL BLOCKOUT REPLACEMENT	450.000	LF
853 9069	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	62.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	88000.000	LF
855(A) 8825	TRAFFIC STRIPE(PLASTIC)(24" WIDE)	100.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0004 - ROADWAY - STPY-109C(177)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 4781	UNCLASSIFIED BORROW (TOPSOIL)	1000.000	CY
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	8000.000	TON
412 5267	COLD MILLING PAVEMENT	600.000	SY

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110165

SECTION 0004 - ROADWAY - STPY-109C(177)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
619(B) 4780	REMOVAL OF GUARDRAIL	300.000	LF
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	75.000	LF
623(C) 5202	BEAM GUARDRAIL THRIE-BEAM SINGLE	62.500	LF
623(D) 5203	BEAM GUARDRAIL THRIE-BEAM DOUBLE	50.000	LF
623(E) 7113	BEAM GUARDRAIL TRANSITION SECTION	4.000	EA
623(G) 8571	GUARDRAIL END TREATMENT (GET)	4.000	EA

SECTION 0005 - TRAFFIC - STPY-109C(177)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
853 9069	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	20.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	98000.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0006 - ROADWAY - STPY-109C(178)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 4781	UNCLASSIFIED BORROW (TOPSOIL)	1000.000	CY
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	8900.000	TON
412 5267	COLD MILLING PAVEMENT	9500.000	SY
619(B) 4780	REMOVAL OF GUARDRAIL	1850.000	LF
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	200.000	LF
623(C) 5202	BEAM GUARDRAIL THRIE-BEAM SINGLE	250.000	LF
623(D) 5203	BEAM GUARDRAIL THRIE-BEAM DOUBLE	100.000	LF
623(E) 7113	BEAM GUARDRAIL TRANSITION SECTION	8.000	EA
623(G) 8571	GUARDRAIL END TREATMENT (GET)	8.000	EA

SECTION 0007 - TRAFFIC - STPY-109C(178)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
853 9069	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	46.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	100000.000	LF
855(A) 8825	TRAFFIC STRIPE(PLASTIC)(24" WIDE)	60.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110004

CALL ORDER: 110
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: CLEVELAND

PROJECT(S) : PCN
 STPG-114B(260)AG 2691504
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$6.50
 30 CALENDAR DAYS
 RES. ENG.: DIVISION 3 (ADA)

CONTRACT DESCRIPTION
 TRAFFIC SIGNAL
 CITY STREET(NE 12TH ST.): AT BUCK THOMAS DRIVE IN THE CITY
 OF MOORE.

SECTION 0001 - TRAFFIC SIGNALS

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
802(B) 8340	2" PVC SCH.40 PLASTIC CONDUIT BORED	30.000	LF
802(B) 8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	100.000	LF
802(B) 8344	3" PVC SCH.40 PLASTIC CONDUIT BORED	250.000	LF
802(B) 8346	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	50.000	LF
803(A) 8065	PULL BOX(SIZE I)	3.000	EA
803(A) 8066	PULL BOX(SIZE II)	1.000	EA
804(A) 2915	STRUCTURAL CONCRETE	8.600	CY
804(B) 2916	REINFORCING STEEL	1271.000	LB
805(A) 8724	(PL)REMOVAL OF EXISTING SIGNS	1.000	EA
806(A) 8312	32'MH POLE 40'TS & 10'LMA(G.STL.)	1.000	EA
806(A) 8351	32'MH POLE 25',TS & 10'LMA(G.STL.)	1.000	EA
806(A) 8732	POLE & 40' TS MST.ARM(G.STL.)	1.000	EA
806(B) 8896	12' MTG.HT.TS PED.POLE(G.STL.)	1.000	EA
809(A) 8090	ROADWAY LUMINAIRE	2.000	EA
810(A) 3118	SERVICE POLE	1.000	EA
811 8040	1/C NO.6 ELECT.COND.	200.000	LF
811 8044	1/C NO.10 ELECT.COND.	625.000	LF
825 8550	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	1.000	EA
828 8132	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
830 8000	PEDESTRIAN PUSH BUTTON	6.000	EA
831 8231	1WAY3SEC.ADJ.SIG.HD.S-6	6.000	EA
831 8286	1WAY5SEC.ADJ.SIG.HD.S-19	1.000	EA
831 8295	1WAY2SEC.ADJ.PED.SIG.HD.S-20	6.000	EA
833 3030	BACKPLATE	7.000	EA
834(A) 8207	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	954.000	LF
834(A) 8208	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	211.000	LF
834(A) 8213	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	451.000	LF
834(B) 8220	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	82.000	LF
840(B) 8593	E.P.S. OPTICAL DETECTOR	2.000	EA
840(C) 8594	E.P.S. OPTICAL DETECTOR CABLE	400.000	LF
840(D) 8595	E.P.S. 2 CHANNEL PHASE SELECTOR	1.000	EA

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT****CONTRACT ID: 110004****SECTION 0001 - TRAFFIC SIGNALS**

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
850(C) 8118	MAST ARM MOUNTED SIGNS(ALUM.)	79.000	SF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	110.000	LF
855(A) 8825	TRAFFIC STRIPE(PLASTIC)(24" WIDE)	65.000	LF

SECTION 0002 - STAKING

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
642(A) 0095	CONSTRUCTION STAKING LEVEL I	1.000	LSUM

SECTION 0003 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
641 1552	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**STATE PROJECT**

CONTRACT ID: 110005

CALL ORDER: 120
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: CLEVELAND

PROJECT(S) : PCN
SSR-114A(270)SR 2741704
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
60 CALENDAR DAYS
RES. ENG.: BRUCE VALLEY, PURCELL

CONTRACT DESCRIPTION
RESURFACE (ASPHALT)
SH-9: FROM 24TH AVENUE IN THE CITY OF NORMAN, EXTEND EAST.
PROJECT LENGTH = 4.16 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	1237.000	TON
407 0250	TACK COAT	16759.000	GAL
411(S5) 5970	(SP)ASPH.CONC.,TYPE S5(PG 70-28 OK)	22896.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	14837.000	SY
610(A) 0602	4" CONCRETE SIDEWALK	26.800	SY
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	212150.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	62.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	31.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110046

CALL ORDER: 130
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: COMANCHE

PROJECT(S) : PCN
 NHY-020N(038)3P 2462104
 DBE GOALS : 4.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 60 CALENDAR DAYS
 RES. ENG.: DIVISION 7 (DUNCAN)

CONTRACT DESCRIPTION
 RESURFACE (ASPHALT)
 US-62: FROM THE KIOWA COUNTY LINE, EXTEND EAST.
 PROJECT LENGTH = 4.98 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(G) 0185	EARTHWORK	1.000	LSUM
223 2801	TEMPORARY SILT FENCE	1600.000	LF
227 0100	TEMPORARY SILT DIKE	160.000	LF
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	28580.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	9180.000	TON
413(A) 4861	RUMBLE STRIP-METHOD AC-CON	99600.000	LF
417 4267	COLD MILLING BITUMINOUS PAVEMENT	10200.000	SY
420(A) 4242	FABRIC REINFORCEMENT	151924.000	SY
420(B) 4268	BITUMINOUS BINDER	37982.000	GAL
504(F) 1381	CONCRETE PARAPET	96.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	2447.500	LF
623(E) 7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	8.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	8.000	EA
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	119680.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	18.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	9.000	EA
876(C) 8482	(PL)TRUCK MOUNTED ATTENUATOR	16.000	SD
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110007

CALL ORDER: 140
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: COMANCHE

PROJECT(S) : PCN
 SBR-116C(190)SB 2733004
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$19.51
 90 CALENDAR DAYS
 RES. ENG.: DIVISION 7 (DUNCAN)

CONTRACT DESCRIPTION
 BRIDGE REHABILITATION
 SH-65: OVER WEST FORK OF BEAVER CREEK, 4.2 MILES NORTH OF
 THE SH-7 JUNCTION.
 PROJECT LENGTH = 0.191 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 0186	SELECT BORROW	55.000	CY
222 2801	TEMPORARY BALE BARRIER	200.000	LF
223 2801	TEMPORARY SILT FENCE	510.000	LF
230(A) 2806	SOLID SLAB SODDING	340.000	SY
407 0250	TACK COAT	250.000	GAL
411(S5) 5975	(SP)ASPH.CONC.,TYPE S5(PG 64-22 OK)	670.000	TON
417 5267	COLD MILLING PAVEMENT	2500.000	SY
619(B) 4780	REMOVAL OF GUARD RAIL	240.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	237.500	LF
623(E) 7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	4.000	EA
623(F) 4447	GUARD RAIL ANCHOR UNIT (TYPE B)	1.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	3.000	EA

SECTION 0002 - BRIDGE 'A'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
501(G) 6309	CLSM BACKFILL	7.000	CY
502 6116	(PL)FALSEWORK JACKING	1.000	LSUM
504(A) 1304	APPROACH SLAB	188.000	SY
504(C) 6250	SEALED EXPANSION JOINT	71.000	LF
504(E) 6245	CONCRETE RAIL (TR4)	516.300	LF
504(H) 6390	RAPID CURE JOINT SEALANT	34.500	LF
506(A) 1322	STRUCTURAL STEEL	2160.000	LB
509(A) 1326	CLASS AA CONCRETE	160.000	CY
509(D) 1331	CLASS C CONCRETE	8.000	CY
511 6306	(PL)MECHANICAL SPLICES	476.000	EA
511(B) 6010	EPOXY COATED REINFORCING STEEL	35298.000	LB
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
520(A) 6058	PREPARATION OF CRACKS ABOVE WATER	30.000	LF
520(C) 6060	EPOXY RESIN ABOVE WATER	5.000	GAL
521(A) 6210	PNEUMATICALLY PLACED MORTAR	20.000	SY

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110007

SECTION 0002 - BRIDGE 'A'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
523(A) 6550	(SP) SEALER CRACK PREPARATION	305.300	LF
523(B) 6560	(SP) SEALER RESIN	4.900	GAL
535 6164	(PL)FIXED BEARING ASSEMBLY	25.000	EA
535 6165	(PL)EXPANSION BEARING ASSEMBLY	25.000	EA
540 4515	(PL)REPAIR BRIDGE ITEM (TYPE A)	6.000	EA
540 4525	(PL)REPAIR BRIDGE ITEM (TYPE B)	6.000	EA
619(B) 2500	(PL)REMOVAL OF BRIDGE ITEMS	1.000	LSUM

SECTION 0003 - TRAFFIC

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
623 8572	(PL)CURVED APPROACH GUARD RAIL	1.000	EA
627(O) 4410	REL.OF RENTED PORT.PREC.CONC.MED.BARRIER	1230.000	LF
627(P) 4425	RENTED PORT.TYPE PREC.CONC.MED. BARR.	1230.000	LF
823 8478	(PL)PORTABLE TRAFFIC SIGNAL SYSTEM	90.000	SD
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	4040.000	LF
871 8705	(PL)CONST.ZONE IMPACT ATTEN.	180.000	SD
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	180.000	SD

SECTION 0004 - STAKING

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
642 0098	STAKING	1.000	LSUM

SECTION 0005 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
641 1399	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110106

CALL ORDER: 160
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: CRAIG

PROJECT(S) : PCN
 BRF-118C(070)CI 2341804
 DBE GOALS : 4.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$16.26
 210 CALENDAR DAYS
 RES. ENG.: DIVISION 8 (TULSA)

CONTRACT DESCRIPTION
 BRIDGE AND APPROACHES
 COUNTY ROAD (EW-19): OVER BIG CABIN CREEK, 2.3 MILES WEST
 OF THE SH-2 JUNCTION.
 PROJECT LENGTH = 0.610 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
201(A) 0102	CLEARING AND GRUBBING	1.000	LSUM
202(A) 0183	UNCLASSIFIED EXCAVATION	4584.000	CY
202(D) 0184	UNCLASSIFIED BORROW	13989.000	CY
205(A) 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
221(C) 2801	TEMPORARY SILT FENCE	5448.000	LF
221(F) 0100	TEMPORARY SILT DIKE	512.000	LF
230(A) 2806	SOLID SLAB SODDING	15491.000	SY
233(A) 2817	VEGETATIVE MULCHING	3.200	AC
402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	3012.000	TON
509(D) 0325	CLASS C CONCRETE	10.000	CY
613(D) 4504	21" X 15" CORR. ALUMINUM PIPE ARCH	101.000	LF
613(L) 4504	21" X 15" PREFAB. CULVERT END SEC., ARCH	6.000	EA
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM

SECTION 0002 - BRIDGE 'A'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	90.000	CY
501(G) 6309	CLSM BACKFILL	102.000	CY
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	1250.000	LF
504(A) 1304	APPROACH SLAB	115.000	SY
504(D) 6239	CONCRETE RAIL (TR3)	695.000	LF
506(A) 1322	STRUCTURAL STEEL	5120.000	LB
509(A) 1326	CLASS AA CONCRETE	286.000	CY
509(B) 1328	CLASS A CONCRETE	107.000	CY
511(A) 1332	REINFORCING STEEL	87920.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	106.000	LF
514(A) 6011	PILES, FURNISHED (HP 12X53)	287.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	106.000	LF
514(B) 6294	PILES, DRIVEN (HP 12X53)	287.000	LF
516(A) 6093	DRILLED SHAFTS 42" DIAMETER	74.000	LF
601(B) 1353	TYPE I-A PLAIN RIPRAP	3532.000	TON

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110106

SECTION 0002 - BRIDGE 'A'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
601(C) 1355	TYPE I-A FILTER BLANKET	923.000	TON
601(I) 6312	FILTER FABRIC (RIPRAP)	74.000	SY
613(H) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	70.000	LF
613(I) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	20.000	LF
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	50.000	LF
623(F) 5686	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
623(G) 8571	GUARDRAIL END TREATMENT (GET)	4.000	EA

SECTION 0003 - TRAFFIC

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0004 - STAKING

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

SECTION 0005 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
220 2800	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
640(A) 1398	FIELD OFFICE	1.000	EA
641 1399	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110008

CALL ORDER: 170
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: CREEK

PROJECT(S) : PCN
 BRO-119D(044)CO 1816804
 DBE GOALS : 4.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$14.09
 120 CALENDAR DAYS
 RES. ENG.: DIVISION 8 (TULSA)

CONTRACT DESCRIPTION
 BRIDGE AND APPROACHES
 COUNTY ROAD (EW-67): OVER BUCKEYE CREEK, 4.7 MILES EAST OF
 THE SH-99 JUNCTION.
 PROJECT LENGTH = 0.207 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
201 0102	CLEARING AND GRUBBING	1.000	LSUM
202(G) 0185	EARTHWORK	1.000	LSUM
205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223 2801	TEMPORARY SILT FENCE	500.000	LF
227 0100	TEMPORARY SILT DIKE	500.000	LF
230(A) 2806	SOLID SLAB SODDING	12406.000	SY
233(A) 2817	VEGETATIVE MULCHING	2.560	AC
327(A) 4200	(SP)FLY ASH	112.000	TON
327(E) 4240	(SP)CEMENTITIOUS STABILIZED SUBGRADE	2524.000	SY
407 0250	TACK COAT	282.000	GAL
408 5774	PRIME COAT	439.000	GAL
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	672.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	326.000	TON
509(D) 0325	CLASS C CONCRETE	10.000	CY
601(A) 0297	TYPE I PLAIN RIPRAP	631.000	TON
613(CC) 7187	TYPE B4 CULVERT END TREATMENT	4.000	EA
613(D) 0690	24" CORR. GALV. STEEL PIPE	114.000	LF
854(A) 8800	TRAFFIC STRIPE(PAINT)(4" WIDE)	2269.000	LF
880(C) 8845	BARRICADES(TYPE III)	2.000	EA

SECTION 0002 - BRIDGE 'A'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	68.000	CY
501(D) 6353	UNCLASSIFIED BACKFILL	50.000	CY
503(B) 6144	PRESTRESSED CONCRETE DOUBLE TEE	817.500	LF
504(E) 1380	CONCRETE RAIL (TR1)	387.000	LF
509(A) 1326	CLASS AA CONCRETE	112.000	CY
509(B) 1328	CLASS A CONCRETE	81.700	CY
511(A) 1332	REINFORCING STEEL	32025.000	LB
514 6260	(PL)PILOT HOLES	69.500	LF

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110008

SECTION 0002 - BRIDGE 'A'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
514(A) 6010	PILES, FURNISHED (HP 10X42)	305.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	305.000	LF
516(A) 6093	DRILLED SHAFTS 42" DIAMETER	122.400	LF
601(A-1)1353	TYPE I-A PLAIN RIPRAP	1287.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	382.000	TON
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0003 - STAKING

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
642 0098	STAKING	1.000	LSUM

SECTION 0004 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
220 2800	(SP)SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
641 1399	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110049

CALL ORDER: 180
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: CREEK

<u>PROJECT(S) :</u>	<u>PCN</u>
SSR-119B(175)SR	2544604
SSR-119B(210)SR	2762904

DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 75 CALENDAR DAYS
 RES. ENG.: DIVISION 8 (TULSA)

CONTRACT DESCRIPTION

RESURFACE (ASPHALT)
 SH-117: FROM THE US-75A JUNCTION, EXTEND EAST.
 SH-117A: FROM THE SH-117 JUNCTION, EXTEND NORTH.
 PROJECT LENGTH = 5.45 MILES

SECTION 0001 - ROADWAY - SSR-119B(175)SR

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
411(C) 5950	SUPERPAVE, TYPE S4(PG 76-28 OK)	10742.000	TON
411(H) 6210	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	10.000	TON
411(I) 6310	SUPERPAVE, TYPE S4(PATCH)(PG64-22OK)	10.000	TON
412 5267	COLD MILLING PAVEMENT	127307.000	SY
805(A) 8702	REMOVAL OF CLASS C PAVEMENT MARKERS	2465.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	76427.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	125.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	5.000	EA
857(F) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	19760.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	240.000	HOURL
882(A) 8306	PORT.CHANGEABLE MESSAGE SIGN	240.000	SD

SECTION 0002 - ROADWAY - SSR-119B(210)SR

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
411(C) 5950	SUPERPAVE, TYPE S4(PG 76-28 OK)	2420.000	TON
411(H) 6210	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	10.000	TON
411(I) 6310	SUPERPAVE, TYPE S4(PATCH)(PG64-22OK)	10.000	TON
412 5267	COLD MILLING PAVEMENT	21480.000	SY
828(B) 8136	LOOP DETECTOR WIRE	1540.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	11150.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	8.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	3.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	150.000	HOURL
882(A) 8306	PORT.CHANGEABLE MESSAGE SIGN	75.000	SD

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110052

CALL ORDER: 190
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: CREEK

PROJECT(S) : PCN
 SBR-119C(209)SB 2762504
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$34.68
 240 CALENDAR DAYS
 RES. ENG.: DIVISION 8 (TULSA)

CONTRACT DESCRIPTION
 BRIDGE REHABILITATION
 SH-66: OVER LITTLE POLECAT CREEK, 13.4 MILES NORTHEAST OF
 THE SH-48 JUNCTION.

SECTION 0001 - BRIDGE 'A'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
411(B) 5940	SUPERPAVE, TYPE S3(PG 70-28 OK)	270.000	TON
411(B) 5945	SUPERPAVE, TYPE S3(PG 64-22 OK)	258.000	TON
411(C) 5955	SUPERPAVE, TYPE S4(PG 70-28 OK)	135.000	TON
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	129.000	TON
501(G) 6309	CLSM BACKFILL	20.000	CY
504(A) 1304	APPROACH SLAB	137.800	SY
504(B) 1305	SAW-CUT GROOVING	461.100	SY
504(C) 6250	SEALED EXPANSION JOINT	64.400	LF
504(D) 6245	CONCRETE RAIL (TR4)	151.340	LF
506(A) 1322	STRUCTURAL STEEL	3356.000	LB
507(A) 6164	FIXED BEARING ASSEMBLY	21.000	EA
507(A) 6165	EXPANSION BEARING ASSEMBLY	21.000	EA
509(A) 1326	CLASS AA CONCRETE	93.000	CY
509(B) 0321	CLASS A CONCRETE	77.000	CY
509(D) 1331	CLASS C CONCRETE	2.000	CY
511(A) 0332	REINFORCING STEEL	6000.000	LB
511(B) 6010	EPOXY COATED REINFORCING STEEL	20637.000	LB
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	184.000	SY
521(A) 6210	PNEUMATICALLY PLACED MORTAR	5.000	SY
535 6280	REMOVE AND RE-ERECT STEEL BEAMS	21.000	EA
619(B) 2500	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
619(B) 4780	REMOVAL OF GUARDRAIL	236.000	LF
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	237.500	LF
623(G) 8571	GUARDRAIL END TREATMENT (GET)	2.000	EA
623(I) 8675	GUARDRAIL BRIDGE CONNECTION-TYPE A	2.000	EA

SECTION 0002 - BRIDGE 'B'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
411(B) 5940	SUPERPAVE, TYPE S3(PG 70-28 OK)	292.000	TON

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110052

SECTION 0002 - BRIDGE 'B'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
411(B) 5945	SUPERPAVE, TYPE S3(PG 64-22 OK)	340.000	TON
411(C) 5955	SUPERPAVE, TYPE S4(PG 70-28 OK)	146.000	TON
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	170.000	TON
501(G) 6309	CLSM BACKFILL	29.000	CY
504(A) 1304	APPROACH SLAB	137.800	SY
504(B) 1305	SAW-CUT GROOVING	461.100	SY
504(C) 6250	SEALED EXPANSION JOINT	64.400	LF
504(D) 6245	CONCRETE RAIL (TR4)	151.340	LF
506(A) 1322	STRUCTURAL STEEL	2896.000	LB
507(A) 6164	FIXED BEARING ASSEMBLY	15.000	EA
507(A) 6165	EXPANSION BEARING ASSEMBLY	15.000	EA
509(A) 1326	CLASS AA CONCRETE	94.000	CY
509(D) 1331	CLASS C CONCRETE	2.000	CY
511(B) 6010	EPOXY COATED REINFORCING STEEL	24350.000	LB
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	225.000	SY
520(A) 6058	PREPARATION OF CRACKS, ABOVE WATER	16.000	LF
520(C) 6060	EPOXY RESIN, ABOVE WATER	0.500	GAL
535 6280	REMOVE AND RE-ERECT STEEL BEAMS	15.000	EA
619(B) 2500	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
619(B) 4780	REMOVAL OF GUARDRAIL	236.000	LF
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	237.500	LF
623(G) 8571	GUARDRAIL END TREATMENT (GET)	2.000	EA
623(I) 8675	GUARDRAIL BRIDGE CONNECTION-TYPE A	2.000	EA

SECTION 0003 - TRAFFIC

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	14160.000	LF
857(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	12320.000	LF
857(C) 8851	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	1440.000	LF
857(F) 8006	PAVEMENT MRKNG.REMOVAL(TRAFF.STRP)	20660.000	LF
870(A) 8485	SAND FILLED IMPACT ATTEN.MODULE	480.000	SD
876(A) 8482	(PL)TRUCK MOUNTED ATTENUATOR	5.000	SD
877(B) 8484	DELIVER PORTABLE LONGITUDINAL BARRIER	2454.000	LF
877(C) 8486	RELOCATION OF PORTABLE LONGITUDINAL BARR	2454.000	LF
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	2400.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1440.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2880.000	SD
880(C) 8842	CONSTRUCTION BARRICADES(TYPE III)	720.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	1440.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	22800.000	SD
880(F) 8878	DRUMS	22800.000	SD

OKLAHOMA DEPARTMENT OF TRANSPORTATION**STATE PROJECT****CONTRACT ID: 110052****SECTION 0003 - TRAFFIC**

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
882(A) 8306	PORT.CHANGEABLE MESSAGE SIGN	720.000	SD

SECTION 0004 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
641 1399	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110009

CALL ORDER: 210
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: CUSTER

PROJECT(S) : PCN
 CIRB-120C(157)RB 2486204
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$14.09
 120 CALENDAR DAYS
 RES. ENG.: DIVISION 5 (CLINTON)

CONTRACT DESCRIPTION
 BRIDGE AND APPROACHES
 COUNTY ROAD (NS-208); OVER PANTHER CREEK, 3.0 MILES SOUTH OF
 THE SH-33 JUNCTION.
 PROJECT LENGTH = 0.210 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(C) 0184	UNCLASSIFIED BORROW	4703.000	CY
202(G) 0185	EARTHWORK	1.000	LSUM
223 2801	TEMPORARY SILT FENCE	1000.000	LF
230(A) 2806	SOLID SLAB SODDING	14000.000	SY
233(A) 2817	VEGETATIVE MULCHING	2.890	AC
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	530.000	TON
509(D) 0325	CLASS C CONCRETE	58.600	CY
613(CC) 7187	TYPE B4 CULVERT END TREATMENT	2.000	EA
613(CC) 7189	TYPE D4 CULVERT END TREATMENT	2.000	EA
613(D) 0692	36" CORR. GALV. STEEL PIPE	128.000	LF
613(D) 4528	28" X 20" CORR. GALV. STEEL PIPE ARCH	58.000	LF
850(A) 8110	SHEET ALUMINUM SIGNS	15.460	SF
851(D) 8597	FLANGE CHANNEL POSTS(4 LB/FT)	24.000	LF

SECTION 0002 - BRIDGE 'A'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	84.000	CY
501(D) 6353	UNCLASSIFIED BACKFILL	82.000	CY
503(A) 1313	PRESTRESSED CONCRETE BEAMS (TYPE IV)	416.670	LF
504(E) 1380	CONCRETE RAIL (TR1)	275.000	LF
506(A) 1322	STRUCTURAL STEEL	1810.000	LB
509(A) 1326	CLASS AA CONCRETE	80.600	CY
509(B) 1328	CLASS A CONCRETE	53.800	CY
511(A) 1332	REINFORCING STEEL	25429.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	216.000	LF
514(A) 6011	PILES, FURNISHED (HP 12X53)	931.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	216.000	LF
514(B) 6294	PILES, DRIVEN (HP 12X53)	931.000	LF
601(A-1)1353	TYPE I-A PLAIN RIPRAP	1880.000	TON

OKLAHOMA DEPARTMENT OF TRANSPORTATION**STATE PROJECT****CONTRACT ID: 110009****SECTION 0002 - BRIDGE 'A'**

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
601(A-2)1355	TYPE I-A FILTER BLANKET	516.000	TON
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0003 - STAKING

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
642 0098	STAKING	1.000	LSUM

SECTION 0004 - CONSTRUCTION

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
220 2800	(SP)SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
641 1399	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**STATE PROJECT**

CONTRACT ID: 110056

CALL ORDER: 220
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: DELAWARE

<u>PROJECT(S) :</u>	<u>PCN</u>
SSR-121C(144)SR	2760704
SSR-121C(149)SR	2761504

DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
90 CALENDAR DAYS
RES. ENG.: DIVISION 8 (TULSA)

CONTRACT DESCRIPTION

RESURFACE (ASPHALT)

SH-20: FROM 10.0 MILES EAST OF THE SH-10 JCT, EXTEND NORTH.

SH-10: FROM THE ADAIR COUNTY LINE, EXTEND NORTH.

PROJECT LENGTH = 9.18 MILES

SECTION 0001 - ROADWAY - SSR-121C(144)SR

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
411(C) 5955	SUPERPAVE, TYPE S4(PG 70-28 OK)	6898.000	TON
412 5267	COLD MILLING PAVEMENT	81758.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	122074.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	180.000	HOUR

SECTION 0002 - ROADWAY - SSR-121C(149)SR

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
411(C) 5955	SUPERPAVE, TYPE S4(PG 70-28 OK)	5211.000	TON
412 5267	COLD MILLING PAVEMENT	46323.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	69485.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	360.000	HOUR

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110057

CALL ORDER: 230
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: DELAWARE

PROJECT(S) :	PCN
SSR-121B(145)SR	2760904
SSR-121B(146)SR	2761004
SSR-121B(147)SR	2761204

DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 150 CALENDAR DAYS
 RES. ENG.: DIVISION 8 (TULSA)

CONTRACT DESCRIPTION
 RESURFACE (ASPHALT)
 US-59: FROM THE US-412A JUNCTION, EXTEND NORTH.
 PROJECT LENGTH = 17.24 MILES

SECTION 0001 - ROADWAY - SSR-121B(145)SR

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	658.000	TON
411(C) 5950	SUPERPAVE, TYPE S4(PG 76-28 OK)	6817.000	TON
412 5267	COLD MILLING PAVEMENT	986.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	99475.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	180.000	HOUR

SECTION 0002 - ROADWAY - SSR-121B(146)SR

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	592.000	TON
411(C) 5950	SUPERPAVE, TYPE S4(PG 76-28 OK)	6952.000	TON
412 5267	COLD MILLING PAVEMENT	11475.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	96518.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	2.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	1.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	180.000	HOUR

SECTION 0003 - ROADWAY - SSR-121B(147)SR

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	1117.000	TON
411(C) 5950	SUPERPAVE, TYPE S4(PG 76-28 OK)	11412.000	TON
412 5267	COLD MILLING PAVEMENT	986.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	167904.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	180.000	HOUR

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 110060

CALL ORDER: 260
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: DELAWARE

PROJECT(S) : PCN
STPY-121B(148)3P 2761304
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
70 CALENDAR DAYS
RES. ENG.: DIVISION 8 (TULSA)

CONTRACT DESCRIPTION
RESURFACE (ASPHALT)
US-59: FROM THE SH-20 WEST JUNCTION, EXTEND NORTH.
PROJECT LENGTH = 1.71 MILES

SECTION 0001 - ROADWAY

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
411(C) 5950	SUPERPAVE, TYPE S4(PG 76-28 OK)	8195.000	TON
412 5267	COLD MILLING PAVEMENT	52976.000	SY
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	38227.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	6.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	4.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	360.000	HOURL

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110025

CALL ORDER: 280
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: DEWEY
 BLAINE

PROJECT(S) :	PCN
STPY-122C(078)3P	2746804
STPY-122C(079)3P	2746805

DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 60 CALENDAR DAYS
 RES. ENG.: DIVISION 5 (CLINTON)

CONTRACT DESCRIPTION
 RESURFACE (ASPHALT)
 SH-51: FROM THE US-270 JUNCTION, EXTEND EAST.
 PROJECT LENGTH = 12.95 MILES

SECTION 0001 - ROADWAY STPY-122C(078)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	22248.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	3500.000	SY
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	151384.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0002 - ROADWAY STPY-122C(079)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	13545.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	2334.000	SY
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	83572.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110069

CALL ORDER: 290
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: GRADY

PROJECT(S) : PCN
 SSP-126N(177)SS 2703504
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$26.01
 90 CALENDAR DAYS
 RES. ENG.: DIVISION 7 (DUNCAN)

CONTRACT DESCRIPTION
 WIDEN AND RESURFACE (ASPHALT)
 US-81: FROM 1.5 MILES NORTH OF SH-19E, EXTEND NORTH.
 PROJECT LENGTH = 0.799 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
201(A) 0102	CLEARING AND GRUBBING	1.000	LSUM
202(D) 0184	UNCLASSIFIED BORROW	525.000	CY
205(A) 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
221(D) 2803	TEMPORARY SEDIMENT FILTER	1.000	EA
221(F) 0100	TEMPORARY SILT DIKE	184.000	LF
230(A) 2806	SOLID SLAB SODDING	3616.000	SY
232(B) 2814	SEEDING METHOD B	1.000	AC
241 2832	MOWING	2.000	AC
310(B) 0149	SUBGRADE, METHOD B	574.000	SY
407(B) 0250	TACK COAT	1468.000	GAL
411(B) 5935	SUPERPAVE, TYPE S3(PG 76-28 OK)	1782.000	TON
411(C) 5950	SUPERPAVE, TYPE S4(PG 76-28 OK)	1892.000	TON
412 5267	COLD MILLING PAVEMENT	17223.000	SY
414(B) 5725	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	174.000	SY
414(G) 5275	P.C. CONCRETE FOR PAVEMENT	58.000	CY
509(D) 0325	CLASS C CONCRETE	2.000	CY
609(A) 5864	CONC.CURB(6" BARRIER-DOWELLED)	7059.000	LF
609(B) 1501	1'-8" COMB.CRB.& GUT.(6" MNTBLE)	5168.000	LF
609(B) 1513	1'-8" COMB.CRB.& GUT.(6" BARRIER)	4056.000	LF
619(B) 4726	REMOVAL OF CURB AND GUTTER	11995.000	LF
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	449.000	SY
619(B) 4775	REMOVAL OF CONCRETE CURB OPENING	177.000	SY
619(B) 4791	REMOVAL OF CURB	765.000	LF
619(B) 6130	REMOVAL OF 4" CONCRETE DIVIDING STRIP	328.000	SY
619(C) 0924	SAWING PAVEMENT	18094.000	LF

SECTION 0002 - ADD ALT 1

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 0184	UNCLASSIFIED BORROW	525.000	CY
609(A) 5864	CONC.CURB(6" BARRIER-DOWELLED)	2071.000	LF
610(C) 0608	4" CONCRETE DIVIDING STRIP	2045.000	SY

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110069

SECTION 0002 - ADD ALT 1

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
619(C) 0924	SAWING PAVEMENT	6457.000	LF

SECTION 0003 - ADD ALT 2

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
610(J) 4810	(PL) STAMPED CONCRETE FINISH	2045.000	SY

SECTION 0004 - TRAFFIC CONTROL

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
857(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	7700.000	LF
857(E) 8887	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	3500.000	EA
876(A) 8482	(PL)TRUCK MOUNTED ATTENUATOR	120.000	SD
880(A) 8812	ARROW DISPLAY(TYPE C)	180.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	840.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	660.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	780.000	SD
880(C) 8842	CONSTRUCTION BARRICADES(TYPE III)	900.000	SD
880(C) 8848	WING BARRICADES	240.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	2520.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	1500.000	SD
880(F) 8878	DRUMS	1500.000	SD
880(G) 8890	CHANNELIZER CONES	6000.000	SD
882(A) 8306	PORT.CHANGEABLE MESSAGE SIGN	60.000	SD

SECTION 0005 - TRAFFIC STRIPING & SIGNALS

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
804(A) 2915	STRUCTURAL CONCRETE	3.100	CY
804(B) 2916	REINFORCING STEEL	477.100	LB
805(A) 8726	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
805(D) 8756	(PL)REMOVE & RESET EXISTING SIGNS	1.000	EA
806(A) 8329	32'MH POLE 50'TS & 15'LMA(G.STL.)	1.000	EA
809(A) 8090	ROADWAY LUMINAIRE	1.000	EA
811 8044	1/C NO.10 ELECT.COND.	750.000	LF
828 8132	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
831 8231	1WAY3SEC.ADJ.SIG.HD.S-6	3.000	EA
831 8252	1WAY3SEC.ADJ.SIG.HD.S-9	1.000	EA
833 3030	BACKPLATE	4.000	EA
834(A) 8207	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	580.000	LF
834(A) 8209	9/C TRAFFIC SIGNAL ELECTRICAL CABLE	360.000	LF
850(C) 8118	MAST ARM MOUNTED SIGNS(ALUM.)	5.000	SF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	7246.000	LF
855(A) 8814	TRAFFIC STRIPE(PLASTIC)(8" WIDE)	820.000	LF
855(A) 8825	TRAFFIC STRIPE(PLASTIC)(24" WIDE)	85.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	3.000	EA

OKLAHOMA DEPARTMENT OF TRANSPORTATION**STATE PROJECT****CONTRACT ID: 110069****SECTION 0006 - STAKING**

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

SECTION 0007 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
641 1552	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110027

CALL ORDER: 300
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: HARMON

PROJECT(S) : PCN
 NHY-020N(036)3P 2751704
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 65 CALENDAR DAYS
 RES. ENG.: DIVISION 5 (CLINTON)

CONTRACT DESCRIPTION
 RESURFACE (ASPHALT)
 US-62: FROM 1.0 MILE EAST OF THE SH-30 JUNCTION, EXTEND
 EAST.
 PROJECT LENGTH = 8.00 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	20948.500	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	6067.000	SY
619(B) 4780	REMOVAL OF GUARD RAIL	400.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	550.000	LF
623(E) 7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	8.000	EA
623(F) 5686	GUARD RAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	12.000	EA
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	110214.000	LF
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	2600.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
884(B) 8421	(PL)CONC.BRIDGE PARAPET RETROFIT	150.000	LF
884(C) 8424	REMOVE BRIDGE RAIL & POSTS(CONC.)	150.000	LF

SECTION 0002 - ADD ALT. 1

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	2293.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	1672.000	SY
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	8918.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110010

CALL ORDER: 310
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: WOODWARD
 BEAVER

PROJECT(S) : PCN
 SSP-104C(080)SS 2422504
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$9.75
 45 CALENDAR DAYS
 RES. ENG.: DIVISION 6 (BUFFALO)

CONTRACT DESCRIPTION
 JOINT SEAL/REPAIR
 US-270/SH-50: AT MULTIPLE LOCATIONS IN DIVISIONS VI.

SECTION 0001 - BRIDGE 'A'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
426(A) 5095	CORED HOLES	10.000	EA
426(B) 5096	PORTLAND CEMENT	2.000	TON
426(C) 5097	FLY ASH	2.000	TON
509 6386	(PL)SILICONE CONSTRUCTION JOINT	101.000	LF

SECTION 0002 - BRIDGE 'B'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
426(A) 5095	CORED HOLES	5.000	EA
426(B) 5096	PORTLAND CEMENT	1.000	TON
426(C) 5097	FLY ASH	1.000	TON
504(H) 6390	RAPID CURE JOINT SEALANT	113.000	LF
509 6386	(PL)SILICONE CONSTRUCTION JOINT	113.000	LF

SECTION 0003 - BRIDGE 'C'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
505(B) 6019	CLASS B BRIDGE DECK REPAIR	15.000	SY
509 6386	(PL)SILICONE CONSTRUCTION JOINT	89.000	LF

SECTION 0004 - BRIDGE 'D'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
504(H) 6390	RAPID CURE JOINT SEALANT	56.000	LF
504(I) 6389	ELASTOMERIC MORTAR	7.000	CF
509 6386	(PL)SILICONE CONSTRUCTION JOINT	112.000	LF

SECTION 0005 - BRIDGE 'E'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
509 6386	(PL)SILICONE CONSTRUCTION JOINT	1008.000	LF

SECTION 0006 - TRAFFIC

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0007 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
641 1399	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110079

CALL ORDER: 320
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: KAY

PROJECT(S) : PCN
 NHY-018N(055)3P 1164304
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 90 CALENDAR DAYS
 RES. ENG.: DIVISION 4 (PERRY)

CONTRACT DESCRIPTION
 RESURFACE (ASPHALT)
 US-60: FROM 1.66 MILES EAST OF US-177, EXTEND EAST.
 PROJECT LENGTH = 6.38 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 4781	UNCLASSIFIED BORROW (TOPSOIL)	4000.000	CY
230(A) 2806	SOLID SLAB SODDING	3000.000	SY
303(A) 2100	AGGREGATE BASE TYPE A	400.000	CY
411(B) 5945	SUPERPAVE, TYPE S3(PG 64-22 OK)	2000.000	TON
411(C) 5955	SUPERPAVE, TYPE S4(PG 70-28 OK)	20800.000	TON
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	12800.000	TON
411(E) 5990	SUPERPAVE, TYPE S6(PG 64-22 OK)	8300.000	TON
412 5267	COLD MILLING PAVEMENT	116000.000	SY
413(A) 4861	RUMBLE STRIP-METHOD HMA-CON	114000.000	LF
613(A) 0492	24" R.C.PIPES CLASS III	10.000	LF
613(O) 4375	SP. END SECTION OF 24" RCP ROUND	1.000	EA
619(B) 0291	REMOVAL OF HEADWALL	1.000	EA

SECTION 0002 - BRIDGE

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
504(G) 6390	RAPID CURE JOINT SEALANT	5516.000	LF
504(H) 6389	ELASTOMERIC MORTAR	804.000	CF
513(B) 6019	CLASS B BRIDGE DECK REPAIR	200.000	SY
513(C) 6020	CLASS C BRIDGE DECK REPAIR	20.000	SY

SECTION 0003 - TRAFFIC

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110081

CALL ORDER: 330
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: KAY

PROJECT(S) : PCN
 STPY-136A(208)3P 2824604
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 60 CALENDAR DAYS
 RES. ENG.: DIVISION 4 (PERRY)

CONTRACT DESCRIPTION
 RESURFACE (ASPHALT)
 US-60B: FROM ASH STREET, EXTEND EAST IN PONCA CITY.
 PROJECT LENGTH = 1.21 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
411(B) 5945	SUPERPAVE, TYPE S3(PG 64-22 OK)	50.000	TON
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	3900.000	TON
412 5267	COLD MILLING PAVEMENT	48000.000	SY
609(B) 1525	2'-8" COMB.CRB.& GUT.(6" BARRIER)	400.000	LF
610(A) 0602	4" CONCRETE SIDEWALK	450.000	SY
610(I) 4610	TACTILE WARNING DEVICE-NEW	200.000	SF
612(A) 0641	MANHOLES ADJUST TO GRADE	1.000	EA
612(C) 0645	INLET ADJUST TO GRADE	2.000	EA
612(E) 0647	VALVE BOXES ADJUST TO GRADE	12.000	EA
619(B) 4726	REMOVAL OF CURB AND GUTTER	400.000	LF
619(B) 4763	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	10.000	SY
619(B) 4792	REMOVAL OF SIDEWALK	350.000	SY

SECTION 0002 - TRAFFIC

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
828(B) 8136	LOOP DETECTOR WIRE	8000.000	LF
854(B) 8809	TRAFFIC STRIPE(PAINT)(SYMBOLS)	8.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	20000.000	LF
855(A) 8813	TRAFFIC STRIPE(PLASTIC)(6" WIDE)	5000.000	LF
855(A) 8825	TRAFFIC STRIPE(PLASTIC)(24" WIDE)	3000.000	LF
855(B) 8824	TRAFFIC STRIPE(PLASTIC)(SYMBOLS)	4.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 110161

CALL ORDER: 342
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: KIOWA
WASHITA

<u>PROJECT(S) :</u>	<u>PCN</u>
STPY-175C(128)3P	2814404
STPY-138C(186)3P	2832104

DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
60 CALENDAR DAYS
RES. ENG.: DIVISION 5 (CLINTON)

CONTRACT DESCRIPTION
RESURFACE (ASPHALT)
SH-54: FROM THE SH-9 JUNCTION, EXTEND NORTH.
PROJECT LENGTH = 15.36 MILES

SECTION 0001 - ROADWAY - STPY-175C(128)3P

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	17858.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	4000.000	SY
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	151444.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0002 - ROADWAY - STPY-138C(186)3P

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	16448.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	6000.000	SY
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	121212.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 110028

CALL ORDER: 350
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: LOGAN

PROJECT(S) : PCN
STP-142C(176)AG 2569504
DBE GOALS : 4.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$3.25
60 CALENDAR DAYS
RES. ENG.: DIVISION 4 (PERRY)

CONTRACT DESCRIPTION
RESURFACE (ASPHALT)
CITY STREET (WESTERN AVE): FROM WATERLOO ROAD, EXTEND
NORTH IN THE TOWN OF SEWARD.
PROJECT LENGTH = 3.50 MILES

SECTION 0001 - ROADWAY

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
230(A) 2806	SOLID SLAB SODDING	10500.000	SY
303 0192	AGGREGATE BASE	1800.000	CY
327(A) 4200	(SP)FLY ASH	370.000	TON
327(E) 4240	(SP)CEMENTITIOUS STABILIZED SUBGRADE	6674.000	SY
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	500.000	TON
408 5774	PRIME COAT	1050.000	GAL
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	1140.000	TON
411(S3) 6210	(SP)ASPH.CONC.,TYPE S3(PATCH)(PG64-22OK)	750.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	7795.000	TON
417 5267	COLD MILLING PAVEMENT	600.000	SY
619(C) 0924	SAWING PAVEMENT	800.000	LF
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	36960.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0002 - CONSTRUCTION

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
641 1399	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110092

CALL ORDER:	370	PROJECT(S) :	<u>PCN</u>
LETTING DATE:	January 20, 2011	STPY-142C(211)3P	2824004
LETTING TIME:	10:30 A.M.	STPY-142C(212)3P	2824504
COUNTIES:	LOGAN	STPY-142C(213)3P	2825404

DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 100 CALENDAR DAYS
 RES. ENG.: DIVISION 4 (PERRY)

CONTRACT DESCRIPTION

RESURFACE (ASPHALT)
 US-77:FROM 4.0 MILES SOUTH OF THE SH-51 JUNT, EXTEND NORTH.
 SH-74F: FROM 4.9 MILES WEST OF SH-74 JCT., EXT EAST.
 SH-51: FROM 5.6 MILES EAST OF THE SH-74 JCT., EXTEND EAST.
 PROJECT LENGTH = 14.59 MILES

SECTION 0001 - ROADWAY - STPY-142C(211)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 4781	UNCLASSIFIED BORROW (TOPSOIL)	1500.000	CY
407(C) 0300	POLYMER MODIFIED CATIONIC RAPID SET - 1	14200.000	GAL
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	6300.000	TON
412 5267	COLD MILLING PAVEMENT	1000.000	SY

SECTION 0002 - TRAFFIC - STPY-142C(211)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0003 - ROADWAY (STPY-142C(212)3P)

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 4781	UNCLASSIFIED BORROW (TOPSOIL)	500.000	CY
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	7000.000	TON
412 5267	COLD MILLING PAVEMENT	600.000	SY

SECTION 0004 - TRAFFIC STPY-142C(212)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0005 - ROADWAY - STPY-142C(213)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 4781	UNCLASSIFIED BORROW (TOPSOIL)	1500.000	CY
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	9900.000	TON
412 5267	COLD MILLING PAVEMENT	5000.000	SY

SECTION 0006 - TRAFFIC - STPY-142C(213)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
805(A) 8702	REMOVAL OF CLASS C PAVEMENT MARKERS	220.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110099

CALL ORDER: 400
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: MCCURTAIN

PROJECT(S) : PCN
 SBR-145C(169)SB 2474305
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$21.68
 90 CALENDAR DAYS
 RES. ENG.: BRENT FRANK, ANTLERS

CONTRACT DESCRIPTION
 BRIDGE REHABILITATION
 SH-37: OVER WATERHOLE CREEK, 6.2 MILES EAST OF THE
 OKLAHOMA/TEXAS STATE LINE.

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
201 0102	CLEARING AND GRUBBING	1.000	LSUM
202(C) 0184	UNCLASSIFIED BORROW	3960.000	CY
205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223 2801	TEMPORARY SILT FENCE	880.000	LF
227 0100	TEMPORARY SILT DIKE	60.000	LF
230(A) 2806	SOLID SLAB SODDING	2540.000	SY
303 0192	AGGREGATE BASE	220.000	CY
408 5774	PRIME COAT	340.000	GAL
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	130.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	242.000	TON
417 5267	COLD MILLING PAVEMENT	536.000	SY
509(D) 0325	CLASS C CONCRETE	5.000	CY
613(D) 0690	24" CORR. GALV. STEEL PIPE	30.000	LF
613(M) 5730	24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	200.000	LF
623(E) 7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	4.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	4.000	EA

SECTION 0002 - BRIDGE "A"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	60.000	CY
501(G) 6309	CLSM BACKFILL	42.000	CY
502 6116	(PL)FALSEWORK JACKING	1.000	LSUM
504(A) 1304	APPROACH SLAB	187.400	SY
504(C) 6250	SEALED EXPANSION JOINT	43.200	LF
504(E) 6245	CONCRETE RAIL (TR4)	282.400	LF
506(A) 1322	STRUCTURAL STEEL	25580.000	LB
509(A) 1326	CLASS AA CONCRETE	115.100	CY
509(B) 1328	CLASS A CONCRETE	51.400	CY
511(B) 6010	EPOXY COATED REINFORCING STEEL	33350.000	LB
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110099

SECTION 0002 - BRIDGE "A"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
514(A) 6012	PILES, FURNISHED (HP 14X73)	250.000	LF
514(B) 6296	PILES, DRIVEN (HP 14X73)	250.000	LF
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	356.000	SY
523(A) 6550	(SP) SEALER CRACK PREPARATION	142.000	LF
523(B) 6560	(SP) SEALER RESIN	3.000	GAL
535 6164	(PL)FIXED BEARING ASSEMBLY	14.000	EA
535 6165	(PL)EXPANSION BEARING ASSEMBLY	28.000	EA
601(A) 1351	TYPE I PLAIN RIPRAP	260.000	TON
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

SECTION 0003 - TRAFFIC

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
627(G) 4316	RELOC.PORT.TYPE PRECAST CONC.MEDIAN BARR	750.000	LF
627(H) 5856	DEL.PORT.TYPE PREC. CONCRETE MEDIAN BARR	1500.000	LF
823 8478	(PL)PORTABLE TRAFFIC SIGNAL SYSTEM	90.000	SD
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	1850.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0004 - STAKING

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
642 0098	STAKING	1.000	LSUM

SECTION 0005 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
641 1399	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 110100

CALL ORDER: 410
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: MCCURTAIN

PROJECT(S) : PCN
 NHY-022N(204)3P 2819704
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 75 CALENDAR DAYS
 RES. ENG.: DIVISION 2 (ANTLERS)

CONTRACT DESCRIPTION
 PAVEMENT REHABILITATION (ASPHALT)
 US-70: FROM 13.5 MILES EAST OF THE CHOCTAW COUNTY LINE,
 EXTEND EAST.
 PROJECT LENGTH = 6.004 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	1125.000	TON
407(B) 0250	TACK COAT	6655.000	GAL
407(C) 0300	POLYMER MODIFIED CATIONIC RAPID SET - 1	19165.000	GAL
410(A) 6530	(SP)HOT-IN-PLACE RECYCLED ASPH CONCRETE	88978.000	SY
410(B) 6540	(SP)HOT-IN PLACE ASPHALT EMULSION	399.000	TON
411(D) 5975	SUPERPAVE, TYPE S5(PG 64-22 OK)	5451.000	TON
411(F) 6100	STONE MATRIX ASPHALT	13416.000	TON
412 5267	COLD MILLING PAVEMENT	2500.000	SY

SECTION 0002 - TRAFFIC

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	75000.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	18.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0003 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
641 1552	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110102

CALL ORDER: 420
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: MURRAY

PROJECT(S) : PCN
 SBR-150N(082)SB 2633104
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$24.93
 150 CALENDAR DAYS
 RES. ENG.: DIVISION 7 (DUNCAN)

CONTRACT DESCRIPTION
 BRIDGE REHABILITATION
 I-35: OVER SH-77D, 4.8 MILES NORTH OF THE CARTER
 COUNTY LINE.

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	102.000	TON
619(B) 4780	REMOVAL OF GUARD RAIL	183.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	100.000	LF
623(E) 7114	THRIE BEAM BRIDGE CONNECTION-TYPE A	2.000	EA

SECTION 0002 - BRIDGE "A"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
501(G) 6309	CLSM BACKFILL	28.000	CY
502 6116	(PL)FALSEWORK JACKING	1.000	LSUM
504 6179	(PL)BRIDGE TRAFFIC RAIL	440.000	LF
504(A) 1304	APPROACH SLAB	352.190	SY
504(C) 6250	SEALED EXPANSION JOINT	117.000	LF
505(B) 6019	CLASS B BRIDGE DECK REPAIR	15.000	SY
505(C) 6020	CLASS C BRIDGE DECK REPAIR	8.000	SY
506(A) 1322	STRUCTURAL STEEL	1925.000	LB
509(A) 1326	CLASS AA CONCRETE	146.420	CY
511(B) 6010	EPOXY COATED REINFORCING STEEL	56846.340	LB
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION & HANDLING OF WASTE	1.000	LSUM
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	511.000	SY
520(A) 6058	PREPARATION OF CRACKS ABOVE WATER	25.000	LF
520(C) 6060	EPOXY RESIN ABOVE WATER	2.500	GAL
540 4515	(PL)REPAIR BRIDGE ITEM (TYPE A)	2.000	EA
540 4525	(PL)REPAIR BRIDGE ITEM (TYPE B)	7.000	EA
619(B) 2500	(PL)REMOVAL OF BRIDGE ITEMS	1.000	LSUM

SECTION 0003 - TRAFFIC

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
627(O) 4410	REL.OF RENTED PORT.PREC.CONC.MED.BARRIER	754.000	LF
627(P) 4425	RENTED PORT.TYPE PREC.CONC.MED. BARR.	754.000	LF
823 8478	(PL)PORTABLE TRAFFIC SIGNAL SYSTEM	150.000	SD
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	12312.000	LF

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110102

SECTION 0003 - TRAFFIC

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
855(A) 8813	TRAFFIC STRIPE(PLASTIC)(6" WIDE)	252.000	LF
856(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	2850.000	LF
856(C) 8851	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	4240.000	LF
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAFF.STRP)	12564.000	LF
870(A) 8485	SAND FILLED IMPACT ATTEN.MODULE	150.000	SD
876(C) 8482	(PL)TRUCK MOUNTED ATTENUATOR	5.000	SD
880(A) 8806	ARROW DISPLAY(TYPE B)	375.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	2100.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	900.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3300.000	SD
880(C) 8842	BARRICADES(TYPE III)	1350.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	2700.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	12750.000	SD
880(F) 8878	DRUMS	12750.000	SD
880(G) 8884	TUBE CHANNELIZERS	500.000	SD
880(I) 8902	FLAGGER	20.000	SD
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	15.000	HOURL
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	450.000	SD

SECTION 0004 - STAKING

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
642 0098	STAKING	1.000	LSUM

SECTION 0005 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
641 1399	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110103

CALL ORDER: 430
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: MUSKOGEE

PROJECT(S) : PCN
 SBR-151A(229)SB 2799404
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$59.61
 120 CALENDAR DAYS
 RES. ENG.: DIVISION 1 (MUSKOGEE)

CONTRACT DESCRIPTION
 BRIDGE REHABILITATION
 US-62: OVER THE MK&T RAILROAD, 3.2 MILES EAST OF THE US-69
 JUNCTION.

SECTION 0001 - ROADWAY BRIDGE "A"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
411(C) 5950	SUPERPAVE, TYPE S4(PG 76-28 OK)	266.000	TON
412 5267	COLD MILLING PAVEMENT	845.000	SY
619(B) 4780	REMOVAL OF GUARDRAIL	200.000	LF
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	300.000	LF
623(G) 8571	GUARDRAIL END TREATMENT (GET)	2.000	EA
623(I) 8675	GUARDRAIL BRIDGE CONNECTION-TYPE A	2.000	EA

SECTION 0002 - BRIDGE "A"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	36.700	CY
501(G) 6309	CLSM BACKFILL	12.000	CY
504(A) 1304	APPROACH SLAB	326.800	SY
504(B) 1305	SAW-CUT GROOVING	1546.000	SY
504(C) 6250	SEALED EXPANSION JOINT	138.000	LF
504(E) 6190	42" F-SHAPED PARAPET	927.700	LF
506(A) 1322	STRUCTURAL STEEL	500.000	LB
509(A) 1326	CLASS AA CONCRETE	327.200	CY
509(D) 1331	CLASS C CONCRETE	36.700	CY
511(B) 6010	EPOXY COATED REINFORCING STEEL	107462.000	LB
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	414.000	SY
520(A) 6058	PREPARATION OF CRACKS, ABOVE WATER	114.000	LF
520(C) 6060	EPOXY RESIN, ABOVE WATER	3.800	GAL
521(A) 6210	PNEUMATICALLY PLACED MORTAR	17.200	SY
524(A) 6610	(SP)CARBON FIBER-REINFORCED POLYMER	139.500	SF
535 6130	(SP)CORROSION INHIBITOR(SURFACE APPLIED)	15.500	SY
540 4515	(PL)REPAIR BRIDGE ITEM (TYPE A)	18.000	EA
540 4525	(PL)REPAIR BRIDGE ITEM (TYPE B)	1.000	EA
542 4600	(PL)INSTALLATION OF BRIDGE ITEMS	1.000	LSUM
619(B) 2500	REMOVAL OF BRIDGE ITEMS	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110103

SECTION 0003 - BRIDGE "B"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	22.600	CY
501(G) 6309	CLSM BACKFILL	12.000	CY
504(C) 6250	SEALED EXPANSION JOINT	225.400	LF
504(E) 1381	CONCRETE PARAPET	70.000	LF
504(G) 6390	RAPID CURE JOINT SEALANT	247.200	LF
506(A) 1322	STRUCTURAL STEEL	500.000	LB
509(D) 1331	CLASS C CONCRETE	45.300	CY
511(B) 6010	EPOXY COATED REINFORCING STEEL	5960.000	LB
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
513(A) 6018	CLASS A BRIDGE DECK REPAIR	37.000	SY
513(B) 6019	CLASS B BRIDGE DECK REPAIR	37.000	SY
513(C) 6020	CLASS C BRIDGE DECK REPAIR	165.200	SY
520(A) 6058	PREPARATION OF CRACKS, ABOVE WATER	43.200	LF
520(C) 6060	EPOXY RESIN, ABOVE WATER	1.500	GAL
521(A) 6210	PNEUMATICALLY PLACED MORTAR	65.100	SY
523(C) 6570	DECK AREA SEALED (FLOODCOATS)	1776.200	SY
524(A) 6610	(SP)CARBON FIBER-REINFORCED POLYMER	350.300	SF
535 6130	(SP)CORROSION INHIBITOR(SURFACE APPLIED)	39.000	SY
540 4515	(PL)REPAIR BRIDGE ITEM (TYPE A)	64.000	EA
540 4525	(PL)REPAIR BRIDGE ITEM (TYPE B)	5.000	EA

SECTION 0004 - TRAFFIC CONTROL BRIDGE "A"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
857(C) 8851	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	8565.000	LF
857(F) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	3480.000	LF
870(A) 8485	SAND FILLED IMPACT ATTEN.MODULE	120.000	SD
877(A) 8483	PORTABLE LONGITUDINAL BARRIER	1150.000	LF
877(C) 8486	RELOCATION OF PORTABLE LONGITUDINAL BARR	1150.000	LF
880(A) 8812	ARROW DISPLAY(TYPE C)	120.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	960.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	780.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2400.000	SD
880(C) 8842	CONSTRUCTION BARRICADES(TYPE III)	1500.000	SD
880(D) 8854	VERTICAL PANELS	3120.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	1680.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	3600.000	SD
880(F) 8878	DRUMS	6240.000	SD
882(A) 8306	PORT.CHANGEABLE MESSAGE SIGN	120.000	SD

SECTION 0005 - TRAFFIC CONTROL BRIDGE "B"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
857(C) 8851	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	5240.000	LF

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110103

SECTION 0005 - TRAFFIC CONTROL BRIDGE "B"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
857(F) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	2650.000	LF
870(A) 8485	SAND FILLED IMPACT ATTEN.MODULE	120.000	SD
877(A) 8483	PORTABLE LONGITUDINAL BARRIER	840.000	LF
877(C) 8486	RELOCATION OF PORTABLE LONGITUDINAL BARR	840.000	LF
880(A) 8812	ARROW DISPLAY(TYPE C)	120.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	840.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	480.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2400.000	SD
880(C) 8842	CONSTRUCTION BARRICADES(TYPE III)	960.000	SD
880(D) 8854	VERTICAL PANELS	1920.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	1680.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	2580.000	SD
880(F) 8878	DRUMS	3540.000	SD
882(A) 8306	PORT.CHANGEABLE MESSAGE SIGN	120.000	SD

SECTION 0006 - TRAFFIC SIGNING AND STRIPING BRIDGE "A"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	8485.000	LF

SECTION 0007 - TRAFFIC SIGNING AND STRIPING BRIDGE "B"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	5230.000	LF

SECTION 0008 - STAKING

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
642(B) 0096	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

SECTION 0009 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
641 1399	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110112

CALL ORDER: 440
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: NOBLE

PROJECT(S) : PCN
 STPY-152C(185)3P 2735904
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 90 CALENDAR DAYS
 RES. ENG.: DIVISION 4 (PERRY)

CONTRACT DESCRIPTION
 RESURFACE (ASPHALT)
 US-64: FROM THE US-177 JUNCTION, EXTEND EAST.
 PROJECT LENGTH = 8.00 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 4781	UNCLASSIFIED BORROW (TOPSOIL)	2000.000	CY
202(H) 0185	EARTHWORK	1.000	LSUM
230(A) 2806	SOLID SLAB SODDING	1400.000	SY
411(B) 5945	SUPERPAVE, TYPE S3(PG 64-22 OK)	280.000	TON
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	12000.000	TON
411(E) 5990	SUPERPAVE, TYPE S6(PG 64-22 OK)	4500.000	TON
412 5267	COLD MILLING PAVEMENT	13000.000	SY
414(B) 5725	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	800.000	SY
414(G) 5275	P.C. CONCRETE FOR PAVEMENT	200.000	CY
415 6300	CONCRETE JOINT SEALING	20000.000	LF
509(C) 0322	CLASS A CONCRETE, SMALL STRUCTURES	3.000	CY
511(A) 0332	REINFORCING STEEL	300.000	LB
609(A) 0300	CONC.CURB(6" BARRIER-INTEGRAL)	300.000	LF
613(N) 7501	TYPE B4 SLOPED CONCRETE END SECTION	1.000	EA
619(B) 0291	REMOVAL OF HEADWALL	1.000	EA
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	800.000	SY
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	100.000	LF
623(C) 5202	BEAM GUARDRAIL THRIE-BEAM SINGLE	100.000	LF
623(D) 5203	BEAM GUARDRAIL THRIE-BEAM DOUBLE	50.000	LF
623(E) 7113	BEAM GUARDRAIL TRANSITION SECTION	4.000	EA
623(G) 8571	GUARDRAIL END TREATMENT (GET)	4.000	EA

SECTION 0002 - TRAFFIC

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
623(H) 0940	GUARDRAIL BLOCKOUT REPLACEMENT	375.000	LF
853 9069	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	72.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
884(C) 8427	REMOVE BRIDGE RAIL & POSTS(STEEL)	54.000	LF

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 100615

CALL ORDER: 450
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: OKLAHOMA

PROJECT(S) : PCN
 IMY-0235-1(103)005IP 0903340
 DBE GOALS : 4.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$277.44
 365 CALENDAR DAYS
 TIME 'B' BID - \$ 10000 / DAY
 TIME 'C' BID - \$ 5000 / DAY
 TIME 'D' BID - \$ 5000 / DAY
 TIME 'E' BID - \$ 5000 / DAY
 RES. ENG.: DIVISION 4 (PERRY)

CONTRACT DESCRIPTION
 GRADE, DRAIN, SURFACE, AND BRIDGE
 I-235: ON THE SOUTHBOUND TO WESTBOUND OFF RAMP, AT THE I-44
 INTERCHANGE.
 PROJECT LENGTH = 2.335 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
201 0102	CLEARING AND GRUBBING	1.000	LSUM
202(A) 0183	UNCLASSIFIED EXCAVATION	76125.770	CY
202(C) 0184	UNCLASSIFIED BORROW	18459.000	CY
205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223 2801	TEMPORARY SILT FENCE	3362.000	LF
224 2803	TEMPORARY SEDIMENT FILTER	15.000	EA
227 0100	TEMPORARY SILT DIKE	1300.000	LF
229 4318	DITCH LINER PROTECTION	4899.620	LF
230(A) 2806	SOLID SLAB SODDING	29951.000	SY
233(A) 2817	VEGETATIVE MULCHING	6.190	AC
235(C) 0102	(PL)ROCK FILTER DAM, TYPE 3	25.000	CY
241 2832	MOWING	99.600	AC
242 0400	(PL)STABILIZED CONSTRUCTION EXIT	2.000	EA
303 0192	AGGREGATE BASE	500.000	CY
327(K) 4300	(SP)STABILIZED SUBGRADE	43887.050	SY
407 0250	TACK COAT	1442.510	GAL
408 5774	PRIME COAT	6628.540	GAL
411(S2) 5930	(SP)ASPH.CONC.,TYPE S2(PG 64-22 OK)	399.110	TON
411(S3) 5935	(SP)ASPH.CONC.,TYPE S3(PG 76-28 OK)	1667.190	TON
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	8176.160	TON
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	695.830	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	62.420	TON
414(A) 0261	9" P.C. CONCRETE PAVEMENT	11067.190	SY
414(A) 0263	11" P.C. CONCRETE PAVEMENT	1099.580	SY
414(A1) 5754	9" P.C. DOWEL JOINTED CONCRETE PAVEMENT	22488.830	SY
418 4200	(SP)SMA (1/2 INCH NMS)	128.420	TON

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 100615

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
501(A) 0313	STRUCTURAL EXCAVATION UNCLASSIFIED	1198.330	CY
504(F) 1381	CONCRETE PARAPET	1088.440	LF
504(F) 6190	42" F-SHAPED PARAPET	6687.230	LF
509(A) 0319	CLASS AA CONCRETE	3400.990	CY
509(B) 4153	CLASS A CONCRETE (MED.BAR.DES.1-A)	797.630	CY
509(D) 0325	CLASS C CONCRETE	815.570	CY
510(A) 6334	RETAINING WALL	420.000	SY
510(A) 6341	(PL)MSE RETAINING WALL	5463.000	SY
510(D) 0350	(SP)GRAFFITI TREATMENT	40599.000	SF
511(A) 0332	REINFORCING STEEL	649240.230	LB
601(A) 0297	TYPE I PLAIN RIPRAP	200.000	TON
609(A) 0287	CONC.CURB(4" MNTBLE-INTEGRAL)	240.000	LF
609(B) 1526	2'-8" COMB.CRB.& GUT.(8" BARRIER)	2195.000	LF
610(B) 0399	6" CONCRETE DRIVEWAY (H.E.S.)	195.370	SY
610(C) 0609	6" CONCRETE DIVIDING STRIP	432.650	SY
611(A) 2657	MANHOLE (4' DIA.)	3.000	EA
611(A) 2658	MANHOLE (5' DIA.)	7.000	EA
611(A) 2659	MANHOLE (6' DIA.)	7.000	EA
611(B) 2680	ADD'L.DEPTH IN MANHOLE (4' DIA.)	1.870	VF
611(B) 2681	ADD'L.DEPTH IN MANHOLE (5' DIA.)	30.530	VF
611(B) 2682	ADD'L.DEPTH IN MANHOLE (6' DIA.)	27.180	VF
611(D) 4215	MANHOLE FRAME & COVER	24.000	EA
611(E) 5112	INLET CICI DES. 2 (STD)	1.000	EA
611(E) 5113	INLET CICI DES. 2 (B)	5.000	EA
611(E) 5118	INLET CICI DES. 2 (B-D)	1.000	EA
611(E) 5120	INLET CICI DES. 3 (STD)	3.000	EA
611(E) 5125	INLET CICI DES. 3 (2D)	1.000	EA
611(E) 5334	INLET GPI TYPE 2 (DES. 8)	3.000	EA
611(E) 5340	INLET GPI TYPE 2 (DES. 14)	2.000	EA
611(E) 6000	INLET (SMD-TYPE 1)	1.000	EA
611(E) 6006	INLET (SMD-TYPE 2B)	8.000	EA
611(F) 5325	INLET CICI DES. 2 (ADD'L DEPTH)	26.320	VF
611(F) 5330	INLET CICI DES. 3 (ADD'L DEPTH)	9.380	VF
611(F) 5375	INLET GPI TYPE 2 (ADD'L DEPTH)	26.540	VF
611(G) 4488	INLET FRM&GRT (SSIF-FRM,CIG-GRT-VG-F)	101.000	EA
611(K) 4488	CAST IRON CURB INLETS	54.000	EA
612(A) 0641	MANHOLES ADJUST TO GRADE	5.000	EA
612(E) 0645	INLETS ADJUST TO GRADE	5.000	EA
612(G) 0647	VALVE BOXES ADJUST TO GRADE	10.000	EA
612(J) 0650	FIRE HYDRANT RESET	5.000	EA
612(L) 0652	WATER METERS RESET	10.000	EA
613(B) 0491	18" R.C.PIPES CLASS III	1714.000	LF

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 100615

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
613(B) 0492	24" R.C.P.I.P.E CLASS III	630.000	LF
613(B) 0493	30" R.C.P.I.P.E CLASS III	639.000	LF
613(B) 0494	36" R.C.P.I.P.E CLASS III	676.000	LF
613(B) 0495	42" R.C.P.I.P.E CLASS III	177.000	LF
613(B) 0583	24" R.C.P.I.P.E CLASS IV	16.000	LF
613(B) 0584	30" R.C.P.I.P.E CLASS IV	62.000	LF
613(B) 0587	48" R.C.P.I.P.E CLASS IV	87.000	LF
613(S) 1180	TRENCH EXCAVATION	4909.770	CY
613(T) 1181	STANDARD BEDDING MATERIAL	2210.990	CY
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 4726	REMOVAL OF CURB AND GUTTER	702.000	LF
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	13322.600	SY
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	5555.950	SY
619(B) 4791	REMOVAL OF CURB	435.000	LF
619(C) 0924	SAWING PAVEMENT	4669.570	LF
622(A) 4445	2" PIPE RAILING	90.000	LF
624(D) 4292	FENCE-STYLE CLF (6'HIGH, CLASS A)	4069.000	LF
627(A) 4310	PRECAST CONCRETE MEDIAN BARRIER, TYPE I	1230.000	LF
627(I) 4317	CONCRETE MEDIAN BARRIER, DESIGN 1	313.000	LF

SECTION 0002 - WATERLINE

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
616(I) 0150	(PL)INSTALL WATER LINE	1.000	LSUM

SECTION 0003 - SANITARY SEWER

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
516(A) 6092	DRILLED SHAFTS 36" DIAMETER	1037.000	LF
615(H) 0110	SANITARY SEWER LINE RELOCATION	1.000	LSUM

SECTION 0004 - BRIDGE 'R'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	10.000	CY
501(C) 1308	SUBSTRUCTURE EXCAVATION ROCK	776.100	CY
501(G) 6309	CLSM BACKFILL	1128.000	CY
502(A) 6173	ENGINEERED FALSEWORK	1.000	LSUM
504(A) 1304	APPROACH SLAB	234.400	SY
504(C) 6250	SEALED EXPANSION JOINT	60.000	LF
504(F) 6190	42" F-SHAPED PARAPET	1311.500	LF
506(A) 1322	STRUCTURAL STEEL	1081630.000	LB
509(A) 1326	CLASS AA CONCRETE	533.300	CY
509(B) 1328	CLASS A CONCRETE	633.700	CY
510(C) 6138	SLOPE WALL (5")	4090.000	SY
511(B) 6010	EPOXY COATED REINFORCING STEEL	186330.000	LB
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	1331.800	SY

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 100615

SECTION 0004 - BRIDGE 'R'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
516(A) 6096	DRILLED SHAFTS 60" DIAMETER	60.000	LF
516(A) 6100	DRILLED SHAFTS 84" DIAMETER	30.000	LF
517(A) 6002	PRESTRESSING	1.000	LSUM
523(A) 6550	(SP) SEALER CRACK PREPARATION	64.000	LF
523(B) 6560	(SP) SEALER RESIN	2.000	GAL
535 6138	(PL)INLET AND BASIN	1.000	EA
535 6164	(PL)FIXED BEARING ASSEMBLY	12.000	EA
535 6165	(PL)EXPANSION BEARING ASSEMBLY	16.000	EA
535 6282	(PL)ELASTOMERIC BEARING PADS	2.000	EA
535 6780	ORNAMENTAL MEDALLION	3.000	EA
613(P) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	64.000	LF
613(Q) 6207	6" NON-PERF.PIPE UNDERDRAIN RND.	47.000	LF

SECTION 0005 - TRAFFIC SIGNING AND STRIPING

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
804(A) 2915	STRUCTURAL CONCRETE	5.280	CY
804(B) 2916	REINFORCING STEEL	872.000	LB
850(A) 8110	SHEET ALUMINUM SIGNS	252.900	SF
850(B) 8112	EXTRUDED ALUMINUM PANEL SIGNS	301.500	SF
850(B) 8114	EXTR.ALUM.PAN.SGN.(OVRHD SIGNS)	941.680	SF
851(A) 3206	4"@13 GALV.STL.WD.FLANGE BM.POST	74.000	LF
851(A) 3207	6"@15 GALV.STL.WD.FLANGE BM.POST	93.000	LF
851(B) 3217	2 1/2"@5.79 GALV.STL.PIPE POST	64.000	LF
851(C) 8324	2" SQUARE TUBE POST	272.000	LF
854(C) 8525	(SP)TRAF.STR.(MULTI-POLY.)(SYM,WRD,ETC)	16.000	EA
854(C) 8530	(SP)TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	36430.000	LF
854(C) 8535	(SP)TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	9798.000	LF
854(C) 8540	(SP)TRAFFIC STRIPE(MULTI-POLY.)(8" WIDE)	11485.000	LF
871 8325	(PL)IMPACT ATTENUATOR	5.000	EA
890(A) 8722	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM

SECTION 0006 - TRAFFIC LIGHTING

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
509(B) 0321	CLASS A CONCRETE	4.860	CY
516(A) 6091	DRILLED SHAFTS 30" DIAMETER	19.500	LF
516(A) 6094	DRILLED SHAFTS 48" DIAMETER	40.000	LF
610(A) 0602	4" CONCRETE SIDEWALK	84.000	SY
802(A) 8302	1" GALV.STEEL ELECT.COND. EXPOSED	70.000	LF
802(A) 8314	2" GALV.STEEL ELECT.COND. TRENCHED	2557.000	LF
802(B) 8342	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	2336.000	LF
802(D) 8370	JUNCTION BOX(6" X 6" X 4")	1.000	EA
803 8065	PULL BOX(SIZE I)	19.000	EA
804(A) 2915	STRUCTURAL CONCRETE	1.160	CY

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 100615

SECTION 0006 - TRAFFIC LIGHTING

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
804(B) 2916	REINFORCING STEEL	786.800	LB
806(D) 8989	40' MTG.HT.HL.PTP.(G.STL.)	14.000	EA
807 8092	BREAKAWAY BASE (DES. B)	1.000	EA
809(A) 8090	(PL)ROADWAY LUMINAIRE	28.000	EA
809(B) 8098	UNDERPASS LUMINAIRE	4.000	EA
809(E) 8103	HIGH MAST LUMINAIRE	32.000	EA
810(A) 3118	SERVICE POLE	2.000	EA
811 8036	1/C NO.2 ELECT.COND.	9960.000	LF
811 8038	1/C NO.4 ELECT.COND.	13260.000	LF
811 8044	1/C NO.10 ELECT.COND.	210.000	LF
811 8046	1/C NO.12 ELECT.COND.	2940.000	LF
812 8068	140' HIGH MAST POLE(G.STL.)	4.000	EA
813 8074	HIGH MAST LOWERING DEV.TYP.I	4.000	EA
890(A) 8711	(PL)REMOVAL OF POWER POLE	1.000	EA
890(A) 8712	(PL)REMOVAL OF LIGHT POLE	25.000	EA

SECTION 0007 - TRAFFIC OPERATIONS

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
627(O) 4410	REL.OF RENTED PORT.PREC.CONC.MED.BARRIER	2770.000	LF
627(P) 4425	RENTED PORT.TYPE PREC.CONC.MED. BARR.	6175.000	LF
856(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	9255.000	LF
856(G) 8887	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	5000.000	EA
859(A) 8006	PAVEMENT MRKNG.REMOVAL(TRAFF.STRP)	30000.000	LF
870(A) 8490	(PL)SAND FILLED IMPACT ATTEN.SYSTEM	305.000	SD
876(C) 8482	(PL)TRUCK MOUNTED ATTENUATOR	60.000	SD
880(A) 8812	ARROW DISPLAY(TYPE C)	60.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	7205.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	9345.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	9615.000	SD
880(B) 8827	CONSTRUCTION SIGNS 33.0 SF & OVER	1215.000	SD
880(C) 8842	BARRICADES(TYPE III)	4030.000	SD
880(C) 8848	WING BARRICADES	4630.000	SD
880(D) 8854	VERTICAL PANELS	2190.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	15485.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	15945.000	SD
880(F) 8878	DRUMS	15945.000	SD
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	200.000	HOURL
882 8370	(SP)SMART WK. ZONE SYS.-PORT.CHNG.MSG.SN	2190.000	SD
882 8372	(SP)SMART WK. ZONE SYS.-PORT.TRAFF.SENSOR	2190.000	SD
882 8374	(SP)SMART WK ZONE SYS-PAN-TILT-ZOOM CMRA	2190.000	SD
882 8376	(SP)SMART WK. ZONE SYS.-WEBSITE SYSTEM	365.000	SD
882(B) 8306	PORT.CHANGEABLE MESSAGE SIGN	850.000	SD

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT****CONTRACT ID: 100615****SECTION 0008 - STAKING**

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
642 0098	STAKING	1.000	LSUM

SECTION 0009 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
220 2800	(SP)SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
640 1426	FIELD OFFICE	1.000	EA
641 1552	MOBILIZATION	1.000	LSUM
643 0087	(SP)CONTRACTORS QUALITY CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 110013

CALL ORDER: 470
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: OKLAHOMA

PROJECT(S) : PCN
STP-155B(480)AG 2223204
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$7.59
45 CALENDAR DAYS
RES. ENG.: DIVISION 4 (PERRY)

CONTRACT DESCRIPTION
RESURFACE (ASPHALT)
CITY STREET (SE 15TH ST.): FROM INDIAN MERIDAN, EXTEND EAST
IN THE CITY OF CHOCTAW.
PROJECT LENGTH = 0.964 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
303 0192	AGGREGATE BASE	800.000	CY
411(S3) 5940	(SP)ASPH.CONC.,TYPE S3(PG 70-28 OK)	2550.000	TON
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	1650.000	TON
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	3645.700	SY
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	20900.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0002 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
641 1552	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110030

CALL ORDER: 480
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: OKLAHOMA

PROJECT(S) : PCN
 STPG-155B(804)AG 2728004
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$5.42
 45 CALENDAR DAYS
 RES. ENG.: DIVISION 4 (PERRY)

CONTRACT DESCRIPTION
 PEDESTRIAN IMPROVEMENTS
 CITY STREET (PENNSYLVANIA AVE.): FROM GLADSTONE TERRACE,
 EXTEND NORTH IN THE CITY OF THE VILLAGE.
 PROJECT LENGTH = 0.123 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 0186	SELECT BORROW	50.000	CY
202(G) 0185	EARTHWORK	1.000	LSUM
205 4230	TYPE A-SALVAGED TOPSOIL	150.000	CY
223 2801	TEMPORARY SILT FENCE	653.000	LF
230(A) 2806	SOLID SLAB SODDING	1200.000	SY
504(G) 6006	HANDRAILING	28.000	LF
509(C) 0322	CLASS A CONCRETE FOR SMALL STRUCTURES	1.440	CY
511(A) 0332	REINFORCING STEEL	103.000	LB
610(A) 0602	4" CONCRETE SIDEWALK	251.870	SY
610(A) 0605	6" CONCRETE SIDEWALK	19.590	SY
610(B) 0399	6" CONCRETE DRIVEWAY (H.E.S.)	13.780	SY
612(A) 0641	MANHOLES ADJUST TO GRADE	1.000	EA
612(G) 0647	VALVE BOXES ADJUST TO GRADE	1.000	EA
612(H) 0648	METER BOXES ADJUST TO GRADE	1.000	EA
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	12.500	SY
619(C) 0924	SAWING PAVEMENT	56.000	LF

SECTION 0002 - TRAFFIC

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
890A/B 8760	(PL)REMOVE & RESET GROUND MOUNTED SIGN	1.000	EA

SECTION 0003 - STAKING

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
642 0098	STAKING	1.000	LSUM

SECTION 0004 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
641 1552	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110115

CALL ORDER: 490
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: OKLAHOMA

PROJECT(S) : PCN
 IMY-35-2(299)126 3P 2746504
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 75 CALENDAR DAYS
 RES. ENG.: DIVISION 4 (PERRY)

CONTRACT DESCRIPTION
 PAVEMENT REHABILITATION (P.C. CONCRETE)
 I-35: FROM S.E. 15TH STREET, EXTEND NORTH IN OKLAHOMA CITY.
 PROJECT LENGTH = 0.44 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
303(A) 2100	AGGREGATE BASE TYPE A	100.000	CY
414(B) 5725	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	1000.000	SY
414(C) 4425	CONT.REINF.P.C.C. PAVT.(PLACEMENT)	150.000	SY
414(G) 5275	P.C. CONCRETE FOR PAVEMENT	350.000	CY
415 6300	CONCRETE JOINT SEALING	42000.000	LF
416 0100	DOWEL BAR RETROFIT	6900.000	EA
425 5195	DIAMOND GRINDING CONCRETE PAVEMENT	25000.000	SY
511(B) 4269	EPOXY COATED REINFORCING STEEL	1000.000	LB
619(B) 4727	REMOVAL OF CONCRETE PAVEMENT	1000.000	SY
619(B) 4780	REMOVAL OF GUARDRAIL	75.000	LF
619(B) 6189	REMOVAL OF EXISTING SLAB	150.000	SY
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	150.000	LF
623(G) 8571	GUARDRAIL END TREATMENT (GET)	1.000	EA

SECTION 0002 - TRAFFIC

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
623(H) 0940	GUARDRAIL BLOCKOUT REPLACEMENT	775.000	LF
805(A) 8702	REMOVAL OF CLASS C PAVEMENT MARKERS	200.000	EA
853 9069	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	55.000	EA
856(A) 8530	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	16000.000	LF
856(A) 8535	TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	10000.000	LF
856(A) 8540	TRAFFIC STRIPE(MULTI-POLY.)(8" WIDE)	3000.000	LF
856(A) 8555	TRAFFIC STRIPE(MULTI-POLY.)(24" WIDE)	48.000	LF
856(B) 8525	TRAF.STR.(MULTI-POLY.)(SYM,WRD,ETC)	40.000	EA
857(F) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	8000.000	LF
857(F) 8007	PAVEMENT MARKING REMOVAL(ARROWS)	10.000	EA
857(F) 8008	PAVEMENT MARKING REMOVAL(WORDS)	10.000	EA
876(A) 8482	(PL)TRUCK MOUNTED ATTENUATOR	60.000	SD
880(A) 8812	ARROW DISPLAY(TYPE C)	120.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	1000.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	5000.000	SD

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT****CONTRACT ID: 110115****SECTION 0002 - TRAFFIC**

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	5000.000	SD
880(C) 8842	CONSTRUCTION BARRICADES(TYPE III)	500.000	SD
880(C) 8848	WING BARRICADES	180.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	6000.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	10000.000	SD
880(F) 8878	DRUMS	10000.000	SD
880(G) 8890	CHANNELIZER CONES	10000.000	SD
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	500.000	HOURL
882(A) 8306	PORT.CHANGEABLE MESSAGE SIGN	120.000	SD

SECTION 0003 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
641 1552	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110014

CALL ORDER: 500
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: OKLAHOMA

PROJECT(S) : PCN
 STP-155B(813)AG 2810504
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 200 CALENDAR DAYS
 RES. ENG.: DIVISION 4 (PERRY)

CONTRACT DESCRIPTION
 GRADE, DRAIN, AND SURFACE
 CITY STREET (HEFNER RD): FROM THE BROADWAY EXTENSION, EXTEND
 EAST IN OKLAHOMA CITY.
 PROJECT LENGTH = 5.280 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
221(C) 2801	TEMPORARY SILT FENCE	41979.000	LF
230(A) 2806	SOLID SLAB SODDING	13327.000	SY
307(A) 4200	FLY ASH	7016.000	TON
307(E) 4240	CEMENTITIOUS STABILIZED SUBGRADE	86623.000	SY
402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	1079.000	TON
407(B) 0250	TACK COAT	3998.000	GAL
411(B) 5940	SUPERPAVE, TYPE S3(PG 70-28 OK)	13433.000	TON
411(C) 5955	SUPERPAVE, TYPE S4(PG 70-28 OK)	8955.000	TON
412 5267	COLD MILLING PAVEMENT	4013.000	SY
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	79960.000	SY
619(C) 0924	SAWING PAVEMENT	977.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	119940.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0002 - STAKING

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
642(A) 0095	CONSTRUCTION STAKING LEVEL I	1.000	LSUM

SECTION 0003 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
641 1552	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110017

CALL ORDER: 510
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: OTTAWA

PROJECT(S) : PCN
 BRFY-158B(055) 2089404
 DBE GOALS : 5.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$70.44
 180 CALENDAR DAYS
 RES. ENG.: DIVISION 8 (TULSA)

CONTRACT DESCRIPTION
 BRIDGE AND APPROACHES
 US-59: OVER THE BNSF RAILROAD, 2.6 MILES NORTH OF THE
 DELAWARE COUNTY LINE.
 PROJECT LENGTH = 0.400 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
201(A) 0102	CLEARING AND GRUBBING	1.000	LSUM
202(A) 0183	UNCLASSIFIED EXCAVATION	68462.000	CY
202(D) 0184	UNCLASSIFIED BORROW	44432.000	CY
205(A) 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
221(C) 2801	TEMPORARY SILT FENCE	6561.000	LF
221(F) 0100	TEMPORARY SILT DIKE	49.000	LF
230(A) 2806	SOLID SLAB SODDING	38161.000	SY
232(A) 2813	SEEDING METHOD A	9.270	AC
233(A) 2817	VEGETATIVE MULCHING	9.270	AC
241 2832	MOWING	18.540	AC
303(A) 2100	AGGREGATE BASE TYPE A	3072.000	CY
307(D) 4230	LIME	370.000	TON
307(H) 4270	LIME STABILIZED SUBGRADE	17204.000	SY
317 4270	CEMENT TREATED BASE	608.000	SY
325 5271	SEPARATOR FABRIC	15634.000	SY
326(B) 0100	GEOGRID REINFORCEMENT	22937.000	SY
402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	600.000	TON
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	2830.000	TON
414(A) 0210	P.C.CONCRETE PAVEMENT(PLACEMENT)	1330.000	SY
414(B) 5725	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	11965.000	SY
414(G) 5275	P.C. CONCRETE FOR PAVEMENT	3502.000	CY
501(A) 0313	STRUCTURAL EXCAVATION UNCLASSIFIED	8.000	CY
509(A) 0319	CLASS AA CONCRETE	126.000	CY
511(A) 0332	REINFORCING STEEL	21586.000	LB
609(A) 0300	CONC.CURB(6" BARRIER-INTEGRAL)	2113.000	LF
613(A) 4498	43" X 26" R.C.PIPES ARCH CLASS A-III	56.000	LF
613(H) 0450	6" PERFORATED PIPE UNDERDRAIN ROUND	75.000	LF
613(I) 1096	6" NON-PERF.PIPES UNDERDRAIN RND.	25.000	LF
613(J) 5915	EDGE DRAIN CONDUIT-PERFORATED	2113.000	LF
613(L) 4531	43" X 26" PREFAB. CULVERT END SEC., ARCH	1.000	EA

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110017

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
613(N) 7525	TYPE F6 SLOPED CONCRETE END SECTION	1.000	EA
619(A) 0920	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
619(B) 4725	REMOVAL OF FENCE	1294.000	LF
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	1403.000	SY
619(B) 4763	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	7241.000	SY
619(B) 4780	REMOVAL OF GUARDRAIL	2316.000	LF
619(C) 0924	SAWING PAVEMENT	2270.000	LF
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	263.000	LF
623(G) 8571	GUARDRAIL END TREATMENT (GET)	2.000	EA
623(I) 8675	GUARDRAIL BRIDGE CONNECTION-TYPE A	2.000	EA
624(E) 4293	FENCE-STYLE CLF (6'HIGH, CLASS B)	555.000	LF

SECTION 0002 - BRIDGE 'A'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	215.000	CY
501(G) 6309	CLSM BACKFILL	662.000	CY
504(A) 1304	APPROACH SLAB	836.000	SY
504(B) 1305	SAW-CUT GROOVING	2523.000	SY
504(C) 6250	SEALED EXPANSION JOINT	173.200	LF
504(D) 6245	CONCRETE RAIL (TR4)	907.900	LF
506(A) 1322	STRUCTURAL STEEL	772390.000	LB
507(A) 6170	STAINLESS STEEL FIXED BEARING ASSEMBLY	21.000	EA
507(B) 6174	STAINLESS STEEL EXP. BEARING ASSEMBLY	21.000	EA
509(A) 1326	CLASS AA CONCRETE	607.000	CY
509(B) 1328	CLASS A CONCRETE	390.800	CY
509(D) 1331	CLASS C CONCRETE	65.000	CY
510(C) 6138	SLOPE WALL (5")	1450.000	SY
511(A) 1332	REINFORCING STEEL	2280.000	LB
511(B) 6010	EPOXY COATED REINFORCING STEEL	193390.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	1148.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	1148.000	LF
515(A) 6013	WATER REPELLENT (VISUALLY INSPECTED)	1000.000	SY
516(A) 6096	DRILLED SHAFTS 60" DIAMETER	272.000	LF
523(A) 6550	SEALER CRACK PREPARATION	173.200	LF
523(B) 6560	SEALER RESIN	1.700	GAL
613(H) 6204	6" PERFORATED PIPE UNDERDRAIN ROUND	1000.000	LF
613(U) 1100	PIPE UNDERDRAIN COVER MAT'L.	1250.000	CY
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

SECTION 0003 - TRAFFIC CONTROL

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
857(A) 8839	CONSTRUCTION TRAFF.STR.(PAINT)(4" WIDE)	15140.000	LF
857(E) 8887	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	5000.000	EA

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110017

SECTION 0003 - TRAFFIC CONTROL

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
857(F) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	8360.000	LF
876(A) 8482	(PL)TRUCK MOUNTED ATTENUATOR	180.000	SD
880(B) 8818	CONSTRUCTION SIGNS 0 TO 6.25 SF	9900.000	SD
880(B) 8821	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1980.000	SD
880(B) 8824	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	4140.000	SD
880(C) 8842	CONSTRUCTION BARRICADES(TYPE III)	1080.000	SD
880(C) 8848	WING BARRICADES	720.000	SD
880(E) 8860	WARNING LIGHTS(TYPE A)	2160.000	SD
880(E) 8872	WARNING LIGHTS(TYPE C)	24480.000	SD
880(F) 8878	DRUMS	48920.000	SD
880(G) 8890	CHANNELIZER CONES	3600.000	SD
882(A) 8306	PORT.CHANGEABLE MESSAGE SIGN	360.000	SD

SECTION 0004 - STAKING

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
642(A) 0095	CONSTRUCTION STAKING LEVEL I	1.000	LSUM

SECTION 0005 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
220 2800	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
640(A) 1398	FIELD OFFICE	1.000	EA
641 1399	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 110127

CALL ORDER: 520
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: PAYNE

PROJECT(S) : PCN
 STPY-160B(209)3P 2823504
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 45 CALENDAR DAYS
 RES. ENG.: DIVISION 4 (PERRY)

CONTRACT DESCRIPTION
 RESURFACE (ASPHALT)
 SH-33: FROM THE US-177 NORTH JUNCTION, EXTEND EAST.
 PROJECT LENGTH = 1.54 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 4781	UNCLASSIFIED BORROW (TOPSOIL)	1000.000	CY
411(C) 5955	SUPERPAVE, TYPE S4(PG 70-28 OK)	7200.000	TON
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	1200.000	TON
412 5267	COLD MILLING PAVEMENT	3000.000	SY

SECTION 0002 - TRAFFIC

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	40000.000	LF
855(A) 8813	TRAFFIC STRIPE(PLASTIC)(6" WIDE)	2000.000	LF
855(A) 8814	TRAFFIC STRIPE(PLASTIC)(8" WIDE)	1000.000	LF
855(A) 8825	TRAFFIC STRIPE(PLASTIC)(24" WIDE)	240.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	24.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	2.000	EA
857(F) 8006	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	240.000	LF
857(F) 8007	PAVEMENT MARKING REMOVAL(ARROWS)	22.000	EA
857(F) 8008	PAVEMENT MARKING REMOVAL(WORDS)	1.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 090126

CALL ORDER: 530
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: PITTSBURG

PROJECT(S) : PCN
NHY-013N(131)3P 2629607
DBE GOALS : 5.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
90 CALENDAR DAYS
RES. ENG.: DIVISION 2 (ANTLERS)

CONTRACT DESCRIPTION

PAVEMENT REHABILITATION (P.C. CONCRETE)
US-69: FROM 6.30 MILES NORTH OF THE SH-63 JUNCTION,
EXTEND NORTH.
PROJECT LENGTH = 2.76 MILES

SECTION 0001 - ROADWAY

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	1500.000	TON
414(B) 5913	H.E.S. CONCRETE (FULL DEPTH PATCHING)	500.000	SY
414(I) 5275	P.C. CONCRETE FOR PAVEMENT	11500.000	CY
414(J) 5400	P.C. CONCRETE PAVEMENT(PLACEMENT ONLY)	56300.000	SY
414(K) 5550	(SP)BONDED P.C.C. OVERLAY(PLACEMENT)	22000.000	SY
417 5267	COLD MILLING PAVEMENT	74000.000	SY
854(C) 8525	(SP)TRAF.STR.(MULTI-POLY.)(SYM,WRD,ETC)	38.000	EA
854(C) 8530	(SP)TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	33200.000	LF
854(C) 8535	(SP)TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	16000.000	LF
854(C) 8540	(SP)TRAFFIC STRIPE(MULTI-POLY.)(8" WIDE)	1000.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**STATE PROJECT**

CONTRACT ID: 110130

CALL ORDER: 540
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: PONTOTOC

PROJECT(S) : PCN
SSR-162B(220)SR 2818704
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
35 CALENDAR DAYS
RES. ENG.: DIVISION 3 (ADA)

CONTRACT DESCRIPTION
RESURFACE (ASPHALT)
SH-99: FROM 8.17 MILES NORTH OF THE JOHNSTON COUNTY LINE,
EXTEND NORTH.
PROJECT LENGTH = 7.4 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 0184	UNCLASSIFIED BORROW	743.000	CY
407(B) 0250	TACK COAT	4984.000	GAL
411(C) 5955	SUPERPAVE, TYPE S4(PG 70-28 OK)	9259.000	TON
412 5267	COLD MILLING PAVEMENT	960.000	SY
856(A) 8530	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	136752.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**STATE PROJECT**

CONTRACT ID: 110131

CALL ORDER: 550
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: POTTAWATOMIE

PROJECT(S) : PCN
SSR-163C(347)SR 2819004
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
30 CALENDAR DAYS
RES. ENG.: DIVISION 3 (ADA)

CONTRACT DESCRIPTION
RESURFACE (ASPHALT)
SH-102: FROM 1.6 MILES SOUTH OF THE SH-39 JUNCTION,
EXTEND NORTH.
PROJECT LENGTH = 1.7 MILES

SECTION 0001 - ROADWAY

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	578.000	TON
407(B) 0250	TACK COAT	2394.000	GAL
411(D) 5975	SUPERPAVE, TYPE S5(PG 64-22 OK)	2980.000	TON
412 5267	COLD MILLING PAVEMENT	350.000	SY
855(A) 8840	TRAF.STR.(PLASTIC)(THIN LINE)(4" WIDE)	32736.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 110132

CALL ORDER: 560
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: POTTAWATOMIE

PROJECT(S) : PCN
STPY-163A(355)3P 2820604
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
40 CALENDAR DAYS
RES. ENG.: DIVISION 3 (ADA)

CONTRACT DESCRIPTION
RESURFACE (ASPHALT)
SH-18: FROM THE US-270B JUNCTION, EXTEND EAST.
PROJECT LENGTH = 4.61 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
407(B) 0250	TACK COAT	7087.000	GAL
411(C) 5955	SUPERPAVE, TYPE S4(PG 70-28 OK)	12501.000	TON
412 5267	COLD MILLING PAVEMENT	141739.000	SY
856(A) 8530	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	74672.000	LF
856(B) 8860	TRAFFIC STRIPE(MULTI-POLY.)(ARROWS)	39.000	EA
856(B) 8870	TRAFFIC STRIPE(MULTI-POLY.)(SYMBOLS)	12.000	EA
856(B) 8880	TRAFFIC STRIPE(MULTI-POLY.)(WORDS)	16.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 110133

CALL ORDER: 570
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: POTTAWATOMIE

PROJECT(S) : PCN
STPY-163B(350)3P 2820904
DBE GOALS : 7.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
35 CALENDAR DAYS
RES. ENG.: DIVISION 3 (ADA)

CONTRACT DESCRIPTION
RESURFACE (UTBWC)
US-177: FROM THE SH-39 JUNCTION, EXTEND NORTH.
PROJECT LENGTH = 7.01 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
209 0120	MACHINE GRADING	2695.000	LF
404(G) 4845	ULTRA-THIN BONDED WEARING COURSE, TYPE C	4561.000	TON
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	366.000	TON
619(B) 4780	REMOVAL OF GUARDRAIL	2950.000	LF
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	2450.000	LF
623(F) 6030	GUARDRAIL ANCHOR UNIT (TYPE B)	9.000	EA
623(G) 8571	GUARDRAIL END TREATMENT (GET)	9.000	EA
856(A) 8530	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	131393.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 110134

CALL ORDER: 580
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: POTTAWATOMIE

PROJECT(S) : PCN
STPY-163B(351)3P 2820905
DBE GOALS : 6.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
50 CALENDAR DAYS
RES. ENG.: DIVISION 3 (ADA)

CONTRACT DESCRIPTION
RESURFACE (UTBWC)
US-177: FROM 7.0 MILES NORTH OF THE SH-39 JUNCTION, EXTEND
NORTH.
PROJECT LENGTH = 6.0 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
209 0120	MACHINE GRADING	7975.000	LF
404(G) 4845	ULTRA-THIN BONDED WEARING COURSE, TYPE C	4388.000	TON
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	1260.000	TON
619(B) 4780	REMOVAL OF GUARDRAIL	6650.000	LF
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	7250.000	LF
623(F) 6030	GUARDRAIL ANCHOR UNIT (TYPE B)	18.000	EA
623(G) 8571	GUARDRAIL END TREATMENT (GET)	18.000	EA
856(A) 8530	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	119880.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 110135

CALL ORDER: 590
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: POTTAWATOMIE

PROJECT(S) : PCN
STPY-163B(352)3P 2820906
DBE GOALS : 6.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
40 CALENDAR DAYS
RES. ENG.: DIVISION 3 (ADA)

CONTRACT DESCRIPTION
RESURFACE (UTBWC)
US-177: FROM 13.0 MILES NORTH OF THE SH-39 JUNCTION, EXTEND
NORTH.
PROJECT LENGTH = 6.0 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
209 0120	MACHINE GRADING	5527.000	LF
404(G) 4845	ULTRA-THIN BONDED WEARING COURSE, TYPE C	4964.000	TON
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	701.000	TON
619(B) 4780	REMOVAL OF GUARDRAIL	6775.000	LF
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	5025.000	LF
623(F) 6030	GUARDRAIL ANCHOR UNIT (TYPE B)	12.000	EA
623(G) 8571	GUARDRAIL END TREATMENT (GET)	11.000	EA
856(A) 8530	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	121493.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110164

CALL ORDER:	591	<u>PROJECT(S) :</u>	<u>PCN</u>
LETTING DATE:	January 20, 2011	STPY-163B(350)3P	2820904
LETTING TIME:	10:30 A.M.	STPY-163B(351)3P	2820905
COUNTIES:	POTTAWATOMIE	STPY-163B(352)3P	2820906

DBE GOALS : 6.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 100 CALENDAR DAYS
 RES. ENG.: DIVISION 3 (ADA)

CONTRACT DESCRIPTION
 RESURFACE (UTBWC)
 US-177: FROM THE SH-39 JUNCTION, EXTEND NORTH.
 PROJECT LENGTH = 19.01 MILES

SECTION 0001 - ROADWAY - STPY-163B(350)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
209 0120	MACHINE GRADING	2695.000	LF
404(G) 4845	ULTRA-THIN BONDED WEARING COURSE, TYPE C	4561.000	TON
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	366.000	TON
619(B) 4780	REMOVAL OF GUARDRAIL	2950.000	LF
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	2450.000	LF
623(F) 6030	GUARDRAIL ANCHOR UNIT (TYPE B)	9.000	EA
623(G) 8571	GUARDRAIL END TREATMENT (GET)	9.000	EA
856(A) 8530	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	131393.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0002 - ROADWAY - STPY-163B(351)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
209 0120	MACHINE GRADING	7975.000	LF
404(G) 4845	ULTRA-THIN BONDED WEARING COURSE, TYPE C	4388.000	TON
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	1260.000	TON
619(B) 4780	REMOVAL OF GUARDRAIL	6650.000	LF
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	7250.000	LF
623(F) 6030	GUARDRAIL ANCHOR UNIT (TYPE B)	18.000	EA
623(G) 8571	GUARDRAIL END TREATMENT (GET)	18.000	EA
856(A) 8530	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	119880.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0003 - ROADWAY - STPY-163B(352)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
209 0120	MACHINE GRADING	5527.000	LF
404(G) 4845	ULTRA-THIN BONDED WEARING COURSE, TYPE C	4964.000	TON
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	701.000	TON
619(B) 4780	REMOVAL OF GUARDRAIL	6775.000	LF
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	5025.000	LF
623(F) 6030	GUARDRAIL ANCHOR UNIT (TYPE B)	12.000	EA

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT****CONTRACT ID: 110164****SECTION 0003 - ROADWAY - STPY-163B(352)3P**

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
623(G) 8571	GUARDRAIL END TREATMENT (GET)	11.000	EA
856(A) 8530	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	121493.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 110136

CALL ORDER: 600
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: POTTAWATOMIE

PROJECT(S) : PCN
STPY-163C(353)3P 2821004
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
25 CALENDAR DAYS
RES. ENG.: DIVISION 3 (ADA)

CONTRACT DESCRIPTION
RESURFACE (ASPHALT)
SH-270: FROM THE OKLAHOMA COUNTY LINE, EXTEND EAST.
PROJECT LENGTH = 2.35 MILES

SECTION 0001 - ROADWAY - STPY-163C(353)3P

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
202(D) 0184	UNCLASSIFIED BORROW	329.000	CY
407(B) 0250	TACK COAT	3033.000	GAL
411(D) 5970	SUPERPAVE, TYPE S5(PG 70-28 OK)	3582.000	TON
412 5267	COLD MILLING PAVEMENT	300.000	SY
856(A) 8530	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	43428.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110138

CALL ORDER: 620
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: PITTSBURG
 PUSHMATAHA
 CHOCTAW

PROJECT(S) : PCN
 BHFY-164F(164) 2092004
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$18.42
 60 CALENDAR DAYS
 RES. ENG.: DIVISION 2 (ANTLERS)

CONTRACT DESCRIPTION
 JOINT SEAL / REPAIR
 SH-2/SH-93/SH-113: AT MULTIPLE LOCATIONS IN DIVISION II.

SECTION 0001 - BRIDGE 'A'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
513(B) 6019	CLASS B BRIDGE DECK REPAIR	30.000	SY
523(A) 6550	SEALER CRACK PREPARATION	56.000	LF
523(B) 6560	SEALER RESIN	0.400	GAL
540 4515	(PL)REPAIR BRIDGE ITEM (TYPE A)	1.000	EA

SECTION 0002 - BRIDGE 'B'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
504(G) 6390	RAPID CURE JOINT SEALANT	364.000	LF
504(H) 6389	ELASTOMERIC MORTAR	4.000	CF
513(B) 6019	CLASS B BRIDGE DECK REPAIR	10.000	SY
520(A) 6058	PREPARATION OF CRACKS, ABOVE WATER	20.000	LF
520(C) 6060	EPOXY RESIN, ABOVE WATER	2.000	GAL
521(A) 6210	PNEUMATICALLY PLACED MORTAR	30.000	SY

SECTION 0003 - BRIDGE 'C'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
502(C) 6116	(PL)FALSEWORK JACKING	1.000	LSUM
504(G) 6390	RAPID CURE JOINT SEALANT	325.000	LF
504(H) 6389	ELASTOMERIC MORTAR	2.000	CF
506(A) 1322	STRUCTURAL STEEL	1230.000	LB
509(D) 1331	CLASS C CONCRETE	9.000	CY
513(B) 6019	CLASS B BRIDGE DECK REPAIR	30.000	SY
520(A) 6058	PREPARATION OF CRACKS, ABOVE WATER	30.000	LF
520(C) 6060	EPOXY RESIN, ABOVE WATER	3.000	GAL
523(A) 6550	SEALER CRACK PREPARATION	154.000	LF
523(B) 6560	SEALER RESIN	1.000	GAL
540 4525	(PL)REPAIR BRIDGE ITEM (TYPE B)	2.000	EA
540 4535	(PL)REPAIR BRIDGE ITEM (TYPE C)	4.000	EA
540 4545	(PL)REPAIR BRIDGE ITEM (TYPE D)	12.000	EA
540 4555	(PL)REPAIR BRIDGE ITEM (TYPE E)	4.000	EA
545 4805	(PL)REPLACE BRIDGE ITEMS	1.000	EA

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT****CONTRACT ID: 110138****SECTION 0004 - TRAFFIC CONTROL**

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
876(A) 8482	(PL)TRUCK MOUNTED ATTENUATOR	60.000	SD
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
882(A) 8306	PORT.CHANGEABLE MESSAGE SIGN	120.000	SD

SECTION 0005 - CONSTRUCTION

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
641 1399	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110139

CALL ORDER: 630
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: PITTSBURG
 PUSHMATAHA
 LEFLORE
 CHOCTAW

PROJECT(S) : PCN
 BHFY-NBIP(437) 2092005
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$19.51
 90 CALENDAR DAYS
 RES. ENG.: DIVISION 2 (ANTLERS)

CONTRACT DESCRIPTION
 BRIDGE PAINTING
 US-70/SH-2/SH-3/SH-93/SH-113: AT VARIOUS LOCATIONS IN
 DIVISION II.

SECTION 0001 - BRIDGE "A"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION AND HANDLING OF WASTE	1.000	LSUM

SECTION 0002 - BRIDGE "B"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION AND HANDLING OF WASTE	1.000	LSUM

SECTION 0003 - BRIDGE "C"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION AND HANDLING OF WASTE	1.000	LSUM

SECTION 0004 - BRIDGE "D"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION AND HANDLING OF WASTE	1.000	LSUM

SECTION 0005 - BRIDGE "E"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION AND HANDLING OF WASTE	1.000	LSUM

SECTION 0006 - BRIDGE "F"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
509 6386	SILICONE CONSTRUCTION JOINT	149.000	LF
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION AND HANDLING OF WASTE	1.000	LSUM

SECTION 0007 - BRIDGE "G"

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
512(A) 1323	PAINTING EXISTING STRUCTURES	1.000	LSUM
512(B) 6303	COLLECTION AND HANDLING OF WASTE	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT****CONTRACT ID: 110139****SECTION 0008 - TRAFFIC CONTROL**

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
876(A) 8482	(PL)TRUCK MOUNTED ATTENUATOR	90.000	SD
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
882(A) 8306	PORT.CHANGEABLE MESSAGE SIGN	180.000	SD

SECTION 0009 - CONSTRUCTION

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
641 1399	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 110109

CALL ORDER: 642
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: ROGER MILLS

<u>PROJECT(S) :</u>	<u>PCN</u>
STPY-165C(119)3P	2813004
STPY-165C(120)3P	2813005

DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
60 CALENDAR DAYS
RES. ENG.: DIVISION 5 (CLINTON)

CONTRACT DESCRIPTION

RESURFACE (ASPHALT)

SH-30: FROM THE BECKHAM COUNTY LINE, EXTEND NORTH.

PROJECT LENGTH = 14.02 MILES

SECTION 0001 - ROADWAY - STPY-165C(119)3P

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	13739.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	1688.000	SY
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	112784.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0002 - ROADWAY - STPY-165C(120)3P

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	10146.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	1668.000	SY
855(A) 8815	TRAFFIC STR.(PLAST.)(THIN-LINE)(4" WIDE)	99500.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

STATE PROJECT

CONTRACT ID: 110140

CALL ORDER: 650
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: ROGERS

PROJECT(S) : PCN
 SSR-166A(253)SR 2760304
 DBE GOALS : 0.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 60 CALENDAR DAYS
 RES. ENG.: DIVISION 8 (TULSA)

CONTRACT DESCRIPTION
 RESURFACE (ASPHALT)
 SH-66: FROM 6.45 MILES NORTH OF THE I-44 JUNCTION, EXTEND
 NORTHEAST.
 PROJECT LENGTH = 4.06 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
303(B) 2110	AGGREGATE BASE TYPE B	667.000	CY
402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	1465.000	TON
409(A) 4242	FABRIC REINFORCEMENT	145974.000	SY
411(C) 5950	SUPERPAVE, TYPE S4(PG 76-28 OK)	31268.000	TON
411(H) 6210	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	200.000	TON
411(I) 6310	SUPERPAVE, TYPE S4(PATCH)(PG64-22OK)	200.000	TON
412 5267	COLD MILLING PAVEMENT	145974.000	SY
414(E) 0225	FULL DEPTH P.C.C. PATCH(PLACEMENT ONLY)	4000.000	SY
414(G) 5275	P.C. CONCRETE FOR PAVEMENT	296.000	CY
805(A) 8702	REMOVAL OF CLASS C PAVEMENT MARKERS	645.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	101974.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	62.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	31.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	480.000	HOURL
882(A) 8306	PORT.CHANGEABLE MESSAGE SIGN	240.000	SD

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110142

CALL ORDER: 670
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: SEQUOYAH

PROJECT(S) : PCN
SEC117-168E(211)SG 2810804
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
60 CALENDAR DAYS
RES. ENG.: DIVISION 1 (MUSKOGEE)

CONTRACT DESCRIPTION
SURFACE (P.C. CONCRETE)
ACCESS ROAD (GEORGE GLEN BLVD): FROM HOUSER INDUSTRIAL BLVD
EXTEND SOUTH THEN EAST IN THE CITY OF SALLISAW.
PROJECT LENGTH = 0.24 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
408 5774	PRIME COAT	1000.000	GAL
414(B) 5725	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	3510.000	SY
414(G) 5275	P.C. CONCRETE FOR PAVEMENT	790.000	CY

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110167

CALL ORDER: 691
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: SEQUOYAH

PROJECT(S) :	PCN
STPY-168A(216)3P	2829204
STPY-168C(217)3P	2829205

DBE GOALS : 2.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 120 CALENDAR DAYS
 RES. ENG.: DIVISION 1 (MUSKOGEE)

CONTRACT DESCRIPTION

RESURFACE (ASPHALT)
 US-59: FROM THE SH-101 JUNCTION, EXTEND NORTH.
 SH-101: FROM THE US-59 JUNCTION, EXTEND EAST.
 PROJECT LENGTH = 8.28 MILES

SECTION 0001 - ROADWAY - STPY-168A(216)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 0184	UNCLASSIFIED BORROW	1000.000	CY
230(A) 2806	SOLID SLAB SODDING	1500.000	SY
402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	4050.000	TON
407(B) 0250	TACK COAT	5410.000	GAL
411(C) 5955	SUPERPAVE, TYPE S4(PG 70-28 OK)	9600.000	TON
509(C) 0322	CLASS A CONCRETE, SMALL STRUCTURES	130.000	CY
511(A) 0332	REINFORCING STEEL	9770.000	LB
619(B) 0291	REMOVAL OF HEADWALL	18.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	96500.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0002 - ROADWAY - STPY-168C(217)3P

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(D) 0184	UNCLASSIFIED BORROW	1000.000	CY
230(A) 2806	SOLID SLAB SODDING	1300.000	SY
402(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	3400.000	TON
407(B) 0250	TACK COAT	3250.000	GAL
411(C) 5960	SUPERPAVE, TYPE S4(PG 64-22 OK)	7100.000	TON
509(C) 0322	CLASS A CONCRETE, SMALL STRUCTURES	90.000	CY
511(A) 0332	REINFORCING STEEL	7000.000	LB
613(A) 0493	30" R.C.PIPE CLASS III	14.000	LF
613(L) 5732	30" PREFAB. CULVERT END SEC., ROUND	2.000	EA
619(B) 0291	REMOVAL OF HEADWALL	14.000	EA
619(B) 4780	REMOVAL OF GUARDRAIL	2420.000	LF
623(A) 0932	BEAM GUARDRAIL W-BEAM SINGLE	900.000	LF
623(C) 5202	BEAM GUARDRAIL THRIE-BEAM SINGLE	190.000	LF
623(E) 7113	BEAM GUARDRAIL TRANSITION SECTION	16.000	EA
623(F) 4446	GUARDRAIL ANCHOR UNIT (TYPE A)	1.000	EA
623(G) 8571	GUARDRAIL END TREATMENT (GET)	16.000	EA
853 9033	DELINEATORS(TYPE 2, CODE 1)	104.000	EA

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT****CONTRACT ID: 110167****SECTION 0002 - ROADWAY - STPY-168C(217)3P**

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	60100.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 110145

CALL ORDER: 700
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: SEQUOYAH

PROJECT(S) : PCN
STPY-168C(218)3P 2829304
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
45 CALENDAR DAYS
RES. ENG.: DIVISION 1 (MUSKOGEE)

CONTRACT DESCRIPTION
RESURFACE (ASPHALT)
US-64: FROM 3.0 MILES WEST OF THE US-59 SOUTH JUNCTION,
EXTEND EAST.
PROJECT LENGTH = 3.00 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
407(B) 0250	TACK COAT	7600.000	GAL
411(C) 5955	SUPERPAVE, TYPE S4(PG 70-28 OK)	12300.000	TON
412 5267	COLD MILLING PAVEMENT	96000.000	SY
828(B) 8136	LOOP DETECTOR WIRE	3000.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	80000.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	110.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110031

CALL ORDER: 710
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: BEAVER
 TEXAS

PROJECT(S) : PCN
 NHY-017N(234)3P 2747604
 DBE GOALS : 4.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 160 CALENDAR DAYS
 RES. ENG.: DIVISION 6 (BUFFALO)

CONTRACT DESCRIPTION
 RESURFACE (ASPHALT)
 SH-3: FROM 6.0 MILES WEST OF THE TEXAS/BEAVER COUNTY LINE,
 EXTEND EAST.
 PROJECT LENGTH = 8.0 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(C) 0184	UNCLASSIFIED BORROW	3150.000	CY
202(G) 0185	EARTHWORK	1.000	LSUM
230(A) 2806	SOLID SLAB SODDING	32854.000	SY
407 0250	TACK COAT	22500.000	GAL
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	32539.000	TON
413(A) 4861	RUMBLE STRIP-METHOD AC-CON	84480.000	LF
414(C) 0309	APPROACH SLABS	705.000	SY
417 4267	COLD MILLING BITUMINOUS PAVEMENT	12730.000	SY
501(G) 6315	CLSM BACKFILL	80.000	CY
619(B) 6189	REMOVAL OF EXISTING SLAB	705.000	SY
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	550.000	LF
623(F) 4446	GUARD RAIL ANCHOR UNIT (TYPE A)	1.000	EA
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	11.000	EA

SECTION 0002 - BRIDGE

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
505(D) 6087	LATEX MODIFIED BRIDGE DECK OVERLAY	3931.000	SY
505(G) 1000	HYDRODEMOLITION	3931.000	SY

SECTION 0003 - TRAFFIC

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
623 8572	(PL)CURVED APPROACH GUARD RAIL	4.000	EA
623(I) 8675	(PL)BRIDGE GUARD RAIL CONNECTION-TYPE A	12.000	EA
823 8478	(PL)PORTABLE TRAFFIC SIGNAL SYSTEM	50.000	SD
854(C) 8530	(SP)TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	126720.000	LF
876(A) 8480	(PL)TRUCK MOUNTED ATTENUATOR	12.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0004 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
641 1552	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110148

CALL ORDER: 720
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: TEXAS

PROJECT(S) : PCN
 NHY-008N(082)3P 2751304
 DBE GOALS : 4.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$0.00
 105 CALENDAR DAYS
 RES. ENG.: DIVISION 6 (BUFFALO)

CONTRACT DESCRIPTION
 RESURFACE (ASPHALT)
 US-54: FROM 0.75 MILES NORTHEAST OF THE TEXAS STATE LINE,
 EXTEND NORTHEAST.
 PROJECT LENGTH = 8.0 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(C) 0184	UNCLASSIFIED BORROW	3400.000	CY
202(G) 0185	EARTHWORK	1.000	LSUM
230(A) 2806	SOLID SLAB SODDING	32000.000	SY
407 0250	TACK COAT	12650.000	GAL
411(S3) 6210	(SP)ASPH.CONC.,TYPE S3(PATCH)(PG64-22OK)	300.000	TON
411(S4) 5950	(SP)ASPH.CONC.,TYPE S4(PG 76-28 OK)	24046.000	TON
413(A) 4861	RUMBLE STRIP-METHOD AC-CON	78680.000	LF
417 4267	COLD MILLING BITUMINOUS PAVEMENT	64232.000	SY
619(B) 4780	REMOVAL OF GUARD RAIL	800.000	LF
623(A) 0932	BEAM GUARD RAIL-W-BEAM-SINGLE	622.000	LF
623(H) 8571	(SP)G.E.T. GUARD RAIL END SECTION	2.000	EA
623(I) 8675	(PL)BRIDGE GUARD RAIL CONNECTION-TYPE A	2.000	EA
854(B) 8803	TRAFFIC STRIPE(PAINT)(ARROW)	24.000	EA
854(C) 8530	(SP)TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	116000.000	LF
876(A) 8480	(PL)TRUCK MOUNTED ATTENUATOR	2.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0002 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
641 1552	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 110151

CALL ORDER: 730
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: TULSA

PROJECT(S) : PCN
STPY-172B(514)3P 2760104
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
50 CALENDAR DAYS
RES. ENG.: DIVISION 8 (TULSA)

CONTRACT DESCRIPTION
RESURFACE (ASPHALT)
SH-117: FROM THE CREEK COUNTY LINE, EXTEND EAST.
PROJECT LENGTH = 1.01 MILES

SECTION 0001 - ROADWAY

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
411(C) 5950	SUPERPAVE, TYPE S4(PG 76-28 OK)	8820.000	TON
411(H) 6210	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	10.000	TON
411(I) 6310	SUPERPAVE, TYPE S4(PATCH)(PG64-22OK)	10.000	TON
412 5267	COLD MILLING PAVEMENT	59400.000	SY
805(A) 8702	REMOVAL OF CLASS C PAVEMENT MARKERS	650.000	EA
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	32800.000	LF
855(B) 8818	TRAFFIC STRIPE(PLASTIC)(ARROWS)	35.000	EA
855(B) 8821	TRAFFIC STRIPE(PLASTIC)(WORDS)	1.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM
880(L) 8911	TRAFFIC SURVEILLANCE, POLICE	300.000	HOURL
882(A) 8306	PORT.CHANGEABLE MESSAGE SIGN	120.000	SD

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110019

CALL ORDER: 740
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: WAGONER

PROJECT(S) : PCN
 BRO-173D(122)CI 2360004
 DBE GOALS : 4.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$13.01
 120 CALENDAR DAYS
 RES. ENG.: DIVISION 1 (MUSKOGEE)

CONTRACT DESCRIPTION
 BRIDGE AND APPROACHES
 COUNTY ROAD (EW-79): OVER RAILROAD CREEK, 0.4 MILES WEST OF
 THE SH-16 JUNCTION.
 PROJECT LENGTH = 0.227 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
201 0102	CLEARING AND GRUBBING	1.000	LSUM
202(A) 0183	UNCLASSIFIED EXCAVATION	2660.000	CY
202(C) 0184	UNCLASSIFIED BORROW	1000.000	CY
205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223 2801	TEMPORARY SILT FENCE	1965.000	LF
227 0100	TEMPORARY SILT DIKE	200.000	LF
230(A) 2806	SOLID SLAB SODDING	6000.000	SY
233(A) 2817	VEGETATIVE MULCHING	2.000	AC
403(E) 0225	TRAFFIC BOUND SURFACE COURSE TYPE E	1500.000	TON
509(D) 0325	CLASS C CONCRETE	20.000	CY
601(A) 0297	TYPE I PLAIN RIPRAP	825.000	TON
613(D) 0690	24" CORR. GALV. STEEL PIPE	60.000	LF
613(D) 0698	72" CORR. GALV. STEEL PIPE	30.000	LF
613(D) 4819	96" CORR. GALV. STEEL PIPE	60.000	LF
613(G) 0761	24" GALV. STEEL CULVERT END SEC. RND.	4.000	EA
613(G) 0769	72" GALV. STEEL CULVERT END SEC. RND.	2.000	EA

SECTION 0002 - BRIDGE 'A'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	60.000	CY
501(D) 6353	UNCLASSIFIED BACKFILL	40.000	CY
503(B) 6144	PRESTRESSED CONCRETE DOUBLE TEE	442.000	LF
504(E) 1380	CONCRETE RAIL (TR1)	265.000	LF
509(A) 1326	CLASS AA CONCRETE	85.000	CY
509(B) 1328	CLASS A CONCRETE	65.000	CY
511(A) 1332	REINFORCING STEEL	22220.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	450.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	450.000	LF
516(A) 6092	DRILLED SHAFTS 36" DIAMETER	48.000	LF
601(A-1)1353	TYPE I-A PLAIN RIPRAP	1080.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	202.000	TON

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT****CONTRACT ID: 110019****SECTION 0002 - BRIDGE 'A'**

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	3.000	EA
623(F) 6034	GUARD RAIL ANCHOR UNIT (TYPE III)	1.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0003 - STAKING

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
642 0098	STAKING	1.000	LSUM

SECTION 0004 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
220 2800	(SP)SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
641 1399	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 110111

CALL ORDER: 750
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: WOODS

PROJECT(S) : PCN
STPY-176C(173)3P 2739804
DBE GOALS : 4.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
45 CALENDAR DAYS
RES. ENG.: DIVISION 6 (BUFFALO)

CONTRACT DESCRIPTION
RESURFACE (ASPHALT)
SH-45: FROM THE US-281 JUNCTION, EXTEND EAST.
PROJECT LENGTH = 4.5 MILES

SECTION 0001 - ROADWAY

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
202(C) 0184	UNCLASSIFIED BORROW	2500.000	CY
202(G) 0185	EARTHWORK	1.000	LSUM
230(A) 2806	SOLID SLAB SODDING	18500.000	SY
407 0250	TACK COAT	10150.000	GAL
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	14400.000	TON
413(A) 4861	RUMBLE STRIP-METHOD AC-CON	47520.000	LF
855(A) 8812	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	83160.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0002 - CONSTRUCTION

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNITS</u>
641 1552	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION

FEDERAL PROJECT

CONTRACT ID: 110020

CALL ORDER: 760
 LETTING DATE: January 20, 2011
 LETTING TIME: 10:30 A.M.
 COUNTIES: WOODWARD

PROJECT(S) : PCN
 BRF-177C(072)CI 2289504
 DBE GOALS : 3.00
 GUARANTY : 5% OF BID TOTAL
 PLAN PRICE : \$14.09
 120 CALENDAR DAYS
 RES. ENG.: DIVISION 6 (BUFFALO)

CONTRACT DESCRIPTION
 BRIDGE AND APPROACHES
 COUNTY ROAD (EW-54): OVER HACKBERRY CREEK, 4.4 MILES EAST
 OF THE SH-34 JUNCTION.
 PROJECT LENGTH = 0.150 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
201 0102	CLEARING AND GRUBBING	1.000	LSUM
202(A) 0183	UNCLASSIFIED EXCAVATION	466.000	CY
202(C) 0184	UNCLASSIFIED BORROW	1072.000	CY
205 4229	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
223 2801	TEMPORARY SILT FENCE	910.000	LF
227 0100	TEMPORARY SILT DIKE	20.000	LF
230(A) 2806	SOLID SLAB SODDING	4400.000	SY
233(A) 2817	VEGETATIVE MULCHING	0.900	AC
310(B) 0149	SUBGRADE, METHOD B	1700.000	SY
411(S3) 5945	(SP)ASPH.CONC.,TYPE S3(PG 64-22 OK)	425.000	TON
411(S4) 5960	(SP)ASPH.CONC.,TYPE S4(PG 64-22 OK)	205.000	TON
509(D) 0325	CLASS C CONCRETE	20.000	CY
619(B) 4728	REMOVAL OF ASPHALT PAVEMENT	1700.000	SY
619(C) 0924	SAWING PAVEMENT	45.000	LF
854(A) 8800	TRAFFIC STRIPE(PAINT)(4" WIDE)	3200.000	LF

SECTION 0002 - BRIDGE 'A'

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
501(B) 1307	SUBSTRUCTURE EXCAVATION COMMON	60.000	CY
501(D) 6353	UNCLASSIFIED BACKFILL	40.000	CY
503(B) 6144	PRESTRESSED CONCRETE DOUBLE TEE	534.000	LF
504(E) 1380	CONCRETE RAIL (TR1)	315.000	LF
509(A) 1326	CLASS AA CONCRETE	92.700	CY
509(B) 1328	CLASS A CONCRETE	54.000	CY
511(A) 1332	REINFORCING STEEL	22445.000	LB
514(A) 6010	PILES, FURNISHED (HP 10X42)	500.000	LF
514(B) 6292	PILES, DRIVEN (HP 10X42)	500.000	LF
516(A) 6094	DRILLED SHAFTS 48" DIAMETER	202.000	LF
601(A-1)1353	TYPE I-A PLAIN RIPRAP	470.000	TON
601(A-2)1355	TYPE I-A FILTER BLANKET	100.000	TON
619(D) 1397	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT****CONTRACT ID: 110020****SECTION 0002 - BRIDGE 'A'**

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
623(F) 6033	GUARD RAIL ANCHOR UNIT (TYPE II)	4.000	EA
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0003 - STAKING

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
642 0098	STAKING	1.000	LSUM

SECTION 0004 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
220 2800	(SP)SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
641 1399	MOBILIZATION	1.000	LSUM

OKLAHOMA DEPARTMENT OF TRANSPORTATION**FEDERAL PROJECT**

CONTRACT ID: 110159

CALL ORDER: 770
LETTING DATE: January 20, 2011
LETTING TIME: 10:30 A.M.
COUNTIES: WOODWARD

PROJECT(S) : PCN
NHY-017N(240)3P 2750904
DBE GOALS : 0.00
GUARANTY : 5% OF BID TOTAL
PLAN PRICE : \$0.00
50 CALENDAR DAYS
RES. ENG.: DIVISION 6 (BUFFALO)

CONTRACT DESCRIPTION
RESURFACE (ASPHALT)
US-183: FROM THE SH-34 SOUTH JUNCTION, EXTEND NORTH.
PROJECT LENGTH = 3.71 MILES

SECTION 0001 - ROADWAY

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
202(C) 0184	UNCLASSIFIED BORROW	1600.000	CY
202(G) 0185	EARTHWORK	1.000	LSUM
230(A) 2806	SOLID SLAB SODDING	10000.000	SY
407 0250	TACK COAT	3200.000	GAL
411(S3) 6210	(SP)ASPH.CONC.,TYPE S3(PATCH)(PG64-22OK)	400.000	TON
411(S4) 5955	(SP)ASPH.CONC.,TYPE S4(PG 70-28 OK)	6900.000	TON
417 4267	COLD MILLING BITUMINOUS PAVEMENT	15700.000	SY
854(C) 8530	(SP)TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	54000.000	LF
880(J) 8905	CONSTRUCTION TRAFFIC CONTROL	1.000	LSUM

SECTION 0002 - CONSTRUCTION

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNITS
641 1552	MOBILIZATION	1.000	LSUM



List of Debarred and/or Suspended Contractors for ODOT's Projects on this month's letting:

The following companies and/or individuals are not permitted to submit bids, provide services as a subcontractor, supply materials, or otherwise participate in any project let by ODOT.

Name of Company and Individual	Suspended	Debarred
J & N INTERNATIONAL COATINGS, INC. Ms. Nikoleta M. Tiliakos Mr. John D. Tiliakos Mr. Drossos J. Tiliakos 17130 Groeschke Road Houston, TX 77084		X
KERRVILLE PAINTING COMPANY, INC. Mr. Nickolas Mouzakis 203 "G" Street, South Kerrville, TX 78028		X
MBE, INC. Ms. Fani Gialousis Mr. Tony Gialousis Mr. Manuel Gialousis 426 South Florida Ave. P.O. Box 1292 Tarpon Springs, FL 34689	X	
GLOVER CONSTRUCTION COMPANY, INC. Mr. George Paul Glover P.O. Box 489 Muskogee, OK 74402		X (pending appeal)
PATTON CONSTRUCTION Mr. Alan Patton Rt. 2, Box 303 Tahlequah, OK 74464		X (Voluntary Exclusion)
SHANKS EXCAVATING COMPANY Jimmy "Dale" Shanks 204 North 4th Street P.O. Box 510 Webbers Falls, OK 74470		X (Voluntary Exclusion)
Mr. Gary Wayne Carr 318 Dog Wood Tahlequah, OK 74464		X
HORIZON CONSTRUCTION CO., INC. Mr. Max Elliot Wolf P.O. Box 690 Owasso, OK 74055	X (suspended by FHWA pending debarment)	



List of Debarred and/or Suspended Contractors for ODOT's Projects on this month's letting:

The following companies and/or individuals are not permitted to submit bids, provide services as a subcontractor, supply materials, or otherwise participate in any project let by ODOT.

Name of Company and Individual	Suspended	Debarred
YOCHAM ENTERPRISES Mr. Harlen Eugene Yocham 12350 S. Mesa Road Sapulpa, OK	X (suspended by FHWA pending debarment)	
HECKERT CONSTRUCTION COMPANY, INC. Mr. Charles Heckert Mr. Roger A. Heckert Mr. Michael Lehman Ms. Dietra Cowan 746 E. 526 th Ave. Pittsburg, KS 66762	X (suspended by FHWA pending debarment)	

BID OPENING OF – January 20, 2011 AM

Date:	Order Taken by:	
Contractor's Id No.:	No. Of Proposal(s):	
Person Ordering:	☐ Pickup ☐ COD ☐ Overnight ☐ Fed Ex #: _____ ☐ Mail	
Contractor's Name:		
Telephone No:		
Physical Address:		Please Return Completed Form to:
		Fax # 405-522-0972 or
		Email mhenry@odot.org

Specification Book Ordered:

#	County	Call No.	Project Number	JP	Sample Proposal	Bid Proposal	Plan Cost	X-sec
1	ADAIR	010	SSR-101A(073)SR	24491(04)		\$50.00	No Charge	0
2	ADAIR	020	SSR-101A(074)SR	24491(05)		\$50.00	No Charge	0
3	ADAIR	021	SSR-101A(073)SR SSR-101A(074)SR	24491(04)C 24491(05)C		\$50.00	No Charge	0
4	ATOKA	040	NHY-013N(139)3P	27449(04)		\$50.00	No Charge	0
5	BLAINE	050	BRO-106D(089)CI	24973(04)		\$50.00	9.00 + 0.75	3
6	BRYAN	060	NHY-013N(147)3P	26295(06)		\$50.00	No Charge	0
7	CANADIAN	070	STPY-109C(176)3P	28241(04)		\$50.00	No Charge	0
8	BLAINE / CANADIAN	080	STPY-109C(177)3P	28251(04)		\$50.00	No Charge	0
9	CANADIAN	090	STPY-109C(178)3P	28252(04)		\$50.00	No Charge	0
10	BLAINE / CANADIAN	091	STPY-109C(176)3P STPY-109C(177)3P STPY-109C(178)3P	28241(04)C 28251(04)C 28252(04)C		\$50.00	No Charge	0
11	CLEVELAND	110	STPG-114B(260)AG	26915(04)		\$50.00	6.00 + 0.50	0
12	CLEVELAND	120	SSR-114A(270)SR	27417(04)		\$50.00	No Charge	0
13	COMANCHE	130	NHY-020N(038)3P	24621(04)		\$50.00	No Charge	0
14	COMANCHE	140	SBR-116C(190)SB	27330(04)		\$50.00	18.00 + 1.51	0
15	CRAIG	160	BRF-118C(070)CI	23418(04)		\$50.00	15.00 + 1.26	7
16	CREEK	170	BRO-119D(044)CO	18168(04)		\$50.00	13.00 + 1.09	3
17	CREEK	180	SSR-119B(175)SR SSR-119B(210)SR	25446(04) 27629(04)		\$50.00	No Charge	0
18	CREEK	190	SBR-119C(209)SB	27625(04)		\$50.00	32.00 + 2.68	0
19	CUSTER	210	CIRB-120C(157)RB	24862(04)		\$50.00	13.00 + 1.09	5
20	DELAWARE	220	SSR-121C(144)SR SSR-121C(149)SR	27607(04) 27615(04)		\$50.00	No Charge	0
21	DELAWARE	230	SSR-121B(145)SR SSR-121B(146)SR SSR-121B(147)SR	27609(04) 27610(04) 27612(04)		\$50.00	No Charge	0
22	DELAWARE	260	STPY-121B(148)3P	27613(04)		\$50.00	No Charge	0
23	BLAINE / DEWEY	280	STPY-122C(078)3P STPY-122C(079)3P	27468(04) 27468(05)		\$50.00	No Charge	0
24	GRADY	290	SSP-126N(177)SS	27035(04)		\$50.00	24.00 + 2.01	0

BID OPENING OF – January 20, 2011 AM

Date:	Order Taken by:	
Contractor's Id No.:	No. Of Proposal(s):	
Person Ordering:	☐ Pickup ☐ COD ☐ Overnight ☐ Fed Ex #: _____ ☐ Mail	
Contractor's Name:		
Telephone No:		
Physical Address:		Please Return Completed Form to:
		Fax # 405-522-0972 or
		Email mhenry@odot.org

Specification Book Ordered:

#	County	Call No.	Project Number	JP	Sample Proposal	Bid Proposal	Plan Cost	X-sec
25	HARMON	300	NHY-020N(036)3P	27517(04)		\$50.00	No Charge	0
26	BEAVER / WOODWARD	310	SSP-104C(080)SS	24225(04)		\$50.00	9.00 + 0.75	0
27	KAY	320	NHY-018N(055)3P	11643(04)		\$50.00	No Charge	0
28	KAY	330	STPY-136A(208)3P	28246(04)		\$50.00	No Charge	0
29	KIOWA / WASHITA	342	STPY-138C(186)3P STPY-175C(128)3P	28321(04)C 28144(04)C		\$50.00	No Charge	0
30	LOGAN	350	STP-142C(176)AG	25695(04)		\$50.00	3.00 + 0.25	0
31	LOGAN	370	STPY-142C(211)3P STPY-142C(212)3P STPY-142C(213)3P	28240(04) 28245(04) 28254(04)		\$50.00	No Charge	0
32	MCCURTAIN	400	SBR-145C(169)SB	24743(05)		\$50.00	20.00 + 1.68	0
33	MCCURTAIN	410	NHY-022N(204)3P	28197(04)		\$50.00	No Charge	0
34	MURRAY	420	SBR-150N(082)SB	26331(04)		\$50.00	23.00 + 1.93	0
35	MUSKOGEE	430	SBR-151A(229)SB	27994(04)		\$50.00	55.00 + 4.61	0
36	NOBLE	440	STPY-152C(185)3P	27359(04)		\$50.00	No Charge	0
37	OKLAHOMA	450	IMY-0235-1(103)005IP	09033(40)		\$50.00	256.00 + 21.44	71
38	OKLAHOMA	470	STP-155B(480)AG	22232(04)		\$50.00	7.00 + 0.59	0
39	OKLAHOMA	480	STPG-155B(804)AG	27280(04)		\$50.00	5.00 + 0.42	0
40	OKLAHOMA	490	IMY-35-2(299)1263P	27465(04)		\$50.00	No Charge	0
41	OKLAHOMA	500	STP-155B(813)AG	28105(04)		\$50.00	No Charge	0
42	OTTAWA	510	BRFY-158B(055)	20894(04)		\$50.00	65.00 + 5.44	16
43	PAYNE	520	STPY-160B(209)3P	28235(04)		\$50.00	No Charge	0
44	PITTSBURG	530	NHY-013N(131)3P	26296(07)		\$50.00	No Charge	0
45	PONTOTOC	540	SSR-162B(220)SR	28187(04)		\$50.00	No Charge	0
46	POTTAWATOMIE	550	SSR-163C(347)SR	28190(04)		\$50.00	No Charge	0
47	POTTAWATOMIE	560	STPY-163A(355)3P	28206(04)		\$50.00	No Charge	0
48	POTTAWATOMIE	570	STPY-163B(350)3P	28209(04)		\$50.00	No Charge	0
49	POTTAWATOMIE	580	STPY-163B(351)3P	28209(05)		\$50.00	No Charge	0
50	POTTAWATOMIE	590	STPY-163B(352)3P	28209(06)		\$50.00	No Charge	0

BID OPENING OF – January 20, 2011 AM

Date:	Order Taken by:	
Contractor's Id No.:	No. Of Proposal(s):	
Person Ordering:	☐ Pickup ☐ COD ☐ Overnight ☐ Fed Ex #: _____ ☐ Mail	
Contractor's Name:		
Telephone No:		
Physical Address:		Please Return Completed Form to:
		Fax # 405-522-0972 or
		Email mhenry@odot.org

Specification Book Ordered:

#	County	Call No.	Project Number	JP	Sample Proposal	Bid Proposal	Plan Cost	X-sec
51	POTTAWATOMIE	591	STPY-163B(350)3P STPY-163B(351)3P STPY-163B(352)3P	28209(04)C 28209(05)C 28209(06)C		\$50.00	No Charge	0
52	POTTAWATOMIE	600	STPY-163C(353)3P	28210(04)		\$50.00	No Charge	0
53	CHOCTAW / PITTSBURG / PUSHMATAHA	620	BHFY-164F(164)	20920(04)		\$50.00	17.00 + 1.42	0
54	CHOCTAW / LEFLORE / PITTSBURG / PUSHMATAHA	630	BHFY-NBIP(437)	20920(05)		\$50.00	18.00 + 1.51	0
55	ROGER MILLS	642	STPY-165C(119)3P STPY-165C(120)3P	28130(04)C 28130(05)C		\$50.00	No Charge	0
56	ROGERS	650	SSR-166A(253)SR	27603(04)		\$50.00	No Charge	0
57	SEQUOYAH	670	SEC117-168E(211)SG	28108(04)		\$50.00	No Charge	0
58	SEQUOYAH	691	STPY-168A(216)3P STPY-168C(217)3P	28292(04)C 28292(05)C		\$50.00	No Charge	0
59	SEQUOYAH	700	STPY-168C(218)3P	28293(04)		\$50.00	No Charge	0
60	BEAVER / TEXAS	710	NHY-017N(234)3P	27476(04)		\$50.00	No Charge	0
61	TEXAS	720	NHY-008N(082)3P	27513(04)		\$50.00	No Charge	0
62	TULSA	730	STPY-172B(514)3P	27601(04)		\$50.00	No Charge	0
63	WAGONER	740	BRO-173D(122)CI	23600(04)		\$50.00	12.00 + 1.01	5
64	WOODS	750	STPY-176C(173)3P	27398(04)		\$50.00	No Charge	0
65	WOODWARD	760	BRF-177C(072)CI	22895(04)		\$50.00	13.00 + 1.09	2
66	WOODWARD	770	NHY-017N(240)3P	27509(04)		\$50.00	No Charge	0