### STATE OF OKLAHOMA CANADIAN COUNTY FILED OR RECORDED

SEP 0 8 2020

SA\$1 1-4040 (2000)

Canadian County, Oklahoma
COUNTY PURCHASING OFFICE
Canadian County Count House
El Rano Oklahoma
Phone: (405.) 295-5125

SHERRY MURRAY COUNTY CLERK

200586

INVITATION TO BID

PLEASE REVIEW TERMS AND CONDITIONS ON REVERSE SIDE RELATING TO SUBMISSION OF THIS BID.

Notarized Affidavit completions and signature required on reverse side

19-29-2020@900am Stork occepting bids

DATE ISSUED

**BID CLOSING DATE AND HOUR** RECURED DELIVERY DATE
SEE SPECIFICATIONS
Days after award of Purchase Order **BID NUMBER** 10-05-2020 9:00am #2021-#08 Asphalt Laid in Place / District 1 DATE OF DELIVERY SEE SPECIFICATIONS TERMS Nat, FOB this bid will open 10-05-2020 during Commissionar's Meeting that begins at 9:00am UNIT OF DESCRIPTION UNIT PRICE ITEM QUANTITY TOTAL Canadian County District 1 are seeking bids for Asphalt laid 1 or more In place. See Specifications attached. The Board of Canadian County Commissioners reserves the right to reject any and all bids or to award all or any portion of the Items bid. All data will be considered in the awarding of the bid including the delivery time. The terms & conditions of this document must be completed and returned or the bid will be rejected. Contact person(s): Justin Alkinson alkinson)@canadiancounty.org Phone: 495-262-4673 Mori-Thurs Bars-4:30pm Officer or Department Head

#### **TERMS AND CONDITIONS**

1	Sealed bids will be opened in the Commissione	er's Conference Room, <u>Canadian</u> , El Reno Oklahoma, at the time and date shown on th				
	County Courthouse, 201 N. Choclaw Avenue, invitation to bid form.	El Reno	Oklah	oma, at the	time and date she	own on the
2	Late bids will not be considered. Bids must be reand closing date written on the outside of the e		aled envelopes	s (one to an	envelope) with bid	i number
3.	Unit prices will be guaranteed correct by the bi	idder.				
4_	Firm prices will be F.O.B. destination.					
5.	Purchases by Canadian	County	, Oklahoma, a	are not subj	ect to state or fed	eral taxes.
6.	This bid is submitted as a legal offer and any b	oid when acce	pted by the C	ounty const	itutes a firm contr	act.
7:	Oklahoma laws require each bidder submittin sworn statement of non-collusion. A form is su			ods or servi	ices to furnish a	notarized
8.	Bids will be firm until 11/05/2020 (0ATE)					
am or v of s mor paid othe trac	by the bidder to submit the above bid. Affiant full one bidders in restraint of freedom of competitivith any state official or employee as to quantitial did prospective contract; or in any discussions selve or other thing of value for special considerad, given or donated or agreed to pay, give or derentity) any money or other thing of value, either the prosument to this bid.  Cribed and swom before this	on by agreen ty, quality or ( between bid ation in the let fonate to any	ent to bid at a price in the priders and any ting of a contra officer or em	a fixed price cospective of state official ract; that the oployee of the	or to refrain from contract or any ot al concerning exce bidder/contract he State of Oklai	n bidding; ther terms thange of or has not homa (or
of	20	(SEAL)				
-	, 20	Firm:				
Муо	ammission expires	Signed by:	anual Signature of	Undersigned)	Title:	
_	NOTARY PUBLIC (CLERK OR JUDGE)	Address			Phone	
	NOTARY PUBLIC (CLERK OR JOUGE)	City:			State:	
					Z p:	
Can Attn PO	ese mail sealed bids to: adian County Clerk's Office : Purchasing Box 458 leno, OK 73036				•	

NOTE. Other iterms and conditions can be added at the discretion of the county officers.

Street Address: 201 N Choctaw Avenue El Reno, OK 73036



# **Bid Specifications**

Date Issued:

September 8, 2020

Bid Number:

2021-#08

Closing Date:

October 5, 2020 at 9:00am

PO Box 458, 201 N. Choctaw Ave., El Reno, OK 73036

Opening Date: October 5, 2020 during the Commissioner's Meeting that begins at 9:00am

Commissioner's Meeting Room, 201 N. Choctaw Ave., El Reno, OK 73036

#### ~ SPECIFICATIONS~

### Asphalt Laid in Place / District 1

Canadian County District 1 is seeking bids for Asphalt laid in place.

### **Specifications:**

See attached specifications.

Bids will be received beginning at 9:00am on Tuesday, September 29, 2020 until 9:00am on Monday, October 5, 2020.

### Bids shall be accompanied by:

• A certified check, cashier's check or bid bond equal to five percent (5%) of the bid, which shall be deposited with the awarding public agency as a guaranty; or

An irrevocable letter of credit terms the Construction and Properties Division of the Office of Management and Enterprise Services prescribes, issued by a financial institution insured by the Federal Deposit Insurance Corporation or the Federal Savings and Loan Insurance Corporation for the benefit of the state, on behalf of the awarding public agency, in an amount equal to five percent (5%) of the bid. The awarding public agency shall deposit the irrevocable letter of credit with Division.

- Business Relationships Affidavit
- Non-Collusion Bidding Certification

(Please review Title 61 O.S. § 101-138 for full disclosure)

#### \*Note\*

#### **Terms for Payment:**

 A purchase order will be issued to the awarded vendor. Once the original itemized invoice is received by the receiving officer it will be processed for payment. For Information Contact:
Justin Atkinson
<a href="mailto:atkinsoni@canadiancounty.org">atkinsoni@canadiancounty.org</a>
405-262-4673
Mon-Thurs 6am-4:30pm

If you have any questions or need additional information, please contact:

Krissi Jensen, Purchasing Agent, 405.295.6125

kjensen@okcana.cogov.net

Canadian County District 1 is seeking bids for:

Less than one mile of asphalt (0.61 miles) laid in place on Richland Rd. from Northwest Highway (aka Highway 3) going north to 164th St. (aka Washington Ave.)

Less than one mile of asphalt (0.15 miles) laid in place on Cimarron Rd. from Northwest Highway (aka Highway 3) going north to 164th St. (aka Washington Ave.)

Roadway modified subgrade width: 23'

Details: 3" of asphalt is to be laid in place. District one work forces will stabilize the subgrade and prepare for paving so it will be ready for application.

#### **Asphalt Specifications:**

S4 (pg 64-22) Hot Mix hauled and In place (FOB jobsite) 3" Surface Course

Project estimated at 9,700 square yards Planned quantity of \$4 - 1,732 tons Paving width: 22'

Prime Coat application included

To pave up to the intersection of 164th St.

To include 18" aprons into driveway entrances of homes and/or businesses, field or other entrances Ali materials to comply with ODOT specifications, current edition

Vendor will be responsible for Traffic Control for the duration of the project.

Vendor will provide load tickets at completion of project

Vendor will be responsible for Striping after completion of the project.

### Striping Specifications:

4" wide traffic paint stripe down centerline only with beads applied

by the drop-on method on the centerline and edge lines

\*centerline striping will include passing lanes as designated in the ODOT specifications, current edition

BID - S4 (PG 64-22) HOT MIX:	_/TON
STRIPING /TOTAL COST:	
TOTAL PROJECT ESTIMATE:	

# **ADD ALTERNATE:**

Asphalt laid in place on Longview Drive which is approx. one mile that extends off of Richland Rd [north of Northwest Highway] and loops around to 164<sup>th</sup> St. (aka Washington Ave)

Details: 2" of asphalt laid in place. District one work forces will stabilize the subgrade and prepare for paving so it will be ready for application.

### **Asphalt Specifications:**

S4 (pg 64-22) Hot Mix hauled and in place (FOB jobsite) 2" Surface Course

Project estimated at 10,560 square yards Planned quantity of S4 – 1,220 tons Paving width: 18'

#### Prime Coat application included

To include 18" aprons into driveway entrances of homes and/or businesses, field or other entrances All materials to comply with ODOT specifications, current edition

Vendor will be responsible for Traffic Control for the duration of the project. Vendor will provide load tickets at completion of project Vendor will be responsible for Striping after completion of the project.

# **Striping Specifications:**

4" wide traffic paint stripe down centerline only with beads applied by the drop-on method on the centerline and edge lines

\*centerline striping will include passing lanes as designated in the ODOT specifications, current edition

ADD ALTERNATE BID – S4 (PG 64-22) HOT MIX:	/TON
STRIPING /TOTAL COST:	
TOTAL ADD ALTERNATE ESTIMATE:	

# ADD ALTERNATE:

Asphalt laid in place on Frisco Rd. from 164th St. (aka Washington Ave) going south for approx. .54 of a mile.

Details: 3" of asphalt laid in place. District one work forces will stabilize the subgrade and prepare for paving so it will be ready for application.

# Asphalt Specifications:

S4 (pg 64-22) Hot Mix hauled and In place (FOB jobsite) 3" Surface Course

Project estimated at 7,546.67 square yards Planned quantity of \$4 - 1,347 tons Paving width: 24'

# Prime Coat application included

To pave up to the intersection of 164th St.

To include 18" aprons into driveway entrances of homes and/or businesses, field or other entrances All materials to comply with ODOT specifications, current edition

Vendor will be responsible for Traffic Control for the duration of the project. Vendor will provide load tickets at completion of project Vendor will be responsible for Striping after completion of the project.

#### Striping Specifications:

4" wide traffic paint stripe down centerline only with beads applied by the drop-on method on the centerline and edge lines

\*centerline striping will include passing lanes as designated in the ODOT specifications, current edition

ADD ALTERNATE BID - S4 (PG 64-22) HOT MIX:	)N
STRIPING /TOTAL COST:	
TOTAL ADD ALTERNATE ESTIMATE:	

Pre-bid Construction Meeting to be held at the north end of the project site on <u>Thursday</u>, <u>September 17, 2020 at 9:00 a.m.</u>

Awarded vendor will be presented a written contract within two weeks from the award date for signature and final approval by the Board of County Commissioners. Awarded vendor must coordinate with the county to ensure that asphalt is laid within two weeks of the base being applied, and must have the project completed no later than November 25, 2020.

Title 61 O.S. 101-138