








Pre-Delivery Inspection Marking Details

Revision: **11/2024**

Inspection Mark	Material Marked	Mark Description	Inspected By
	<ul style="list-style-type: none"> • Reinforced Concrete Pipe/Box (RCP/RCB) • RCP End Sections • Precast Concrete Structures • Large Sign Posts 	Ink Stamp (typically black)	Oklahoma DOT Materials Division (Structural Materials Branch)
	<ul style="list-style-type: none"> • Overhead Sign Structures (Aluminum Truss) 	Steel Die Stamp (leaves imprint in metal)	Oklahoma DOT Materials Division (Structural Materials Branch)
	<ul style="list-style-type: none"> • Prestressed Concrete Bridge Members • Some Elastomeric Bearing Pads • Precast Concrete Walls • Precast Bridge Structures 	Stencil	Clifton Ashford and Associates, LLC
	<ul style="list-style-type: none"> • Prestressed Concrete Bridge Members subject to acceptance under Section 105.03 of Std. Specs. 		
	<ul style="list-style-type: none"> • Steel Bridge Members • Some Elastomeric Bearing Pads • Ancillary Fabricated Steel Materials • Steel Monotube Sign Structures 	Ink Stamp	The Inspection Group
	<ul style="list-style-type: none"> • Structural Steel Fabricated Items; Main Members like bridge beams and girders 	Low Stress steel die impression stamp with rounded corners	The Inspection Group
	<ul style="list-style-type: none"> • Wood Posts • Timber Piles • Timber Ties • Lumber 	Hammer Brand (10) is inspector number and varies	Lee Inspection and Consulting Service, Inc.